

FORM BF-1

State of Michigan
Department of Military and Veterans Affairs
Construction & Facilities Office
Reserve Forces Service Center
3423 N. Martin Luther King Blvd. Rm. 321
Lansing, Michigan 48906-2934

DATE ISSUED: August 17, 2023
INDEX CODE NO: 1540
Project: 26A7722012
State Unit: Dept. of Military Affairs
SUBJECT: Renovate Armory -
Olympia Detroit, MI
BID OPENING: August 23, 2023, 2:00PM

ADDENDUM NO. 1

TO: All Bidders

1. Clarification: See re-issued sheet C0.1 for fence removal.
2. Clarification: See re-issued C1.1 for gate sizes- See new issued sheet C1.9 for gate details.
3. Clarification: The fence that is being removed is inside of the new fence. If the new fence is in place and the perimeter is secure then no temporary fencing will be needed. If temporary fencing is used to secure the perimeter, then it needs to be bolted together. Gate opening can be fencing panels but will have to be chained and locked in a daisy chain fashion.
4. Clarification: Concrete Curbs- Parking lot PKLT 1 requires this next to the new sidewalk only. Symbols have been added to sheet C1.1 and re-issued.
5. Clarification: The specification calls out using W beam guard rails, but this project does not require any of these.
6. Clarification: Fire protection specifications section 210000 have been issued as part of this addendum.
7. Clarification: Metal Locker specifications section 105113 have been issued as part of this addendum. This section also includes the benches that are in front of the lockers. Only lockers that are being installed are in the womens drying area, room #129C. Other lockers are being reused/relocated.
8. Clarification: See revise sheet A1.0 for wall types. We are removing 2 vault doors and using wall type 2 to close them up.
9. Clarification: A new vault addition is being added to vault 120B and it butts up to the existing vault 118A. Sheet A3.3 vault section A shows what vault 120B will look like, on the right side of the drawing it shows how to connect to vault 118A.
10. Change: Install 24" x 18" louvers in doors 129C and 130C. Install 24"x12" louvers in doors 129B and 130B

11. Change: Refer to sheet E3: REPLACE the Type K lighting fixtures with one (1) Type K4 (DRYING room 129C) and one (1) Type K12 for each WOMENS 129 & MENS 130 as follows:
- a. Drying Room 129C utilize lighting fixture Type K4 manufactured by LightControl/Current model # 3L-W-IAD-LPAD-4-04-ASYM-C3-30K9-I030-D050-D01-1C-UNV-L1.
 - b. Women's Restroom 129 and Men's Restroom 130 each with one K12 fixture manufactured by LightControl/Current model #3L-W-IAD-LPAD-12-06-ASYM-C3-30K9-I030-D050-D01-1C-UNV-L1.

NEW ISSUED DRAWINGS:

C1.9

RE-ISSUED DRAWINGS

C0.1

C1.1

A1.0

NEW ISSUED SPECIFICATIONS SECTIONS

105113 Metal Lockers

210000 Fire Suppression

ACKNOWLEDGEMENT: Two copies of this Addendum, properly signed in the space provided below, shall be returned with the Bidder's proposal.

FIRM NAME

BIDDER'S SIGNATURE



Scott Domanski
Project Manager
Construction & Facilities
Management Office