DTMB-0414 (Rev 12/17)

DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET
State Facilities Administration
Design and Construction Division

CONSTRUCTION BID ADDENDUM NO. 2

This form identifies an Addendum to Bidding Documents, and incorporates interpretations or clarifications, modifications, acceptance of proposed "or equal" materials, and other information into the Bidding Documents. Addenda will be numbered by the Professional and distributed through www.michigan.gov/SIGMAVSS as an attachment.

TO:		DATE ISSUED
ALL BIDDERS		11/9/2026
PROJECT NAME Bay City State Park Campground Improvements		FILE NUMBER 751/22413.CTS
PROFESSIONAL Beckett & Raeder, Inc.	PROJECT DIRECTOR Chris Schanbeck, PE	BID OPENING DATE: 11/18/2026

ADDENDUM ITEMS:

Bidder Questions and PSC Responses:

1. Q: Hydrants - Only two new hydrants are clearly shown on C3.1. Where is the third hydrant located?

   A: See sheet C3.2, on the left side of the sheet there is another new hydrant approximately 80' north of the northeast corner of the east bathroom building.

2. Q: Road crossings - At the campground road crossings, may the electrical duct and water service be directionally bored, or is open cut with concrete-encased PVC required? If both are allowed, which does the owner prefer?

   A: The electrical and water service shall be installed by directional boring with open excavations limited to the greatest extent possible to limit damage to existing pavements, roadway or trees. This is the owner's preferred installation method.

3. Q: Restoration - Who is responsible for restoring the turf, asphalt and concrete disturbed by the electrical and boring work? Is the general contractor responsible for all restoration, or does each trade restore its own disturbance?

   A: There should be one landscape contractor, one asphalt contractor, and one concrete contractor to restore all disturbances.

4. Q: Panels and breakers - Given the long lead times on panels and breakers and the July 4 completion, will the owner allow an extension or a phased completion if the gear can't be delivered in time?

   A: No, the Owner will not allow an extension or phased completion. The Contractor should include in their bid any added cost premium necessary for the distribution equipment to be delivered to the project site for completion of the project per the schedule indicated in the bid documents.

ACKNOWLEDGEMENT: This Addendum must be acknowledged by the Bidder in the space provided in the Bid Summary and Bid Form. Failing to acknowledge Addenda may be cause for the Bid to be rejected. Addenda will become part of the Contract Documents.

PROFESSIONAL: Kristofer Enlow, P.E., Beckett & Raeder, Inc.	DATE: 11/9/2026
APPROVED BY: PROJECT DIRECTOR:	DATE: 11/9/2026