
491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN



CONTACTS:

ARCHITECT:



WTA ARCHITECTS 100 S. JEFFERSON AVENUE, SUITE 601 SAGINAW, MICHIGAN 48607 PHONE: (989) 752-8107 EMAIL: DESIGN@WTAARCH.COM

STRUCTURAL ENGINEER:



MACMILLAN ASSOCIATES, INC. 714 E. MIDLAND STREET BAY CITY, MICHIGAN 48706 PHONE: (989) 894-4300 FAX: (989) 864-9930

MECHANICAL & ELECTRICAL ENGINEER:



PETER BASSO ASSOCIATES, INC. CONSULTING ENGINEERS 5145 LIVERNOIS ROAD, SUITE 100 TROY, MICHIGAN 48098 PHONE: (248) 879-5666 FAX: (248) 879-0007

CIVIL ENGINEER:



ROWE PROFESSIONAL SERVICES COMPANY 127 S. MAIN STREET MT. PLEASANT, MICHIGAN 48858 FAX: (989) 773-7757

FOOD SERVICE:



STAFFORD SMITH, INC. 3414 SOUTH BURDICK STREET KALAMAZOO, MICHIGAN 49001 PHONE: (800) 962-2442 PHONE: (269) 343-1240

COMMUNICATIONS & IT:



COMMTECH DESIGN 6581 BELDING RD NE SUITE. #101 ROCKFORD, MICHIGAN 49341 PHONE: (616) 446-4545

INDEX OF DRAWINGS:

CIVIL DRAWINGS CIVIL LEGEND CIVIL NOTES CIVIL DETAILS FENCE DETAILS



UTILITY PLAN

GRADING PLAN

ARCHITECTURAL DRAWINGS

A0.01 PROJECT INFORMATION

FIRST FLOOR MASTER CODE PLAN FIRST FLOOR PARTIAL CODE PLAN

FIRST FLOOR DEMOLITION PLAN

FIRST FLOOR CONSTRUCTION PLAN SECOND FLOOR CONST. PLN, ENLARGED PLN, & INTERIOR ELEVATION

FIRST & SECOND FLOOR FLOORING PLANS

PLAN DETAILS

ROOM FINISH & DOOR SCHEDS, DOOR & WDW TYPES, AND DOOR DTLS

VERTICAL CIRCULATION

EXTERIOR ELEVATIONS

BUILDING SECTIONS

ROOF PLAN

WALL SECTIONS & DETAILS A7.02 WALL SECTIONS & DETAILS

FIRST & SECOND FLOOR REFLECTED CEILING PLAN

FOOD SERVICE DRAWINGS

FS2.01 KITCHEN EQUIPMENT PLAN FS2.02 KITCHEN ELECTRICAL PLAN FS2.03 KITCHEN PLUMBING PLAN FS2.04 KITCHEN VENTILATION PLAN

STRUCTURAL DRAWINGS

FOUNDATION PLAN ROOF FRAMING PLAN

ROOF FRAMING DETAILS

MECHANICAL STANDARDS AND DRAWING

UNDERGROUND PLUMBING PLAN FIRST FLOOR PLUMBING AND FIRE

PROTECTION PLAN - UNIT J

M3.01 FIRST FLOOR HVAC PIPING PLAN - UNIT H

M3.03 PENTHOUSE HVAC PIPING PLAN

PLUMBING ENLARGED PLAN

M6.02 MECHANICAL DETAILS

M6.03 MECHANICAL DETAILS M6.04 MECHANICAL DETAILS

M7.01 MECHANICAL SCHEDULES M7.02 MECHANICAL SCHEDULES

M7.03 MECHANICAL SCHEDULES M7.04 MECHANICAL SCHEDULES

MECHANICAL

These documents are approved

TATE OF MICHIGAN MECHANICAL CODE

subject to field inspection and the

conditions of approval.

FS2.05 SPECIAL CONDTIONS PLAN

NOTES AND SCHEDULES

FOUNDATION DETAILS

MECHANICAL DRAWINGS

FIRE PROTECTION ZONING PLAN

PROTECTION PLAN - UNIT H

M2.02 FIRST FLOOR PLUMBING AND FIRE

M2.03 PENTHOUSE PLUMBING PLAN

FIRST FLOOR SHEET METAL PLAN - UNIT H

M4.03 PENTHOUSE SHEET METAL PLAN

MECHANICAL ROOF PLAN

MECHANICAL DETAILS

DENNIS P. SCZOMAK

ENGINEER

Structural

MAI #2021-1530

JEREMIAH

NO. 52415

M8.01 TEMPERATURE CONTROL STANDARDS AND **GENERAL NOTES**

TEMPERATURE CONTROLS

TEMPERATURE CONTROLS TEMPERATURE CONTROLS

ELECTRICAL DRAWINGS

ELECTRICAL STANDARDS AND DRAWING

ELECTRICAL STANDARD SCHEDULES

ELECTRICAL DEMOLITION SITE PLAN

ELECTRICAL NEW WORK SITE PLAN

FIRST FLOOR ELECTRICAL DEMOLITION PLAN

FIRST FLOOR LIGHTING PLAN - UNIT H

BASEMENT FLOOR POWER PLAN - UNIT H

FIRST FLOOR POWER PLAN - UNIT H

FIRST FLOOR AUXILIARY SYSTEMS PLAN - UNIT

E4.04 ELECTRICAL ROOF PLAN

ONE LINE DIAGRAM - NEW WORK

PANEL SCHEDULES

ELECTRICAL ENLARGED PLAN

ELECTRICAL DETAILS AND DIAGRAMS

ELECTRICAL ENLARGED PLAN

ELECTRICAL DETAILS AND DIAGRAMS

COMMUNICATIONS & IT DRAWINGS

TC1.01 CABLING LEGENDS, SCHEDULES & DETAILS TC1.02 CABLING CONNECTIVITY CODES

TC1.03 CABLING RACK LAYOUTS & DETAILS TC1.04 FENCE DETECTION DETAILS

TC1.05 ACCESS CONTROL DEVICES

TC1.06 SECURITY ACCESS CONTROL DETAILS TC1.07 VIDEO SECURITY SYSTEM DETAILS


TC2.00 TECHNOLOGY SITE PLAN

TC2.01 FIRST FLOOR TECHNOLOGY PLAN

TC2.01A BASEMENT TECHNOLOGY PLAN AREA 100



REVISION



CONTRACT NO.

COPYRIGHT © 2023

Y22003


491/20167.SDW

ENGINEER

6201061469

FUNDING CODE 171CODHHS7255







100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607

491/20167.SDW - PHASE 500: CENTER FOR FORENSIC PSYCHIATRY - CREATE

KITCHEN SALINE, MICHIGAN

PROJECT TITLE

SHEET TITLE TITLE SHEET

2021094 PROJECT DATE SEPTEMBER 6, 2023

CHECKED BY C.D.S.

SHEET NUMBER

STRUCTURE SYMBOLS

- EXISTING CATCH BASIN IN CURB LINE
- PROPOSED CATCH BASIN IN CURB LINE
- EXISTING CATCH BASIN IN GREEN SPACE
- PROPOSED CATCH BASIN IN GREEN SPACE
- EXISTING STORM MANHOLE
- PROPOSED STORM MANHOLE
- PROPOSED CULVERT END SECTION
- EXISTING HEADWALL
- PROPOSED HEADWALL
- EXISTING GATE VALVE AND BOX
- EXISTING WATER SHUT OFF (CURB BOX)
- PROPOSED GATE VALVE AND BOX
- EXISTING GATE VALVE AND WELL
- PROPOSED GATE VALVE AND WELL
- EXISTING SPRINKLER HEAD
- EXISTING WATER WELL
- EXISTING FIRE HYDRANT
- PROPOSED FIRE HYDRANT
- PROPOSED WATER MAIN FITTINGS
- EXISTING CLEAN OUT
- EXISTING SANITARY SEWER MANHOLE
- PROPOSED SANITARY SEWER MANHOLE
- EXISTING MONITORING WELL

EXISTING TOPOGRAPHICAL SYMBOLS

- SIGN
- STREET SIGN
- END OF PIPE
- SWAMP OR WETLAND
- DECIDUOUS TREE
- CONIFEROUS TREE
- TREE STUMP
- MAIL BOX
- SOIL BORING
- ROCK
- METAL POST
- BUMPER BLOCK

UTILITY SYMBOLS

GUY ANCHOR CABLE

UTILITY POLE

- LIGHT POLE / ORNAMENTAL LIGHT
- POWER LIGHT POLE
- TELEPHONE MANHOLE
- UNDERGROUND GAS LINE MARKER
- GAS RISER
- GAS VENT
- GAS VALVE
- RAILROAD SIGNAL
- METAL LIGHT POLE
- OUTLET
- CIRCUIT BREAKER PANEL
- ELECTRICAL TRANSFORMER PAD
- ELECTRICAL TRANSFORMER RISER
- ELECTRIC METER
- TELEPHONE PEDESTAL / RISER
- TRAFFIC SIGNAL ON POLE
- PHONE BOOTH / PAY PHONE

SURVEY SYMBOLS

- MONUMENT
- BENCHMARK
- TRAVERSE POINT
- SECTION CORNER
- FOUND SURVEY MONUMENTATION

MISCELLANEOUS SYMBOLS

- EXISTING STORM SEWER STRUCTURE NUMBER
- EX 5236 EXISTING SANITARY SEWER STRUCTURE NUMBER
- PROPOSED STORM SEWER STRUCTURE NUMBER
- A PROPOSED SANITARY SEWER STRUCTURE NUMBER
- FLOW DIRECTION **~~**



EXISTING RIP-RAP



PROPOSED RIP-RAP

••CAUTION•• HAZARDOUS FLAMMABLE MATERIAL UNDERGROUND

USED WITH UNDERGROUND GAS & ELECTRICAL LINES



USED WITH FIBER OPTICS LINES

CAUTION SYMBOLS

<u>PLAN VIEW</u>	LINE TYPES
12" STM	EXISTING STORM SEWER
======================================	EXISTING CULVERT
	PROPOSED STORM SEWER LESS THAN 24"
	PROPOSED STORM SEWER 24" AND GREATER
12" SAN	EXISTING SANITARY SEWER
	PROPOSED SANITARY SEWER
	EXISTING WATER MAIN
	PROPOSED WATER MAIN
	SECTION LINE
60' ROW	EXISTING RIGHT OF WAY
60' ROW	PROPOSED RIGHT OF WAY
	PROPOSED EASEMENT
·	EXISTING CENTER LINE DITCH
	PROPOSED DITCH CENTERLINE
	EXISTING CENTER LINE ROADWAY

PARCEL LINE / LOT LINE EXISTING OVERHEAD UTILITIES

PROJECT CONTROL LINE TREE LINE

BRUSH LINE --×----×---×---×---×----×----- EXISTING FENCE

EXISTING GUARD RAIL

PROPOSED SLOPE STAKE LINE PROPOSED SILT FENCE

TOPOGRAPHY

PARCEL INFORMATION



EXISTING CONTOURS MAJOR EXISTING CONTOURS MINOR



PROPOSED CONTOUR MAJOR

401-069 #5324

PARCEL/TAX IDENTIFICATION NUMBER ADDRESS/BUSINESS NAME

PROPOSED CONTOURS MINOR


PAVEMENT IDENTIFICATION

EXISTING CURB AND GUTTER


HATCHING LEGEND



REMOVE PAVEMENT



REMOVE SIDEWALK



PROPOSED CONCRETE PAVEMENT

PROPOSED CONCRETE SIDEWALK



SAND BACKFILL (PROFILE)

PROPOSED HMA PAVEMENT



PROPOSED CALLOUTS

TOPO CALLOUTS	<u>PLAN VIEW</u>
ADJ	ADJ
ADJ-X	(ADJ-X)
ADJ-B/O	(ADJ-B/O)
REC	REC

ADJUST STRUCTURE W/ NEW COVER ADJUST STRUCTURE BY OTHERS

ADJUST STRUCTURE

RECONSTRUCT STRUCTURE

REMOVE AND REPLACE

SOIL EROSION CONTROL MEASURE

REL-B/O

REM

REL RELOCATE RELOCATE BY OTHERS R REMOVE


SALV SAVE

SALV SALVAGE SAVE

ABANDON CLEARING

BULKHEAD

SIDEWALK RAMP TYPE



DATE REVISION STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET

REPORT OF THE PROPERTY OF ADMINISTRATION FACILITIES AND BUSINESS SERVICE ADMINISTRATION

DESIGN AND CONSTRUCTION DIVISION


CONTRACT NO.

COPYRIGHT © 2023

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255

ADAM LACH, DIRECTOR





100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107



491/20167.SDW CFP - PHASE 500 CENTER FOR FORENSIC

PSYCHIATRY - CREATE


KITCHEN SALINE, MICHIGAN SHEET TITLE

PROJECT NUMBER 2021094

CIVIL LEGEND

PROJECT DATE | SEPTEMBER 6, 2023 | (CHECKED BY A.J.T.

SHEET NUMBER



GENERAL CONSTRUCTION NOTES

EMERGENCY CONTACTS

BEFORE BEGINNING WORK ON THE PROJECT, THE CONTRACTOR SHALL PROVIDE THE OWNER AND ENGINEER WITH THE NAMES AND TELEPHONE NUMBERS OF EMERGENCY CONTACTS. AT LEAST ONE PERSON REPRESENTING THE CONTRACTOR SHALL BE AVAILABLE TO RESPOND TO EMERGENCIES THROUGHOUT THE LIFE OF THE PROJECT, 24 HOURS A DAY, 7 DAYS A WEEK.

UNDERGROUND UTILITY IDENTIFICATION AND LOCATION

CONTRACTOR TO COMPLETE GROUND PENETRATING RADAR WITHIN CONSTRUCTION LIMITS TO DETERMINE THE EXACT LOCATION OF UNDERGROUND UTILITIES PRIOR TO BEGINNING EXCAVATION.

PUBLIC UTILITIES

EXISTING UTILITIES ARE SHOWN BASED UPON RECORDS AND LOCATIONS PROVIDED BY UTILITY AGENCIES. THE INFORMATION SHOWN IS CONSIDERED APPROXIMATE AND SHALL BE VERIFIED BY THE CONTRACTOR. UNLESS THE PLANS SPECIFICALLY SHOW THAT EXISTING UTILITIES ARE TO BE MOVED, THE CONTRACTOR IS RESPONSIBLE TO PROTECT AND MAINTAIN EXISTING UTILITIES.

VERIFICATION OF UNDERGROUND UTILITIES

THE CONTRACTOR SHALL EXCAVATE AND LOCATE ALL EXISTING UTILITIES IN THE PROJECT AREA IN ADVANCE OF CONSTRUCTION TO VERIFY THEIR ACTUAL LOCATION. POTENTIAL CONFLICTS SHALL BE REPORTED TO THE ENGINEER. THE CONTRACTOR SHALL MAKE SUCH CHANGES TO GRADE AND ALIGNMENT OF PROPOSED WORK AS DIRECTED BY THE ENGINEER TO AVOID CONFLICTS, AT NO INCREASE IN COST TO THE OWNER.

UTILITY SERVICE

UNLESS SPECIFICALLY PROVIDED OTHERWISE IN THE CONTRACT DOCUMENTS, ALL EXISTING UTILITIES ARE TO REMAIN IN SERVICE DURING THE PROJECT.

PRIVATE IRRIGATION SYSTEMS

THE CONTRACTOR SHALL COORDINATE WITH THE FACILITY TO DETERMINE THE LOCATION OF THE IRRIGATION SYSTEM PRIOR TO THE START OF CONSTRUCTION. THE SYSTEM IS TO BE REVISED TO ACCOMMODATE PROPOSED SITE WORK.

SOIL BORINGS / PAVEMENT CORES

IF PROVIDED ON THE PLANS OR IN THE CONTRACT DOCUMENTS, LOGS OF SOIL BORINGS OR PAVEMENT CORES REPRESENT THE SUBSURFACE CONDITIONS ENCOUNTERED AT SPECIFIC POINTS. THE INFORMATION IS PROVIDED FOR THE CONTRACTOR'S INFORMATION ONLY.

LOCAL AND EMERGENCY TRAFFIC SHALL BE MAINTAINED AT ALL TIMES WITHIN THE PROJECT AREA.

WHEN EXCAVATION, FRESH CONCRETE, OR OTHER CONSTRUCTION WORK WILL RESULT IN THE CLOSURE OF A STREET OR DRIVEWAY FOR A PERIOD OF TIME, THE CONTRACTOR IS RESPONSIBLE TO NOTIFY ALL AFFECTED RESIDENTS AND BUSINESSES IN ADVANCE.

THE CONTRACTOR SHALL NOTIFY EMERGENCY RESPONSE AGENCIES IN ADVANCE OF ROAD CLOSURES OR THE ESTABLISHMENT OF DETOURS.

SCHEDULE

THE CONTRACTOR SHALL COMPLETE ALL WORK IN AN EXPEDITIOUS MANNER AND SHALL NOT STOP WORK ON THE PROJECT ONCE BEGUN.

ALIGNMENT

ALIGNMENT AND GRADES FOR CURB AND GUTTER (INCLUDING THROUGH RAMPS AND DRIVEWAY OPENINGS) SHOWN ON THE PLANS ARE FOR THE TOP, BACK OF CURB, UNLESS SPECIFICALLY SHOWN OTHERWISE ON

THE HORIZONTAL ALIGNMENT SHOWN ON THE DRAWINGS FOR DRAINAGE STRUCTURES LOCATED IN THE CURB LINE IS TO THE CENTER OF THE CASTING.

THE HORIZONTAL ALIGNMENT SHOWN ON THE DRAWINGS FOR DRAINAGE STRUCTURES WHICH ARE NOT IN THE CURB LINE AND FOR MANHOLES IS TO THE CENTER OF THE STRUCTURE.

WHERE RIM ELEVATIONS ARE PROVIDED ON THE PLANS FOR MANHOLE CASTINGS, THE ELEVATION PROVIDED IS FOR THE TOP OF THE CASTING.

WHERE RIM ELEVATIONS ARE PROVIDED FOR INLET TYPE CASTINGS, THE ELEVATIONS ARE PROVIDED AS FOLLOWS:

 CURB INLETS – THE ELEVATION OF THE TOP OF CURB ALL OTHER INLETS — THE ELEVATION OF THE FLOW LINE

WHERE RIM ELEVATIONS ARE PROVIDED ON THE PLANS FOR INLETS OR MANHOLE CASTINGS, THE ELEVATIONS PROVIDED ARE CONSIDERED PRELIMINARY. THE CONTRACTOR SHALL MAKE THE FINAL ADJUSTMENT FOLLOWING THE ESTABLISHMENT OF ACTUAL GRADING AND PAVEMENT ELEVATIONS.

CONSTRUCTION STAKING

WHEN CONSTRUCTION STAKING IS TO BE PROVIDED BY THE ENGINEER OR OWNER, THE CONTRACTOR SHALL REQUEST STAKING AT LEAST THREE WORKING DAYS IN ADVANCE.

WHEN CONSTRUCTION STAKING IS TO BE PROVIDED BY THE ENGINEER OR OWNER, STAKING WILL BE PROVIDED ONE TIME. THE CONTRACTOR SHALL PROTECT AND PRESERVE SURVEY CONTROL AND STAKING. RE-STAKING WILL BE AT THE CONTRACTOR'S EXPENSE.

SURVEY CORNERS, BENCHMARKS, AND CONTROL POINTS

THE CONTRACTOR SHALL PRESERVE ALL GOVERNMENT CORNERS. PROPERTY CORNERS. BENCHMARKS. SURVEY CONTROL POINTS AND OTHER SURVEY POINTS WITHIN THE PROJECT AREA. WHERE CORNERS. BENCHMARKS. OR SURVEY POINTS ARE ENCOUNTERED WHICH WILL BE DISTURBED BY THE CONTRACTOR'S ACTIVITIES: A LICENSED SURVEYOR SHALL WITNESS THE POINT BEFORE DISTURBANCE AND SHALL RE-SET THE POINT FOLLOWING THE COMPLETION OF CONSTRUCTION ACTIVITIES. THE CONTRACTOR SHALL PAY THE SURVEYOR TO WITNESS AND TO RE-SET THE POINTS.

PROTECTION OF TREES, SHRUBS, AND LANDSCAPING

SHRUBS, AND LANDSCAPING SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.

ALL TREES, SHRUBS, AND LANDSCAPING WITHIN THE CONSTRUCTION AREA WHICH ARE NOT SPECIFICALLY DESIGNATED FOR REMOVAL SHALL BE PROTECTED FROM DAMAGE BY THE CONTRACTOR. DAMAGED TREES. CONSTRUCTION SIGNING AND BARRICADING

THE CONTRACTOR SHALL PROTECT HAZARDOUS AREAS WITH BARRICADES. BARRICADES LEFT IN PLACE AFTER SUNSET SHALL BE LIGHTED.

THE CONTRACTOR SHALL PROVIDE SUITABLE SANDBAGS OR OTHER SUITABLE MEASURES FOR ANCHORING OF TEMPORARY SIGNS AND BARRICADES, TO PREVENT THEIR TIPPING OR DISPLACEMENT BY WIND OR AIR FLOW FROM VEHICLES.

THE CONTRACTOR SHALL PROVIDE SIGNING, BARRICADES, TRAFFIC REGULATORS, CONES, AND OTHER TRAFFIC CONTROL DEVICES IN ACCORDANCE WITH THE REQUIREMENTS OF THE AGENCY HAVING JURISDICTION OVER STREETS OR ROADS IN THE PROJECT AREA, THE CURRENT MICHIGAN MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES, AND THE PLANS AND SPECIFICATIONS.

THE CONTRACTOR SHALL COVER OR REMOVE TEMPORARY SIGNS DURING PERIODS WHEN THEY ARE NOT APPROPRIATE.

TURF ESTABLISHMENT

ALL DISTURBED AREAS WHICH ARE NOT TO BE SURFACED WITH PAVEMENT, AGGREGATE OR OTHER APPROVED SURFACES SHALL BE ESTABLISHED WITH TURF.

TURF AREAS SHALL BE GRADED TO PROVIDE POSITIVE DRAINAGE.

DISTURBED AREAS SHALL BE SURFACED WITH FOUR INCHES OF SCREENED TOPSOIL.

THE CONTRACTOR IS RESPONSIBLE TO ESTABLISH TURF WHICH IS SUBSTANTIALLY FREE OF BARE SPOTS AND FREE OF WEEDS. THE GROUND SURFACE IN TURF AREAS SHALL BE SMOOTH AND PROVIDE A NATURAL TRANSITION TO ADJACENT, UNDISTURBED AREAS.

THE CONTRACTOR IS RESPONSIBLE TO PROVIDE WATERING, WEEDING, RESEEDING, AND REWORKING AS NECESSARY TO ESTABLISH TURF AREAS TO THE REQUIRED STANDARD.

ADA COMPLIANCE

ALL PROPOSED CONSTRUCTION SHALL COMPLY WITH THE PROVISIONS OF THE AMERICANS WITH DISABILITIES ACT (ADA), AND APPLICABLE GUIDELINES OR STANDARDS. WHERE EXISTING CONDITIONS AND/OR THE REQUIREMENTS OF THE PLANS WILL RESULT IN FINISHED CONDITIONS THAT DO NOT MEET THE ADA REQUIREMENTS, GUIDELINES, OR STANDARDS; THE CONTRACTOR SHALL NOTIFY THE ENGINEER BEFORE PROCEEDING WITH CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE TO REMOVE AND REPLACE WORK DETERMINED TO BE NOT IN ACCORDANCE WITH APPLICABLE REQUIREMENTS, GUIDELINES, OR STANDARDS.

THE CONTRACTOR SHALL MAKE HIS OWN DETERMINATION OF THE EARTHWORK QUANTITIES, AND BASE HIS BID ON HIS DETERMINATION OF THE QUANTITIES OF WORK REQUIRED.

IF ADDITIONAL FILL MATERIAL MUST BE PROVIDED TO ATTAIN THE FINISH GRADES SHOWN ON THE PLANS, THE CONTRACTOR SHALL PROVIDE THE REQUIRED FILL MATERIAL, UNLESS A SPECIFIC BORROW AREA IS IDENTIFIED ON THE PLANS.

EXCESS SOILS RESULTING FROM EXCAVATION AND EARTHWORK SHALL BECOME THE CONTRACTOR'S PROPERTY AND DISPOSED OF PROPERLY, UNLESS AN AREA(S) HAS BEEN DESIGNATED FOR STOCKPILING OR "BLENDING IN" THE EXCESS MATERIAL WITHIN THE PROJECT LIMITS.

BACKFILL AND EMBANKMENT

BACKFILL OF AN EXCAVATION UNDER OR WITHIN THE ONE ON ONE INFLUENCE OF AN EXISTING OR PROPOSED ROAD, SIDEWALK, DRIVEWAY, PAVEMENT, OR AGGREGATE SURFACE, SHALL BE SAND, MEETING THE REQUIREMENTS OF GRANULAR MATERIAL CLASS III AS DESCRIBED IN THE CURRENT MICHIGAN DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION. THE SAND BACKFILL SHALL BE COMPACTED TO AT LEAST 95% OF ITS MAXIMUM UNIT WEIGHT.

BACKFILL OF AN EXCAVATION WHICH IS NOT UNDER OR WITHIN THE ONE ON ONE INFLUENCE OF AN EXISTING OR PROPOSED ROAD, SIDEWALK, DRIVEWAY, PAVEMENT, OR AGGREGATE SURFACE MAY BE SUITABLE EXCAVATED MATERIAL OR OTHER SOIL, WHICH IS FREE OF ORGANIC MATTER, STONES AND ROCKS, ROOTS, BROKEN CONCRETE, FROZEN MATERIAL, OR DEBRIS. THE BACKFILL SHALL BE COMPACTED TO AT LEAST 90% OF ITS MAXIMUM UNIT WEIGHT.

THE CONTRACTOR SHALL INDICATE THE SOURCE OF SAND USED FOR BACKFILL TO THE ENGINEER, AND PROVIDE THE ENGINEER WITH THE RESULTS OF A GRADATION TEST PERFORMED ON A SAMPLE OF THE SAND. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IN ADVANCE OF USING SAND FROM OTHER SOURCES.

EMBANKMENT USED TO BUILD THE SUBGRADE TO REQUIRED ELEVATION SHALL BE SUITABLE SOIL EXCAVATED FROM THE PROJECT SITE, OR FURNISHED BY THE CONTRACTOR FROM OTHER SOURCES. SUITABLE SOIL IS FREE FROM ORGANIC MATTER, ROCKS AND STONES, FROZEN MATERIAL, BROKEN CONCRETE, AND DEBRIS.

EMBANKMENT CONSTRUCTED OF GRANULAR SOILS SHALL BE COMPACTED IN LIFTS NOT EXCEEDING 10 INCHES

TO AT LEAST 95% OF ITS MAXIMUM UNIT WEIGHT. EMBANKMENT CONSTRUCTED OF COHESIVE SOILS SHALL BE COMPACTED IN LIFTS NOT EXCEEDING 10 INCHES TO AT LEAST 95% OF ITS MAXIMUM UNIT WEIGHT.

THE MAXIMUM UNIT WEIGHT OF SAND AND OTHER GRANULAR SOILS WILL BE DETERMINED BY THE ONE POINT CONE TEST, AS DESCRIBED IN THE MICHIGAN DEPARTMENT OF TRANSPORTATION'S DENSITY TESTING AND INSPECTION MANUAL, EXCEPT WHEN ANOTHER TEST METHOD IS SPECIFIED.

THE MAXIMUM UNIT WEIGHT OF COHESIVE SOILS WILL BE DETERMINED BY THE ONE POINT PROCTOR TEST, AS DESCRIBED IN THE MICHIGAN DEPARTMENT OF TRANSPORTATION'S DENSITY TESTING AND INSPECTION MANUAL, EXCEPT WHEN ANOTHER TEST METHOD IS SPECIFIED.

DRAINAGE

THE CONTRACTOR SHALL MAINTAIN DRAINAGE OF THE PROJECT AREA AND ADJACENT AREAS. WHERE EXISTING DRAINAGE FACILITIES ARE DISTURBED OR BLOCKED BY CONSTRUCTION, THE CONTRACTOR SHALL PROVIDE AND MAINTAIN TEMPORARY PROVISIONS FOR DRAINAGE.

WHERE CONSTRUCTION HAS DISTURBED EXISTING DITCHES. SWALES. OR OTHER DRAINAGE FACILITIES: THE CONTRACTOR SHALL RESTORE THEM TO THEIR GRADES AND DIMENSIONS WHICH EXISTED PRIOR TO THE BEGINNING OF CONSTRUCTION, UNLESS DIRECTED OTHERWISE.

DRAINAGE SHALL NOT BE REROUTED ONTO ADJACENT PROPERTIES NOR ALLOWED TO DRAIN ONTO ADJACENT PROPERTIES AT AN INCREASED RATE, AS A RESULT OF THE CONTRACTOR'S WORK.

SIDEWALK CONSTRUCTION

SIDEWALKS SHALL BE CONSTRUCTED TO PROVIDE POSITIVE DRAINAGE OF THE SIDEWALK AND ADJACENT

EXCEPT WHERE NECESSARY TO PROVIDE POSITIVE DRAINAGE OR MEET EXISTING SURFACES, SIDEWALK SHALL BE CONSTRUCTED WITH A CROSS SLOPE SLOPED TOWARD THE STREET. SIDEWALK CROSS SLOPES SHALL NOT EXCEED 2%.

IN TURF AREAS, THE SURFACE OF THE SIDEWALK SHALL BE ABOUT 1/4 INCH HIGHER THAN THE ADJACENT GROUND SURFACES, EXCEPT WHERE NECESSARY TO PROVIDE POSITIVE DRAINAGE OR MEET EXISTING SIDEWALKS, CURBS, OR PAVEMENTS.

SIDEWALK SHALL BE CONSTRUCTED ON A SAND BASE, COMPACTED TO AT LEAST 95% OF ITS MAXIMUM UNIT

THE CONTRACTOR SHALL NOTIFY THE ENGINEER WHEN SIDEWALK FORMS HAVE BEEN SET AND THE SAND BASE PREPARED. CONCRETE SHALL NOT BE PLACED UNTIL THE ENGINEER HAS OBSERVED THE FORMS. CONCRETE DELIVERY SHALL BE SCHEDULED TO ALLOW SUFFICIENT TIME FOR ADJUSTMENT OF THE FORMS, IN THE EVENT THAT ADJUSTMENT IS NECESSARY.

THE CONTRACTOR SHALL PROTECT FRESH CONCRETE FROM DAMAGE BY THE WEATHER, TRAFFIC, OR VANDALISM. DAMAGED CONCRETE SHALL BE REPLACED BY THE CONTRACTOR'S EXPENSE.

STORM SEWER CONSTRUCTION NOTES

DRAINAGE STRUCTURES SHALL BE CONSTRUCTED FROM PRECAST CONCRETE MANHOLE SECTIONS, MEETING

SUMPS IN DRAINAGE STRUCTURES AND PIPELINES SHALL BE FREE OF SEDIMENT AND DEBRIS AT THE TIME OF ACCEPTANCE BY THE OWNER.

ROAD PROJECTS

ADJUSTING STRUCTURES

WHERE CASTINGS FOR MANHOLES, CATCH BASINS, INLETS, VALVE BOXES, AND MONUMENT BOXES ARE TO BE ADJUSTED TO MEET A NEW PAVEMENT SURFACE ELEVATION, THE FINAL ADJUSTMENT SHALL NOT BE COMPLETED UNTIL ALL PAVEMENT COURSES HAVE BEEN PLACED EXCEPT THE FINAL COURSE. THE FINAL ADJUSTMENT SHALL BE COMPLETED JUST PRIOR TO PLACEMENT OF THE FINAL COURSE OF PAVEMENT.

THE MATERIALS AND PROCEDURES FOR ADJUSTING STRUCTURES SHALL MEET THE REQUIREMENTS OF THE AGENCIES HAVING JURISDICTION OVER THE ROAD AND UTILITIES.

SUBGRADE PREPARATION

TOPSOIL, PEAT, AND ORGANIC MATERIAL SHALL BE EXCAVATED AND REMOVED.

SOFT AND YIELDING SOILS SHALL BE REMOVED OR DRIED IF THE RESULT OF EXCESSIVE MOISTURE CONTENT. PRIOR TO CONSTRUCTING FILLS. SUBBASE, OR PAVEMENT ON A SUBGRADE: THE SUBGRADE SHALL BE PROOF-ROLLED TO DETERMINE THE SUITABILITY OF THE SUBGRADE. THE CONTRACTOR SHALL DRIVE A HEAVY PIECE OF WHEELED CONSTRUCTION EQUIPMENT OVER THE SUBGRADE WHILE THE ENGINEER IS OBSERVING. THE CONSTRUCTION OF FILLS, SUBBASE, OR PAVEMENTS SHALL NOT PROCEED UNTIL THE SUBGRADE HAS BEEN DEMONSTRATED TO BE FREE OF SOFT AREAS.

THE CONTRACTOR IS RESPONSIBLE TO MAINTAIN THE MOISTURE CONTENT OF SUBGRADE SOILS WITHIN A SUITABLE RANGE TO ALLOW FOR COMPACTION TO THE REQUIRED DENSITY. WHEN THE SOIL IS TOO DRY. THE CONTRACTOR SHALL ADD WATER. WHEN THE SOIL IS TOO WET, THE CONTRACTOR SHALL PROVIDE DRAINAGE OR AERATE THE SOIL.

THE SURFACE OF THE SUBGRADE SHALL BE COMPACTED TO AT LEAST 95% OF ITS MAXIMUM UNIT WEIGHT. PRIOR TO CONSTRUCTING FILLS, SUBBASE, OR PAVEMENTS.

HOT MIX ASPHALT (HMA) PAVING

PAVEMENTS WHICH ARE TO BE OVERLAID WITH A NEW PAVEMENT COURSE SHALL BE SWEPT TO REMOVE ALL DIRT AND DEBRIS.

A BITUMINOUS BOND COAT SHALL BE APPLIED TO PAVEMENTS WHICH ARE TO BE OVERLAID WITH A NEW PAVEMENT COURSE AND ALLOWED TO CURE PRIOR TO CONSTRUCTING THE NEW PAVEMENT COURSE. HMA PAVEMENT SHALL NOT BE PLACED WHEN THE SURFACE BEING OVERLAID IS WET, OR WHEN RAIN IS FORECAST OR THREATENING.

DRIVEWAY CONSTRUCTION

DRIVEWAY SLOPES SHALL NOT EXCEED 10%, EXCEPT WHERE SPECIFICALLY INDICATED OTHERWISE ON THE PLANS OR DIRECTED BY THE ENGINEER.

THE CONTRACTOR SHALL PROVIDE PROPERTY OWNERS WITH SUITABLE NOTICE BEFORE REMOVING AND REPLACING AN EXISTING DRIVEWAY.

WATER MAIN CONSTRUCTION NOTES

HYDRANTS, VALVES, AND OTHER MATERIALS SHALL MEET THE OWNER'S STANDARDS, WITH REGARD TO MANUFACTURER AND MODEL, AND DETAILS SUCH AS OPENING DIRECTION, HYDRANT COLOR, HYDRANT CONFIGURATION, AND HYDRANT THREAD PATTERN.

WATER MAIN MATERIALS:

TESTING AND DISINFECTION.

5 1/4 INCH AMERICAN FLOW CONTROL PACER OR EAST JORDAN IRON WORKS. BR5: WITH 5 1/4 INCH AMERICAN FLOW CONTROL PACER OR EAST JORDAN IRON WORKS. BR5: WITH

RESILIENT WEDGE GATE VALVES (MUELLER OR EAST JORDAN), OPENS COUNTER CLOCKWISE

NEW WATER MAIN SHALL NOT BE CONNECTED TO THE EXISTING WATER MAIN WITHOUT THE APPROVAL OF THE OWNER.

AT LEAST TEN FEET OF HORIZONTAL AND EIGHTEEN INCHES OF VERTICAL SEPARATION SHALL BE MAINTAINED BETWEEN THE WATER MAIN AND SEWERS (STORM OR SANITARY).

THE DEPTH OF BURY SHOWN ON THE PLANS SHALL BE PROVIDED, AS A MINIMUM, OVER THE TOP OF THE WATER MAIN PIPE TO THE FINISHED GROUND OR PAVEMENT SURFACE. UNLESS SPECIFICALLY DIRECTED OTHERWISE ON THE DRAWINGS, THE DEPTH OF BURY SHOWN ON THE PLANS SHALL BE MAINTAINED BETWEEN THE BOTTOM OF DITCHES AND THE TOP OF THE PIPE.

ALL BENDS, TEES, PLUGS, HYDRANTS, VALVES, AND OTHER FITTINGS WHERE THRUST MAY OCCUR SHALL BE RESTRAINED APPROPRIATELY BY THRUST BLOCKS OR JOINT RESTRAINT.

EXISTING WATER VALVES SHALL BE OPERATED ONLY BY THE WATER DEPARTMENT'S PERSONNEL.

THE SHUTTING DOWN OF EXISTING WATER MAINS TO ALLOW FOR COMPLETING THE CONTRACTOR'S WORK SHALL BE SCHEDULED IN ADVANCE BY THE CONTRACTOR WITH THE OWNER. THE CONTRACTOR SHALL PROVIDE NOTIFICATION TO AFFECTED WATER CUSTOMERS IN AT LEAST A DAY IN ADVANCE OF ANY SCHEDULED SERVICE DISRUPTIONS.

THE CONTRACTOR SHALL EXPOSE EXISTING MAINS TO VERIFY THE SIZE, MATERIALS, AND ANY FITTINGS NECESSARY BEFORE SHUTTING DOWN EXISTING WATER MAINS FOR NEW CONNECTIONS. ALL FITTINGS, PARTS, AND EQUIPMENT NECESSARY TO COMPLETE THE PROPOSED CONNECTIONS TO THE EXISTING MAIN SHALL BE AVAILABLE AT THE SITE BEFORE THE EXISTING MAIN IS SHUT DOWN.

THE COMPLETED WATER MAIN SHALL BE SUBJECTED TO A HYDROSTATIC PRESSURE. THE TEST PRESSURE

SHALL BE 150 PSI. THE TEST DURATION SHALL BE 2 HOURS. THE CONTRACTOR SHALL CONDUCT SUCH

PRELIMINARY LESTING TO EXPEL AIR AND VERIFY THAT THERE ARE NO LEAKS IN THE PIPELINE. THE LES SHALL BE WITNESSED BY THE ENGINEER OR OWNER. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OR OWNER AT LEAST 24 HOURS IN ADVANCE OF THE TIME FOR TESTING. IF THE CONTRACTOR ELECTS TO PRESSURE TEST AGAINST AN EXISTING VALVE. THE OWNER DOES NOT

GUARANTEE THAT EXISTING VALVES CAN RESIST THE TEST PRESSURE. IF THE CONTRACTOR BELIEVES THAT

AN EXISTING VALVE IS THE CAUSE OF A FAILED PRESSURE TEST, THE CONTRACTOR SHALL EITHER REPAIR THE VALVE AND RETEST OR TEST AGAINST A PLUG, AT THEIR EXPENSE. UNLESS SPECIFICALLY PROVIDED OTHERWISE, THE CONTRACTOR IS RESPONSIBLE TO FURNISH WATER FOR

WATER FROM THE CONTRACTOR'S FLUSHING AND DISINFECTION ACTIVITIES SHALL BE DISPOSED OF TO PREVENT EROSION OR FLOODING.

THE CONTRACTOR SHALL FURNISH AND INSTALL CORPORATIONS, TAPS, PIPING, AND FITTINGS AS NECESSARY TO COMPLETE THE REQUIRED FLUSHING AND TESTING FOR ACCEPTANCE. AFTER ACCEPTANCE, THE CONTRACTOR SHALL REMOVE ALL CORPORATIONS, TAPS, PIPING, AND FITTINGS USED FOR FLUSHING AND TESTING. TAPS TO THE WATER MAIN SHALL BE PLUGGED WITH BRASS PLUGS.

TAPS FOR SERVICE CONNECTIONS SHALL BE COMPLETED UNDER PRESSURE. THE CORPORATION AND SERVICE LEAD SHALL BE VISUALLY CHECKED FOR LEAKAGE WHILE UNDER PRESSURE. ALL JOINTS SHALL REMAIN EXPOSED UNTIL THE ENGINEER HAS OBSERVED THEM.

CORPORATIONS SHALL BE LEFT IN THE "OPEN" POSITION. CURB STOPS FOR FUTURE CONNECTIONS SHALL BE LEFT "CLOSED"; CURB STOPS FOR CURRENT WATER CUSTOMERS SHALL BE LEFT "OPEN" ONCE CONNECTED.

SANITARY SEWER CONSTRUCTION NOTES

THE NEW SANITARY SEWER SHALL NOT BE CONNECTED TO THE EXISTING SEWER UNTIL APPROVED BY THE

AT LEAST TEN FEET OF HORIZONTAL AND EIGHTEEN INCHES OF VERTICAL SEPARATION SHALL BE MAINTAINED BETWEEN THE SEWER AND EXISTING WATER MAINS.

MANHOLES SHALL BE CONSTRUCTED FROM PRECAST CONCRETE MANHOLE SECTIONS, MEETING ASTM C443. MANHOLE JOINTS SHALL BE MADE WITH RUBBER O-RING GASKETS. THE SECTION BETWEEN THE TOP OF THE PRECAST CONE AND THE BOTTOM OF THE CASTING SHALL BE CONSTRUCTED OF PRECAST GRADE RINGS, OF TOTAL THICKNESS SO THAT THE MANHOLE CASTING IS PLACED AT THE PROPER FINAL ELEVATION, EXCEPT THAT THE TOTAL THICKNESS SHALL NOT EXCEED TEN INCHES.

MANHOLE STEPS SHALL BE EQUALLY SPACED AT 15 INCHES. THE DISTANCE FROM THE TOP STEP TO THE TOP OF THE MANHOLE CASTING SHALL NOT EXCEED 16 INCHES.

THE CONTRACTOR SHALL CONDUCT A LOW PRESSURE AIR TEST ON ALL SANITARY SEWERS LESS THAN 24 INCHES IN DIAMETER. THE AIR TEST SHALL MEET THE REQUIREMENTS OF ASTM C 924 FOR CONCRETE PIPE AND ASTM F1471 FOR PLASTIC PIPE. IN AREAS WHERE GROUNDWATER IS OVER THE PIPE, THE TEST PRESSURE SHALL BE INCREASED EQUAL TO THE HYDRAULIC PRESSURE EXERTED BY THE WATER OVER THE PIPE, AS DETERMINED BY THE ENGINEER.



DATE REVISION STATE OF MICHIGAN DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICE ADMINISTRATION

DESIGN AND CONSTRUCTION DIVISION ADAM LACH, DIRECTOR

491/20167.SDW FUNDING CODE

FILE NO.

171CODHHS7255 Y22003

CONTRACT NO.

KEY PLAN

WTAARCH.COM

COPYRIGHT © 2023

NOT TO SCALE



100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107



PROJECT TITLE

KITCHEN


A.J.T.


491/20167.SDW CFP - PHASE 500 CENTER FOR FORENSIC


PSYCHIATRY - CREATE


SALINE, MICHIGAN SHEET TITLE CIVIL NOTES

PROJECT NUMBER SHEET NUMBER 2021094 PROJECT DATE SEPTEMBER 6, 2023 CHECKED BY











NOT TO SCALE


CONSTRUCTION ACCESS DRIVE DETAIL NOT TO SCALE



NOT TO SCALE




FOR PAVEMENT AREAS **CLEANOUT RISER DETAIL**




NOT TO SCALE

SIDEWALK DETAIL NOT TO SCALE



NOTES: 1. SEAL ALL EXPANSION JOINTS WITH 1/2" PREMOLDED FILLER, HELD DOWN 1/2" DOWN.

CONCRETE PAVEMENT CROSS SECTION NOT TO SCALE



FIRE HYDRANT DETAIL

NOT TO SCALE

(2) #4 BARS EACH

SIDE EQUAL SPACED

#4 STIRRUPS @ 18" O.C.

GHOOI	אט טטר			RE PIPES	3 (OLL	NOIL	<i>''</i>
LENGT	H (IN FE	ET) OF R	ESTRAIN	r Require	ED (SEE 1	NOTE 2)	
DEFLECTION PIPE ANGLE DIAMETER	22 1/2*	33 3/4°	45 °	56 1/4*	67 1/2°	78 3/4°	90° TEE OR DEAD END
6"	3	6	11	16	23	29	37
8"	4	8	15	22	31	41	50
10"	5	11	18	28	38	49	61
12"	6	13	22	33	45	59	73
14"	7	14	25	37	52	68	84
16"	8	16	28	42	59	77	95
18"	8	18	31	47	66	86	107
20"	9	20	35	53	73	95	118
24"	11	23	40	61	85	111	138
30"	13	29	50	75	105	136	170
36"	15	34	59	88	123	160	199
42"	17	39	67	101	141	184	228
48"	19	43	75	113	157	206	255

PRESSURE TAPPING SLEEVE & VALVE DETAIL

MINIMUM PIPE RESTRAINT SCHEDULE FOR

1. ALL PRESSURE TAPS MUST BE INSTALLED IN A CONCRETE VALVE MANHOLE.

2. CONTRACTOR SHALL LOCATE AND EXPOSE EXISTING WATER MAIN. THE CONTRACTOR WILL PROVIDE ANY FITTINGS NECESSARY TO COMPLETE

TRANSITION(S) FROM EXISTING MAIN TO PROPOSED CONSTRUCTION.

AND ONE MECHANICAL JOINT END (CONNECTED TO THE PIPELINE).

5. THE VALVE SHALL MEET ALL REQUIREMENTS OF AWWA C500.

8. USE FLAT SLAB FOR COVER WITH 24" OPENING.

6. THE MINIMUM SIZE MANHOLE SHALL BE 6'-0" INTERNAL DIAMETER.

7. THE TOP OPENING SHALL BE CENTERED ON THE VALVE OPERATING NUT.

MECHANICAL JOINT END

- FLANGED TO TAPPING SLEEVE

TAPPING MACHINE CUTTERS.

3. THE VALVE SHALL HAVE ONE FLANGED END (CONNECTED TO THE SLEEVE)


4. THE VALVE SHALL HAVE OVERSIZE SEAT RINGS TO PERMIT ENTRY OF THE

BUILDING These documents are approved for compliance with the STATE OF MICHIGAN BUILDING CODE subject to field inspection and the conditions of approval.

- NOTES: THIS TABLE IS BASED ON A TEST PRESSURE OF 180 PSI (OPERATING PRESSURE + WATER HAMMER.) FOR OTHER TEST PROCEDURES, ALL VALUES ARE TO BE INCREASED OR DECREASED PROPORTIONALLY.
- IN EACH DIRECTION FROM POINT OF DEFLECTION OR TERMINATION EXCEPT FOR A TEE AT WHICH ONLY THE BRANCH IN THE DIRECTION OF THE TEE STEM.

3. IF TIE RODS ARE USED, PLACE 2 RODS 5/8 INCH DIAMETER MINIMUM FOR WATER MAIN 6 INCH TO 10 INCH AND 4 RODS 5/8 INCH DIAMETER MINIMUM FOR 12 INCH AND LARGER.

PIPE RESTRAINT SCHEDULE NOT TO SCALE




OR BRANCH

THRUST BLOCK DETAILS NOT TO SCALE


22 1/2° BEND | PLUGS, HYDRANTS |

11 1/4° BEND

AND TEE




CHAIN LINK FENCE DETAIL NOT TO SCALE



1. STRUCTURE ADJUST SHALL BE CUT IN A DIAMOND WITH A MINIMUM 2' DISTANCE FROM THE CASTING. 2. CONCRETE BACKFILL WILL NOT BE PERMITTED. ALL COSTS OF BACKFILL (AGGREGATE AND HMA) INCLUDED IN COST OF ADJUSTMENT OR NEW STRUCTURE AND WILL NOT BE PAID FOR SEPARATELY.

STRUCTURE COVER ADJUST DETAIL - HMA BASE



HMA PAVEMENT CROSS SECTION NOT TO SCALE




DATE REVISION STATE OF MICHIGAN

DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICE ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, DIRECTOR

FILE NO. 491/20167.SDW FUNDING CODE

CONTRACT NO. Y22003



WTAARCH.COM

100 S Jefferson Ave, Suite 601 | Saginaw, Michigan 48607

989 752 8107 COPYRIGHT © 2023 ROWE PROFESSIONAL


SERVICES COMPANY PROJECT TITLE 491/20167.SDW CFP - PHASE 500


CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN SALINE, MICHIGAN


SHEET TITLE CIVIL DETAILS


CHECKED BY A.J.T.


PROJECT NUMBER SHEET NUMBER 2021094 PROJECT DATE SEPTEMBER 6, 2023






















DEFENCE





TYPICAL FENCE AT BUILDING DETAILS

DATE April 12, 2023


DEFENCE







PERIMETER ELECTRIC FENCE DETAIL NOT TO SCALE





REVISION

STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET
DEPARTMENT OF TECHNOLOGY ADMINISTRATION

DESIGN AND CONSTRUCTION DIVISION

CONTRACT NO.

KEY PLAN NOT TO SCALE

WTAARCH.COM

Y22003

ADAM LACH, DIRECTOR

P

FILE NO.

491/20167.SDW

171CODHHS7255

##

FUNDING CODE

SHEET TITLE FENCE DETAILS

SALINE, MICHIGAN

project number 2021094	SHEET NUMBER
PROJECT DATE SEPTEMBER 6, 2023	
CHECKED BY A.J.T.	

GENERAL CONSTRUCTION NOTES:


1) CONTRACTOR WILL COORDINATE WITH FACILITY STAFF TO DETERMINE THE IRRIGATION SYSTEM LOCATION FOR REMOVALS AND REPLACEMENT AROUND PROPOSED

- IMPROVEMENTS.

 2) CONTRACTOR TO COMPLETE GROUND PENETRATING RADAR WITHIN CONSTRUCTION LIMITS TO DETERMINE THE EXACT LOCATION OF UNDERGROUND UTILITIES PRIOR TO
- 3) PRIOR TO CONSTRUCTION CONTRACTOR IS TO WORK WITH THE FACILITY TO DETERMINE AN ADEQUATE LAYDOWN AREA AND JOB TRAILER LOCATION.

BEGINNING EXCAVATION.

- 4) ALL BENCHES ARE TO BE SALVAGED COORDINATE STORAGE LOCATION WITH OWNER.
- 5) EXISTING ABANDONED CONDUIT ALONG EXPOSED WALL SHALL BE REMOVED TO THE BUILDING FOUNDATION AND SHALL BE SEALED TO BE MADE WATER TIGHT.





EXISTING STRUCTURE INVENTORY

MH# 28B TYPE: STORM TYPE: STORM COVER: FLAT GRATE COVER: RND INLET RIM=835.90' RIM=839.64' 8.0" PVC S INV.=830.80' 4" PVC NW INV.=831.47' 8.0" PVC SW INV.=830.80' 8" NE INV.=830.62' 8.0" PVC W INV.=830.48' 6.0" PVC NW INV.=830.80' 12.0" RCP N INV.=830.39' MH# 28A TYPE: STORM COVER: RND INLET RIM= 834.18' MH# 19B TYPE: STORM 8" SE INV.=828.18' 8" SW INV.=828.28' COVER: RND INLET RIM=833.80' 8.0" PVC N INV.=831.14' MH# 30 TYPE: STORM COVER: RND INLET MH# 20 RIM=831.07' TYPE: STORM COVER: RND INLET 15" SW INV.=819.10' 15" SE INV.=820.57' RIM= 835.49' 12' RCP SW INV.=829.70' 15" RCP NE INV.=830.29' MH# 71 TYPE: STORM MH# EX 22A COVER: RND INLET

TYPE: STORM RIM=832.02' COVER: CURB INLET 15" NW INV.=820.45' RIM= 835.23' 12" SW INV.=820.45' 8" S INV.=830.26' 15" SW INV.=829.26' 12" SE INV.=820.91' 15" NE INV.=829.37' MH# 71A TYPE: STORM MH# 22B TYPE: STORM COVER: RND INLET RIM= 831.36' COVER: RND INLET

COVER: RND INLET
RIM= 834.16'
8" N INV.=830.49'

MH# 22
TYPE: STORM

TYPE: STORM

OVER: RND INLET
RIM= 831.36'
12' NE INV.=828.96'

MH# 73
TYPE: STORM

TYPE: STORM
COVER: FLATE GRATE
RIM= 836.54'
15" SW INV.=829.16'
12" S INV.=827.89'
18" N INV.=828.81'

MH# 24
TYPE: STORM
COVER: RND INLET
RIM= 829.27
12" NW INV.=820.45'
12" N INV.=824.28'
15" SE INV.=820.91'

MH# 73A
TYPE: STORM

MH# 24
TYPE: STORM
COVER: RND INLET
RIM= 832.41'
12" N INV.=828.81'
8.0" S INV.=828.49'

MH# 24-1

MH# 24-1

MH# 24-1

MH# 24-1

MH# 24-1

MH# 73A

TYPE: STORM
COVER: RND INLET
RIM= 829.58'
12" S INV.=827.33'
4" N INV.=828.73'
8" E INV.=827.33'

TYPE: STORM
COVER: RND INLET
RIM= 830.72'
8.0" N INV.=528.52'


MH# 28

MH# 73B
TYPE: STORM
COVER: RND INLET
RIM= 831.22'
8" W INV.=827.48'
4" N INV.=828.68'
4" S INV.=828.48'

MH# 28 TYPE: STORM COVER: RND INLET RIM= 828.97 12" SW INV.=819.10' 8" NW INV.=825.61' 15" NE INV.=820.57'

MICHIGAN UNIFIED KEYING SYSTEM
SOIL EROSION AND SEDIMENTATION CONTROL MEASURES

KEY	DETAIL	CHARACTERISTICS
36	CATCH BASIN, DRAIN INLET	COLLECTS HIGH VELOCITY CONCENTRATED RUNOFF MAY USE FILTER CLOTH OVER INLET








NO.		REVISION	DATE
TUENC	DR	STATE OF MICHIGAN DEPARTMENT OF TECHNOLOGY, MANAGEMENT AN FACILITIES AND BUSINESS SERVICE ADMINISTRATE DESIGN AND CONSTRUCTION DIVI	ION


CONTRACT NO.

FILE NO. 491/20167.SDW

ADAM LACH, DIRECTOR

FUNDING CODE
171CODHHS7255





WTA ARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107



PROJECT TITLE

A.J.T.

491/20167.SDW CFP - PHASE 500


CENTER FOR FORENSIC PSYCHIATRY — CREATE KITCHEN saline, michigan

SITE DEMOLITION PLAN

PROJECT NUMBER
2021094


PROJECT DATE
SEPTEMBER 6, 2023


CHECKED BY



1) PROPOSED PERIMETER ELECTRIC AND CHAIN LINK FENCE IS TO MATCH THE EXISTING FENCE SIZE AND STYLE. ALL FENCING IS TO BE INSTALLED PER MANUFACTURES REQUIREMENT. SEE SHEET C1.04 FOR MORE DETAILS.

2) PERIMETER ELECTRIC FENCE IS TO BE INSTALLED AGAINST PROPOSED BUILDING CORNER AS SHOWN TO ALLOW FOR NO GAP OR MEANS OF PASSAGE. SEE SHEET C1.04 FOR MORE DETAILS.





SITE INFORMATION

PROPERTY ADDRESS: 8303 PLATT ROAD SALINE, MI 48176

PROPERTY OWNER: CENTER FOR FORENSIC PSYCHIATRY

PROPERTY TAX ID: S-19-02-200-003

ZONING AND SETBACK REQUIREMENTS: A-2; INTERIM AGRICULTURE

FRONT YARD SETBACK - 50 FT SIDE YARD SETBACK - 30 FT REAR YARD SETBACK - 50 FT

TH N 88-35-59 E 353.45 FT, TH S


LEGAL DESCRIPTION: OWNER REQUEST YO 2-7A-1 BEG AT NW COR SEC 2, TH N 88-33-31 E 2488.02 FT,

> 01-24-01 W 388.00 FT, TH N 88-35-59 E 245.00 FT, TH N 01-24-01 E 388.00 FT, TH N 88-35-59 E 344.48 FT, TH S 01-30-15 E 1199.51 FT, TH S 88-33-41 W 3429.32 FT, TH N 01-34-54 W 1200.00 FT TO THE POB. PT OF N 1/2 SEC 2, T4S-R6E. 92.31 AC SPLIT ON 06/29/2005 FROM S

-19-02-200-001;

ADJACENT PROPERTIES: S-19-02-200-002 S-19-02-200-004

TOTAL SITE AREA: 92.31 ACRES




REVISION STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET

FACILITIES AND BUSINESS SERVICE ADMINISTRATION
DESIGN AND CONSTRUCTION DIVISION
ADAM LACH, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255

CONTRACT NO. Y22003





WTAARCH.COM

COPYRIGHT © 2023

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107



491/20167.SDW CFP - PHASE 500


CENTER FOR FORENSIC PSYCHIATRY — CREATE KITCHEN

SALINE, MICHIGAN SHEET TITLE SITE PLAN

A.J.T.

PROJECT NUMBER 2021094 SHEET NUMBER PROJECT DATE
SEPTEMBER 6, 2023

CHECKED BY



WATER MAIN FITTING TABLE

5 8" X 12" TAPPING SLEEVE & VALVE IN WELL 244808.58 13306256.48

FITTING TYPE HYDRANT ASSEMBLY

6" GATE VALVE 8" X 6" REDUCER

45° BEND


NORTHING EASTING


244776.00 | 13306121.18 |

244779.62 | 13306124.36 |

244785.58 | 13306129.58 |

244807.65 | 13306148.92 |





		PROP(DSED STORM	SEWER STRUCTURE	TABLE	
STRUCT NO.	DIA.	COVER TYPE	RIM ELEVATION	INVERT	NORTHING	EASTING
EX 28	N/A	N/A	RIM=835.09	12" 827.27 SW (EX) 8" 829.27 SE (PR) 8" 825.61 NW (EX) 15" 819.10 E (EX)	244819.86	13306172.92
EX 20	N/A	N/A	T/C=834.37	12" 830.29 S (PR) 15" 830.29 NE (EX)	244876.50	13306008.16
EX 28A	N/A	N/A	RIM=833.60	8" 828.18 SW (PR) 8" 828.18 SE (EX)	244841.58	13306136.61
1	48"	G	RIM=835.60	12" 831.21 NE (PR) 6" 831.46 SW (PR) 6" 831.46 NW (PR)	244808.30	13305954.08
2	48"	G	RIM=835.63	12" 830.57 N (PR) 12" 830.57 SW (PR) 6" 830.82 NW (PR)	244848.48	13306004.16
3	48"	G	RIM=834.30	8" 830.16 NE (PR) 6" 830.84 NW (PR) 6" 830.65 N (PR)	244677.20	13306025.68
4	24"	G	RIM=833.04	8" 829.57 NW (PR)	244792.70	13306186.54

24	<u> </u>	1/11/1-055.04	0 023	.57 1111 (111) 244/	92.70 130	1001
PROPOSED STORM SEWER PIPE TABLE							
	PIPE JMBER	DIAMETER	TOTAL LENGTH	SLOPE	TRENCH DETAIL A (T.D. A)	TRENCH DETAIL B (T.D. B)	
STI	M 1-2	12"	64'	1.00%	42'	22'	
STM	2-EX 20	12"	28'	1.00%	20'	8']
STM 3	5–EX 28A	8"	198'	1.00%	8'	190'	
STM	4-EX 28	8"	30'	1.00%	5'	25'	
STM E	BLDG-CO1	6"	5'	1.00%	0'	5'	
STM E	LDG-CO2	12"	31'	1.00%	0'	31'	
STM E	LDG-CO3	6"	37'	1.00%	0'	37'	
STM B	BLDG-CO4	6"	5'	1.00%	0'	5'	
STM E	LDG-CO5	6"	3'	1.00%	0'	3'	
STM	CO1-2	6"	38'	1.00%	10'	28'	
STM	CO2-1	6"	33'	1.00%	8'	25'	
STM	CO3-1	6"	28'	1.00%	5'	23'	
STM	CO4-3	6"	118'	1.00%	0'	118'	
STM (CO5-CO6	6"	10'	1.00%	7'	3'	
STM(CO6-CO7	6"	57'	1.00%	15'	42'	
STM	CO7-3	6"	15'	1.00%	12'	3'	

PRO	POSED CLE TABLE	ANOUT
CLEANOUT	NORTHING	EASTING
CO1	244865.88	13305970.76
CO2	244834.65	13305934.31
CO3	244787.91	13305934.89
CO4	244748.56	13305931.40
C05	244740.57	13305981.26
C06	244730.57	13305981.61
C07	244691.72	13306023.27

BUILDING

These documents are approved for compliance with the STATE OF MICHIGAN BUILDING CODE subject to leid inspections.

conditions of approval.



NO.	REVISION	DATE
TUERO	STATE OF MICHIGAN DEPARTMENT OF TECHNOLOGY, MANAGEMENT AN FACILITIES AND BUSINESS SERVICE ADMINISTRAT DESIGN AND CONSTRUCTION DIVI ADAM LACH, DIRECTOR	ION

CONTRACT NO.

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255

Y22003 KEY PLAN NOT TO SCALE



WTAARCH.COM

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107




PROJECT TITLE


491/20167.SDW CFP - PHASE 500


CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN SALINE, MICHIGAN

SHEET TITLE UTILITY PLAN

PROJECT NUMBER 2021094	SHEET NUMBER
PROJECT DATE SEPTEMBER 6, 2023	
CHECKED BY A.J.T.	







	N	•
0	20 ft	40

		GRADING TA	BLE					GRADING TA	GRADING TABLE
POINT	ELEVATION	DESCRIPTION	NORTHING	EASTING		POINT	POINT ELEVATION	POINT ELEVATION DESCRIPTION	POINT ELEVATION DESCRIPTION NORTHING
100	TW=835.88	PC	244707.13	13305976.81		124	124 TW=836.40	124 TW=836.40	124 TW=836.40 244849.15
101	TW=836.39	PC	244743.58	13305949.46		125	125 ME=836.05	125 ME=836.05	125 ME=836.05 244901.07
102	TW=835.94	PC	244712.98	13305982.26		126	126 ME=835.59	126 ME=835.59	126 ME=835.59 244901.74
103	TW=836.32	PC	244737.73	13305944.00		127	127 TW=836.50	127 TW=836.50 ME	127 TW=836.50 ME 244814.66
104	TW=836.44	PC	244748.17	13305939.24		128	128 TW=836.50	128 TW=836.50	128 TW=836.50 244754.02
105	TW=836.44	PC	244748.45	13305947.24		129	129 TW=836.50	129 TW=836.50	129 TW=836.50 244754.30
106	TW=836.50	ME	244846.22	13305945.58		130	130 TW=836.08	130 TW=836.08 TP	130 TW=836.08 TP 244726.12
107	TW=836.50	ME	244855.07	13305911.66		131	131 TW=836.17	131 TW=836.17 TP	131 TW=836.17 TP 244731.57
108	TW=836.50	ME	244848.42	13305947.63		132	132 TW=836.29	132 TW=836.29 TP	132 TW=836.29 TP 244739.70
109	TW=836.51	ME	244846.88	13305920.36		133	133 TW=836.50	133 TW=836.50	133 TW=836.50 244747.42
110	TW=836.33		244823.43	13305957.90		134	134 TW=836.50	134 TW=836.50	134 TW=836.50 244753.52
111	TW=836.50	ME	244867.31	13305923.18		135	135 TW=836.29	135 TW=836.29 TP	135 TW=836.29 TP 244746.15
112	TW=836.50		244831.69	13305965.57		136	136 TW=835.86	136 TW=835.86 PC	136 TW=835.86 PC 244715.13
113	TW=836.26	ME	244828.69	13305933.78		137	137 TW=835.78	137 TW=835.78 PC	137 TW=835.78 PC 244709.69
114	TW=836.27		244829.58	13305951.26		138	138 RIM=835.60	138 RIM=835.60	138 RIM=835.60 244808.30
115	TW=836.50		244857.19	13305955.82	I	139	139 RIM=835.52	139 RIM=835.52	139 RIM=835.52 244848.48
116	TW=836.00	ME	244877.73	13305974.97		140	140 TP=834.74	140 TP=834.74 PC	140 TP=834.74 PC 244835.45
117	TW=836.50		244840.72	13305973.48		141	141 RIM=833.60	141 RIM=833.60	141 RIM=833.60 244841.58
118	TW=835.73	ME	244861.26	13305992.63		142	142 TP=834.74	142 TP=834.74 PC	142 TP=834.74 PC 244853.31
119	TW=835.44		244694.09	13306017.22		143	143 TP=834.98	143 TP=834.98 PC	143 TP=834.98 PC 244934.55
120	RIM=834.30		244677.20	13306025.68		144	144 TP=834.67	144 TP=834.67 PC	144 TP=834.67 PC 244960.41
121	TW=836.07	ME	244874.11	13306007.56		145	145 TP=834.37	145 TP=834.37 PC	145 TP=834.37 PC 244961.22
122	TW=836.05	ME	244878.49	13306011.66		146	146 TP=834.10	146 TP=834.10	146 TP=834.10 244965.22
123	TW=836.50		244844.77	13306039.02		147	147 TP=834.46	147 TP=834.46 PC	147 TP=834.46 PC 244995.77

POINT	ELEVATION	DESCRIPTION	NORTHING	EASTING	POINT	ELEVATION	DESCRIPTION	NORTHING	EASTING
148	TP=834.72		245013.07	13306190.85	172	TP=833.46	PC	244816.12	13306252.98
149	TP=834.88		245026.20	13306182.61	173	TP=833.76	ME	244797.03	13306254.47
150	TP=834.93		245029.63	13306178.98	174	TP=834.31	PC & ME	244800.13	13306233.36
151	TP=835.06		245038.01	13306170.08	175	TP=834.06	PC	244806.70	13306223.79
152	TP=835.16	ME	245042.73	13306162.31	176	TP=835.23	PC	244803.49	13306143.51
153	TP=835.11		245041.43	13306166.45	177	TP=834.94	PC	244795.20	13306134.06
154	TP=834.97	ME	245055.73	13306174.61	178	TP=834.92		244794.45	13306133.93
155	TP=834.91		245049.44	13306173.99	179	TP=835.24		244770.93	13306112.48
156	TP=834.86		245046.02	13306177.62	180	TP=835.35		244770.45	13306103.94
157	TP=834.73		245037.64	13306186.52	181	SWALE=835.20		244739.12	13306099.42
158	TP=834.68		245034.21	13306190.16	182	SWALE=834.54		244761.94	13306123.34
159	TP=834.52		245027.63	13306204.57	183	SWALE=833.96		244783.62	13306142.19
160	TP=834.26	PC	245010.33	13306222.93	184	SWALE=833.65		244790.44	13306155.81
161	TP=833.84	PC	244969.65	13306233.79	185	RIM=833.04	SWALE	244792.70	13306186.54
162	TP=833.51	ME	244941.53	13306225.30	186	TW=835.57		244702.01	13306016.20
163	TP=834.01	ME	244941.15	13306193.63	187	TP=834.67		244893.93	13306142.21
164	TP=834.54	ME	244939.83	13306160.64	188	TW=836.50		244656.05	13306031.57
165	TP=834.96	ME	244893.52	13306162.14	189	TW=836.50		244651.83	13306027.45
166	TP=835.04	ME	244884.64	13306162.54	190	TW=836.50		244702.93	13305972.87
167	TP=835.31	ME	244824.44	13306164.62	191	TW=836.50		244733.58	13305940.12
168	TP=835.23	ME	244824.56	13306169.98	192	TW=836.50		244748.04	13305924.64
169	TP=834.14	ME	244827.05	13306229.80	193	TW=836.50		244752.18	13305928.51
170	TP=834.12	ME	244830.70	13306229.65	194	TW=836.50		244851.59	13306031.71
171	TP=833.69	PC	244830.52	13306238.32	195	TW=836.40		244855.97	13306035.80

GRADING TABLE

GRADING TABLE


RADIUS POINTS					
POINT	DESCRIPTION	NORTHING	EASTING		
Α	7' & 15' R	244748.70	13305954.23		
В	42' & 50' R	244743.69	13306010.91		
С	10' R	244793.49	13306143.91		
D	10' R	244796.70	13306223.97		
E	15' R	244815.52	13306238.00		
F	25' R	244935.42	13306165.79		
G	20' & 40'R	244981.21	13306195.50		
Н	20' R	244770.50	13306157.28		
I	25' R	244852.45	13306118.63		

POINT	DESCRIPTION	NORTHING	EASTING
Α	7' & 15' R	244748.70	13305954.23
В	42' & 50' R	244743.69	13306010.91
С	10' R	244793.49	13306143.91
D	10' R	244796.70	13306223.97
Ε	15' R	244815.52	13306238.00
F	25' R	244935.42	13306165.79
G	20' & 40'R	244981.21	13306195.50
Н	20' R	244770.50	13306157.28
I	25' R	244852.45	13306118.63

1)	CONTRACTOR TO COMPLETE GROUND PENETRATING	
•	RADAR WITHIN CONSTRUCTION LIMITS TO DETERMINE	TH
	EXACT LOCATION OF UNDERGROUND UTILITIES PRIOR	T0
	BEGINNING EXCAVATION.	

GRADING LEGEND

TP - TOP OF PAVEMENT
TW - TOP OF CONCRETE SIDEWALK
ME - MATCH EXISTING ELEVATION
PC - POINT OF CURVATURE
RIM - MANHOLE RIM




ı					
	NO.		REVISION		
	(Time)	Mis.	STATE OF MICHIGAN		
	· · · · · · · · · · · · · · · · · · ·		DEPARTMENT OF TECHNOLOGY, MANAGEMENT AN	ND BUDGET	
	TUEBO	R	FACILITIES AND BUSINESS SERVICE ADMINISTRAT		
	DESIGN AND CONSTRUCTION DIVISION				
ı			ADAM LACH DIRECTOR		

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255

CONTRACT NO. Y22003





WTAARCH.COM

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023 ROWE PROFESSIONAL SERVICES COMPANY

PROJECT TITLE


491/20167.SDW CFP - PHASE 500

CENTER FOR FORENSIC PSYCHIATRY — CREATE KITCHEN SALINE, MICHIGAN

SHEET TITLE GRADING PLAN

PROJECT NUMBER 2021094	SHEET NUMBER
PROJECT DATE SEPTEMBER 6, 2023	
CHECKED BY A.J.T.	









 REFER TO WALL TYPES <1.0> AND <3.0>. IN LIEU OF RIGID INSULATION AND VAPOR BARRIER INDICATED PROVIDE SPRAY INSULATION. MATCH THE REQUIRED R-VALUE AND MUST ALSO ACT AS A VAPOR BARRIER

#.# WALL TYPES:

SCALE: 1/2" = 1'-0" NOTE: REFER TO SHEETS A1.01 FOR RATED WALL LOCATIONS.

1.0 4" VENEER FACE BRICK / BURNISHED / SPLIT FACE BLOCK (REFER TO ELEVATIONS) w/ 3" RIGID INSUALTION IN AIR SPACE ON BITUMINOUS DAMPPROOFING ON 8" CONCRETE MASONRY UNITS. REFER TO ELEVATIONS AND SECTIONS FOR EXTENSION OF MATERIALS. LOAD BEARING.

2.0 8" CONCRETE MASONRY UNITS. EXTEND FROM FINISH FLOOR TO UNDERSIDE OF STRUCTURE

2.1 4" CONCRETE MASONRY UNITS. EXTEND FROM FINISH FLOOR TO UNDERSIDE OF STRUCTURE

DATE

WTAARCH.COM

COPYRIGHT © 2023

REVISION

DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET

CONTRACT NO.

Y22003

FACILITIES AND BUSINESS SERVICES ADMINISTRATION

DESIGN AND CONSTRUCTION DIVISION

WTA ARCHITECTS

STATE OF MICHIGAN


491/20167.SDW

171CODHHS7255

FUNDING CODE

ADAM LACH, RA, DIRECTOR

3.0 4" VENEER FACE BRICK / BURNISHED / SPLIT FACE BLOCK (REFER TO ELEVATIONS) w/ AIR SPACE w/ 3" RIGID INSUALTION ON BITUMINOUS DAMPPROOFING ON 6" METAL STUD FRAMING @ 16" O.C. w/ 5/8" TYPE "X" GYPSUM BOARD. REFER TO ELEVATIONS AND SECTIONS FOR EXTENSION OF MATERIALS. LOAD BEARING.



ABBREVIATIONS ABOVE FINISHED FLOOR ACOUSTIC(AL)

ACOUSTIC CEILING PANEL
ACOUSTIC CEILING TILE

ACRYLIC RESIN PANEL

ADJIUSTABLE
ALTERNATE
ALUMINUM
ANODIZED
APPROXIMATE
ARCHITECTURAL


BACKER BOARD


C.M.TILE/CMT

G. TILE/GT

3 5 8 9 10 11 12 13 | 14 | 15 | 16 | 17 | 18 19 20 21 22 23 24

LOCATION NUMBER GRID





REFERENCE BUBBLES:

LOCATION NUMBER

ROOM IDENTIFIER:

ROOM NAME

F.R.L./FRL F.S.F./FSF F.T.F./FTF

BEARING
BITUMINOUS
BLOCKING
BOARD
BOTTOM
BOTTOM OF CURB
BOTTOM OF FOOTING
BRICK
BUILDING SPLIT FACE
SQUARE FEET
STAINLESS STEEL
STANDARD
STORAGE
STRAIGHT
STRUCTURE
SUSPENDED LAMINATE(D)
LAVATORY (SINK)
LINOLEUM SHEET FLOORING
LINOLEUM TILE FLOORING LAM./LAM LAV. L.S.F./LSF L.T.F./LTF STD. STO./STOR. STRT. STRUC. SUSP. CARPET
CATCH BASIN
CEILING
CERAMIC MOSAIC TILE
CERAMIC TILE
CHALKBOARD
CLEAR
COLUMN
CONCRETE
CONCRETE
CONCRETE MASONRY UNIT
CONTINUOUS
CONTINUOUS JOINT
COLUMTER TOP LUXURY VINYL TILE TACKBOARD
TELEPHONE
TELEVISION
TEMPER(ED)
THICK
TOILET PAPER DISPENSER MANUFACTURE(R) MARKERBOARD MASONRY MASONRY OPENING MECHANICAL
METAL
METAL PANEL
MICHIGAN DEPARTMENT OF
TRANSPORTATION TOP OF MASONRY CONTINUOUS JOINT
COUNTER TOP
COVERING
DEPARTMENT
DIAMETER
DOOR OPENING
DOUBLE
DOWN
DRAIN TILE
DRAWING
DRINKING FOUNTAIN
DETENTION HOLLOW METAL UNLESS NOTED OTHERWISE MIRROR MISCELLANEOUS VERIFY IN FIELD VERTICAL VENT THROUGH ROOF NOMINAL NOT IN CONTRACT NOT TO SCALE VNL./VNL V.C.T./VCT VINYL COMPOSITION TILE WATER CLOSET NUMBER W.MAT/WOM WALK-OFF MAT ON CENTER
OPPOSITE (HAND)
ORIENTED STRAND BOARD
OUTSIDE DIAMETER EACH
EACH WAY
ELECTRIC(AL)
ELECTRIC HAND DRYER
ELECTRIC WATER COOLER
ELEVATION W.W.F. W.W.M. W.O. WELDED WIRE FABRIC WELDED WIRE MESH WINDOW OPENING WITH WOOD OUTSIDE FACE OF BLOCK OUTSIDE FACE OF BRICK ELEVATION
ELEVATOR
EQUAL
EXHAUST FAN
EXISTING
EXPOSED
EXTERIOR OUTSIDE FACE OF CONCRETE OUTSIDE FACE OF MASONRY OUTSIDE FACE OF STUDS PT./P PAINT(ED) PAINT(ED)
PAIR
PAPER TOWEL DISPENSER FEET PART. BD.
FINISHED FACE PTN.
FINISHED OPENING PLAS.
FIRE EXTINGUISHER PLAM./PL
FIRE EXTINGUISHER PLAM./PL
FIRE EXTINGUISHER CABINET
FIRE RATED PLYWD.
FIRE RETARDANT P.J.LLE/PT
FIBER REINFORCED LAMINATE PWR.
FIXTURE
FIXTURE
FIXTURE
FIXTURE
FICOKED SHEET FLOORING
FLOCKED TILE FLOORING
FLOOR Q.TILE/QT
FLOOR DRAIN QTZ./QTZ
FOOTING PARTICLE BOARD PHYSICALLY HANDICAPPED PLASTER PLASTIC LAMINATE PLYWOOD POINT OF NEW CONNECTION PORCELAIN TILE PRECAST CONCRETE POLISHED CONCRETE

FIBER REINFORCED POLYESTER RAD.

S.A.T. SF.GL. S.N.DR. S.N.DL.

GRAB BAR GYPSUM BOARD

HIGH POINT HOLLOW METAL HORIZONTAL

INSULATE(D) INTERIOR

INSIDE FACE OF BLOCK INSIDE FACE OF BRICK

REFRIGERATOR REINFORCE(MENT)

ROUGH OPENING

SANITARY NAPRIN SASH OPENING SCHEDULE SEALANT SHEET SIMILAR SMOOTH FACE SPECIFICATION(S) SPLIT FACE

REQUIRED RESILIENT WALL BASE

RESILIENT SHEET FLOORING RESILIENT TILE FLOORING

SUSPENDED ACOUSTICAL TILE

SANITARY NAPKIN DISPENSER SANITARY NAPKIN DISPOSAL

LEGEND OF ABBREVIATIONS

- 24" x 36" MIRROR BOTTOM OF LAVATORY 60" MIN. BOTTOM OF 12" MIN. LAV. APRON TOP OF FIXTURES DEPICTED WITHIN THIS LAVATORY SCHEDULE ARE SCHEMATIC ONLY. FOR BOTTOM OF EXACT FIXTURE TYPES AND QUANTITIES, REFER TO MECHANICAL DRAWINGS AS WELL AS THE SPECIFICATION MANUAL. GLASS

TOILET TISSUE 36" DISPENSER (2) MAX. OPTIONAL LOCATIONS SANITARY

NAPKIN

DISPOSAL

EXTINGUISHER CABINET DRINKING FOUNTAI N (E.W.C.)

COIN/CARD -SLOT SOAP TOWEL DISPENSER BAR THERMOSTAT DISPENSER BAR PAPER TOWEL DISPENSER (P.T.D.) TELEPHONE WASTE RECEPTACLE

SALINE, MICHIGAN SHEET TITLE PROJECT INFORMATION

KITCHEN

CHECKED BY C.D.S.

100 S Jefferson Ave, Suite 601

Saginaw, Michigan 48607

989 752 8107

PROJECT TITLE


PROJECT NUMBER SHEET NUMBER 2021094 PROJECT DATE A0.01 SEPTEMBER 6, 202

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC

PSYCHIATRY - CREATE

MNT HEIGHT DETAIL 25/A0.01 SCALE: 1/4" = 1'-0"



CODE LEGEND ■ ● ■ 3-HOUR BUILDING SEPARATION 2-HOUR BARRIER ● ● ● ● ● ■ 1-HOUR ENCLOSURE 1-HOUR SMOKE BARRIER → → → → TRAVEL DISTANCE 100% SPRINKLED **DF** DRINKING FOUNTAIN FIRE EXTINGUISHER # OCCUPANT LOAD # EXIT CAPACITY

NO.	REVISION	DATE


STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET
FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255

Y22003

CONTRACT NO.





WTAARCH.COM

WTA ARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023

PROJECT TITLE

C.D.S.

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN


SALINE, MICHIGAN

SHEET TITLE FIRST FLOOR MASTER CODE PLAN


PROJECT NUMBER 2021094 SHEET NUMBER PROJECT DATE

A2.01 SEPTEMBER 6, 202 CHECKED BY

CODE REFERENCE	2012 NFPA 2015 MICHIGAN BUILDI ANSI A117.1 2015 PLUMBING CODE 2015 ELECTRICAL CODE 2015 MECHANICAL CO	E DE		
DESCRIPTION	REFERENCE	EXISTING	NEW ADDITION	REMARKS
OCCUPANCY CLASSIFICATION	MBC 303.3 / 308.4	I-2 CONDITION 1	A-2	ASSEMBLY - DINING FACILITY & ASSOCATED KITCHEN / INSTITUTIONAL - PSYCHIATRIC HOSPITAL
CONSTRUCTION TYPE	MBC 601	IB	IIB	TYPE IIB: RATING FOR BLDG ELEMENTS = 0-HOUR TYPE IB: RATING FOR BLDG ELEMENTS = 2-HOUR EXCEPTION: NONBEAR INT WALLS = 0-HOUR ROOF = 1-HOUR
NONBEARING EXTERIOR WALL SEPARATION	MBC 602	IB:I > 30 FT = 0-HOUR	IIB:A = 0-HOUR	
FEATURES OF FIRE PROTECTION		FULLY SPRINKLED		
BUILDING HEIGHT	MBC 504.4	ALLOWED - 5 STORIES 180 FT.	- ALLOWED - 3 STORIES - 75 FT.	A-2: ACTUAL - 1 STORY - 18 FT.
BUILDING AREA	MBC 506.2	UNLIMITED	ALLOWED - 38,000 S.F.	A-2: ACTUAL - 11,124 S.F.
SEPARATED OCCUPANCIES	MBC 508.4	I-2	A-2	2-HOUR FIRE BARRIER SEPARATION TO COMPLY WITH A-2 REQUIRMENTS
INCIDENTAL USE AREAS	MBC 509	INPUT = 1 HOUR OR SPR	OR 10 HORSEPOWER = 1	BUILDING FULLY SPRINKLERED
FIRE BARRIERS	MBC 707	SEPARATED OCCUPAN	CIES	CONTINUITY: TOP OF FND OR FLR/CLG ASSEMBLY TO UNDERSIDE OF FLR OR ROOF ABOVE - CONT THRU OUT CONCEALED SPACES
INTERIOR WALL/CEILING FINISHES	MBC TABLE 803.11	INTERIOR EXIT STAIRW CORRIDORS - B ROOMS AND ENCLOSED SPACES - B ADMIN - C ≤ 4 OCC C	AYS - B ROOMS AND ENCLOSED SPACES - C	
		STOR/MECH 1:300 S.F. (WAREHOUSE 1/500 S.F.		
OCCPANT LOAD	MBC 1004.1.2	INPAT 1:240 S.F. (GROSS SLEEPING 1/120 S.F. (GROSS)	KITCHEN 1:200 S.F. (GROSS) DINING ROOM/SERVING 1:5 S.F. (NET)	A-2 : TOTAL OCCUPANTS = 718
FIRE EXTINGUISHERS	NFPA 10	75' MAXIMUM DISTANCE	E APART	
COMMON PATH EGRESS TRAVEL	MBC 1006.2.1	75'		THAT PORTION OF THE EXIT ACCESS TRAVEIDISTANCE MEASURED FROM THE MOST REMOTE POINT WITHIN A STORY TO THAT POINT WHERE THE OCCUPANTS HAVE SEPARATE AND DISTINCT ACCESS TO TWO EXITS OR EXIT ACCESS DOOR-WAYS.
NUMBER OF EXITS	MBC 1006.3.1		REQUIRED: (1) KITCHEN (2) DINING	PROVIDED: (2) DINING ROOM (2) KITCHEN
EXIT ACCESS TRAVEL DISTANCE	MBC 1017.2	200 FT.	250 FT.	
CORRIDOR FIRE RESISTANCE	MBC 1020.1	w/ SPRINKLER = 0 HOU	R	FULLY SPRINKLERED
MINIMUM CORRIDOR WIDTH	MBC 1020.2	MIN. 44 INCHES MIN. 96 INCHES FOR		
DEAD END CORRIDORS	MBC 1020.4	BED CLEARANCE 20 FT.	1	
ACCESSIBILTY	MBC 1101.2		DESIGNED AND CONSTR	UCTED TO BE ACCESSIBLE
PLUMBING FIXTURES	MPC TABLE 403.1		NO ADDITIONAL STAFF FACILITY	OR PATIENTS ARE BEING ADDED TO THE
ENERGY EFFICIENCY	MEC		ROOF - INSULATION ENTIRELY ABOVE DECK = R-30 CI WALLS - MASS = R-11.4 C.I. SLAB ON GRADE = R-15 FOR 24IN.	








SECOND FLOOR CODE PLAN

SCALE: 1/8" = 1'-0"





NO.	REVISION	DATE
•		

STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR


FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255

Y22003

CONTRACT NO.

WTAARCH.COM







WTA ARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN


SALINE, MICHIGAN

SHEET TITLE FIRST FLOOR PARTIAL CODE PLAN

PROJECT NUMBER 2021094 PROJECT DATE SEPTEMBER 6, 2023

CHECKED BY C.D.S.

SHEET NUMBER



GENERAL DEMOLITION NOTES:

. THE CONTRACTOR SHALL PROVIDE ALL SHORING, TEMPORARY SUPPORTS, AND BRACING REQUIRED FOR THE SAFE DEMOLITION AND ERECTION OF

STRUCTURAL COMPONENTS. 2. ALL BUILDING MATERIAL BEING DEMOLISHED IS TO

BE DISPOSED OF BY THE CONTRACTOR, UNLESS NOTED OTHERWISE AND EXCLUDING THOSE ITEMS SALVAGED BY THE OWNER.

PROTECT ADJACENT MEMBERS, FINISHES, AND SURFACES FROM DAMAGE DURING DEMOLITION WORK. CONDUCT DEMOLITION TO MINIMIZE INTERFERENCE W/ ADJACENT STRUCTURAL MEMBERS, BUILDING AREAS, AND PUBLIC AND

EGRESS AND ACCESS AT ALL TIMES. PRIOR TO BEGINNING ANY DEMOLITION WORK PROVIDE TEMPORARY BARRIERS AS REQUIRED TO PREVENT MIGRATION OF DUST AND NOISE INTO ADJACENT AREAS, TO PREVENT UNAUTHORIZED

ACCESS INTO THE WORK AREA, AND TO PROTECT THE GENERAL PUBLIC. REFER TO MECHANICAL AND ELECTRICAL

DRAWINGS FOR ADDITIONAL DEMOLITION WORK.

1 REMOVE EXISTING DOOR, FRAME, AND ALL ASSOCIATED HARDWARE

2 REMOVE A PORTION OF EXISTING WALL CONSTRUCTION FOR NEW OPENING (REFER TO CONSTRUCTION PLAN)

3 REMOVE EXISTING CONCRETE ENTRY SLAB AND FOUNDATION 4 REMOVE EXISTING FENCE, REFER TO CIVIL FOR LOCATION OF TEMPORARY FENCING AND FOR FINAL FENCING LAYOUT - TEMPORY FENCING MUST BE IN PLACE PRIOR TO DEMOLITION OF FENCING BEGINS

5 REMOVE EXISTING FENCE AND GATE 6 REMOVE AND SALVAGE EXISTING SHELVING -RETURN TO OWNER

7 REMOVE EXISTING WATER RESISTANT DAMPROOFING ALONG THE EXTENT OF THE FOUNDATION WALL - REFER TO CIVIL FOR COORDINATION OF SIDE WALK REMOVAL, ENTRY SLAB REMOVAL, AND FENCE MODIFICATIONS -PREP AREA FOR NEW DAMPROOFING (REFER TO CONSTRUCITON PLAN)

8 EXISTING CEILING TO REMAIN - MODIFY AS REQUIRED FOR NEW OPENINGS (REFER TO CONSTRUCTION PLAN).

REVISION

STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255

CONTRACT NO. Y22003

KEY PLAN
NOT TO SCALE

WTAARCH.COM

COPYRIGHT © 2023

WTA ARCHITECTS 100 S Jefferson Ave, Suite 601

Saginaw, Michigan 48607 989 752 8107

491/20167.SDW - PHASE 500:


CENTER FOR FORENSIC PSYCHIATRY - CREATE

KITCHEN SALINE, MICHIGAN

FIRST FLOOR **DEMOLITION PLAN**

PROJECT NUMBER 2021094 SHEET NUMBER PROJECT DATE

A2.11 SEPTEMBER 6, 202



CONSTRUCTION GENERAL NOTES:

- WALL TYPES ARE INDICATED AS A DIAMOND WITH A NUMBER. REFER TO SHEET A0.01 FOR DESCRIPTION OF WALL TYPES.
- PLAN DIMENSIONS DO NOT INCLUDE WALL THICKNESS (REFER TO WALL TYPES).
- DOOR FRAMES ARE TO BE LOCATED 8" FROM THE PERPENDICULAR WALL ON THE HINGE SIDE OF THE DOOR AT MASONRY WALLS, UNLESS NOTED OTHERWISE.
- PROVIDE BLOCKING AT ALL WALL MOUNTED ITEMS INCLUDING BUT NOT LIMITED TO: PLUMBING
- ACCESSORIES, KITCHEN EQUIPMENT, ETC. ALL AREAS DAMAGED BY DEMOLITION WORK ARE
- TO BE PATCHED AND REPAIRED OR REPLACED TO MATCH ADJACENT SURFACES. PATCH AND REPAIR REMAINING WALLS; AT
- DEMOLITION POINTS WITH SIMILAR MATERIALS IN SIZE, COLOR AND TEXTURE. PATCH AND REPAIR ALL EXISTING FLOORS AS

ARCHITECTURAL, MECHANICAL, AND ELECTRICAL

- REQUIRED WHERE EXISTING WALLS HAVE BEEN
- FURNITURE OR EQUIPMENT TO BE BUILT AND/ORG INSTALLED BY CONTRACTOR IS SPECIFICALLY NOTED, DIMENSIONED OR DETAILED. ALL OTHER
- FURNITURE OR EQUIPMENT WILL BE PROVIDED AND INSTALLED BY OWNER. FOR CASEWORK DETAILS - REFER TO "NORTHERN AMERICA ARCHITECTURAL WOODWORK
- 10. CASEWORK DESIGNATION REFERS TO THE WIDTH (W) AND DEPTH (D) OF THE CABINET. REFER TO DIMENSIONS FOR HEIGHT. REFER TO "A.W.S." FOR CABINET NUMBER LOCATED BELOW DIMENSION

| CONSTRUCTION KEYNOTES

- CONCRETE ENTRY SLAB (REFER TO STRUCTURAL) 2 PLUMBING FIXTURE (REFER TO MECHANICAL)
- 4 CASEWORK (REFER TO ELEVATIONS AND DETAILS) 5 STAINLESS STEEL GRAB BARS 6 PAPER TOWEL DISPENSER
- 7 TOILET PAPER DISPENSER 8 SANITARY NAPKIN RECEPTICLE

STANDARDS (A.W.S.).


- 9 MIRROR 18" x 36" 10 SOAP DISPENSER
- 11 RECESSED FIRE EXTINGUISHER CABINET 12 FURNITURE AND EQUIPMENT (BY OWNER)
- 13 SEMI-RECESSED DETENTION FIRE EXTINGUISHER
- 14 PATCH AND REPAIR WALL CONSTRUCTION, WALL BASE, AND FLOORING TO MATCH EXISTING. 15 COORDINATE LOCATION OF FLOOR TILE MOVEMENT JOINTS WITH ARCHITECT, TYPICAL OF
- TCNA EJ-171 16 FIN TUBE RADIATOR (REFER TO MECHANICAL) 17 PROVIDE NEW WATER COLD FLUID-APPLIED
- WATERPROOFING ALONG THE EXENT OF THE EXISTING FOUNDATION WALL - REFER TO CIVIL FOR COORDINATION OF NEW SIDEWALK, NEW ENTRY SLAB, AND FENCE MODIFICATIONS - USE

CAUTION AS UNDERGROUND LINES ARE LOCATED

- 18 MECHANICAL CHASE VERIFY SIZE WITH KITCHEN EQUIPMETN MFR. AND MECHANICAL (REFER TO
- 19 MECHANICAL CHASE VERIFY CLEAR WIDTH REQUIRED WITH MECHANICAL (REFER TO MECHANICAL)

IN THIS AREA.

20 EYE WASH STATION (REFER TO FOOD SERVICE AND MECHANICAL) 21 SEMI-RECESSED WET CHEMICAL FIRE EXTINGUISHER CABINET



STATE OF MICHIGAN DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION


REVISION

ADAM LACH, RA, DIRECTOR

491/20167.SDW

FUNDING CODE

CONTRACT NO. Y22003 171CODHHS7255





WTAARCH.COM

COPYRIGHT © 2023

WTA ARCHITECTS

100 S Jefferson Ave, Suite 601

Saginaw, Michigan 48607 989 752 8107

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN


SALINE, MICHIGAN

SHEET TITLE FIRST FLOOR CONSTRUCTION PLAN

PROJECT NUMBER 2021094 SHEET NUMBER

CHECKED BY C.D.S.

SEPTEMBER 6, 202



CONSTRUCTION GENERAL NOTES:


- WALL TYPES ARE INDICATED AS A DIAMOND WITH A NUMBER. REFER TO SHEET A0.01 FOR DESCRIPTION OF WALL TYPES.
- PLAN DIMENSIONS DO NOT INCLUDE WALL THICKNESS (REFER TO WALL TYPES).
- DOOR FRAMES ARE TO BE LOCATED 8" FROM THE PERPENDICULAR WALL ON THE HINGE SIDE OF THE DOOR AT MASONRY WALLS, UNLESS NOTED OTHERWISE.
- PROVIDE BLOCKING AT ALL WALL MOUNTED ITEMS INCLUDING BUT NOT LIMITED TO: PLUMBING
- ACCESSORIES, KITCHEN EQUIPMENT, ETC. ALL AREAS DAMAGED BY DEMOLITION WORK ARE
- TO BE PATCHED AND REPAIRED OR REPLACED TO MATCH ADJACENT SURFACES.
- 6. PATCH AND REPAIR REMAINING WALLS; AT ARCHITECTURAL, MECHANICAL, AND ELECTRICAL DEMOLITION POINTS WITH SIMILAR MATERIALS IN SIZE, COLOR AND TEXTURE.
- PATCH AND REPAIR ALL EXISTING FLOORS AS REQUIRED WHERE EXISTING WALLS HAVE BEEN
- 8. FURNITURE OR EQUIPMENT TO BE BUILT AND/ORG
- INSTALLED BY CONTRACTOR IS SPECIFICALLY NOTED, DIMENSIONED OR DETAILED. ALL OTHER FURNITURE OR EQUIPMENT WILL BE PROVIDED AND INSTALLED BY OWNER.
- FOR CASEWORK DETAILS REFER TO "NORTHERN AMERICA ARCHITECTURAL WOODWORK STANDARDS (A.W.S.).
- 10. CASEWORK DESIGNATION REFERS TO THE WIDTH (W) AND DEPTH (D) OF THE CABINET. REFER TO DIMENSIONS FOR HEIGHT. REFER TO "A.W.S." FOR CABINET NUMBER LOCATED BELOW DIMENSION

CONSTRUCTION KEYNOTES

- 1 CONCRETE ENTRY SLAB (REFER TO STRUCTURAL) 2 PLUMBING FIXTURE (REFER TO MECHANICAL) 4 CASEWORK (REFER TO ELEVATIONS AND DETAILS)
- 5 STAINLESS STEEL GRAB BARS 6 PAPER TOWEL DISPENSER 7 TOILET PAPER DISPENSER
- 8 SANITARY NAPKIN RECEPTICLE 9 MIRROR 18" x 36"
- 10 SOAP DISPENSER 11 RECESSED FIRE EXTINGUISHER CABINET
- 12 FURNITURE AND EQUIPMENT (BY OWNER) 13 SEMI-RECESSED DETENTION FIRE EXTINGUISHER
- 14 PATCH AND REPAIR WALL CONSTRUCTION, WALL BASE, AND FLOORING TO MATCH EXISTING.
- 15 COORDINATE LOCATION OF FLOOR TILE MOVEMENT JOINTS WITH ARCHITECT, TYPICAL OF TCNA EJ-171
- 16 FIN TUBE RADIATOR (REFER TO MECHANICAL) 17 PROVIDE NEW WATER COLD FLUID-APPLIED WATERPROOFING ALONG THE EXENT OF THE EXISTING FOUNDATION WALL - REFER TO CIVIL FOR COORDINATION OF NEW SIDEWALK, NEW ENTRY SLAB, AND FENCE MODIFICATIONS - USE
- IN THIS AREA. 18 MECHANICAL CHASE VERIFY SIZE WITH KITCHEN EQUIPMETN MFR. AND MECHANICAL (REFER TO

CAUTION AS UNDERGROUND LINES ARE LOCATED

- 19 MECHANICAL CHASE VERIFY CLEAR WIDTH
- REQUIRED WITH MECHANICAL (REFER TO MECHANICAL)
- 20 EYE WASH STATION (REFER TO FOOD SERVICE AND MECHANICAL) 21 SEMI-RECESSED WET CHEMICAL FIRE EXTINGUISHER CABINET




STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION

ADAM LACH, RA, DIRECTOR

491/20167.SDW FUNDING CODE

CONTRACT NO.





WTAARCH.COM

KEY PLAN NOT TO SCALE

COPYRIGHT © 2023

WTA ARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607

989 752 8107

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE

KITCHEN SALINE, MICHIGAN

SHEET TITLE


SECOND FLOOR CONST. PLN, ENLARGED PLN, & INTERIOR ELEVATION

PROJECT NUMBER 2021094 PROJECT DATE

CHECKED BY C.D.S.

SEPTEMBER 6, 202

SHEET NUMBER



FLOORING LEGEND CERAMIC TILE SEALED CONCRETE RESILIENT SHEET FLOORING RESILIENT TILE FLOORING

A3	ADDENDUM NO. 3	09/28/23
NO.	REVISION	DATE


STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255

Y22003

CONTRACT NO.





WTAARCH.COM

WTA ARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN


SHEET TITLE

C.D.S.

FIRST & SECOND FLOOR FLOORING PLANS

PROJECT NUMBER 2021094 SHEET NUMBER PROJECT DATE SEPTEMBER 6, 202

CHECKED BY



MATERIAL KEYNOTES

- 1 EXISTING TO REMAIN
- 2 FULLY ADHEARED SINGLE PLY MEMBRANE
- ROOFING
- 3 3/4" ROOFING BOARD 4 RIDGID ROOF INSULATION R-30
- 5 METAL DECK (REFER TO STRUCTURAL) 6 2x PRESSURE TREATED WOOD BLOCKING
- 7 SPRAY INSULATION IN METAL DECK FLUTES TO
- ALLOW FOR CONTINUOUS INSULATION 8 STEEL LINTEL - EXTERIOR STEEL LINTELS TO BE GALVANIZED - PAINT (REFER TO STRUCTUAL)
- 9 GROUT SOLID 10 THRU WALL FLASHING
- 11 MORTAR NET
- 12 FACE BRICK MATCH EXISTING 13 8x24 BURNISHED BLOCK ACCENT BAND - MATCH
- EXISTING 14 8x24 SPLIT FACE BLOCK WAINSCOT - MATCH
- **EXISTING**
- 15 SEALANT OVER BACKER ROD EXTERIOR / CAULK
- INTERIOR TYPICAL AT ALL WINDOWS AND DOORS 16 ALUMINIUM WINDOW SYSTEM WITH INSULATED
- GLAZING 17 BRICK VENT
- 18 BULLNOSE
- 19 BOND BREAK 20 4" CONCRETE SLAB ON VAPOR BARRIER (REFER TO STRUCTURAL)
- 21 PERIMETER INSULATION EXTEND 2'-0" IN BOTH DIRECTIONS
- 22 COMPACTED GRANULAR FILL
- 23 GRADE (REFER TO CIVIL) 24 POURED CONCRETE FOUNDATION WALL (REFER
- TO STRUCTURAL)
- 25 BITUMINOUS DAMPPROOFING
- 26 STEEL COLUMN (REFER TO STRUCTURAL)
- 27 RIGID INSULATION
- 28 CONTINUOUS METAL ROOF EDGE MATCH
- EXISTING PROFILE AT CONNECTION POINTS ALSO
- MATCH EXISTING HEIGHT (V.I.F.)
- 29 NEW FENCE (REFER TO CIVIL AND ELECTRICAL).

- 30 CONCRETE MASONRY UNIT
- 31 COLD FORMED METAL FRAMING
- 32 DOOR AND FRAME (REFER TO SCHEDULE)
- 33 2" EXPANSION JOINT / CONTROL JOINT AS REQUIRED - FIRE RATE AS REQUIRED (REFER TO
- CODE PLAN) 34 LIGHT FIXTURE (REFER TO ELECTRICAL)
- 35 MECHANICAL ITEM (REFER TO MECHANICAL) 36 POURED CONCRETE FOOTING (REFER TO
- STRUCTURAL) 37 STEEL ANGLE (REFER TO STRUCTURAL)
- 38 STEEL TUBE (REFER TO STRUCTURAL)
- 39 STEEL JOIST (REFER TO STRUCTURAL)
- 40 STEEL BEAM (REFER TO STRUCTURAL)
- 41 SUSPENDED CEILING SYSTEM (REFER TO SCHEDULE)
- 42 LOUVER (REFER TO MECHANICAL)
- 43 BOND BEAM WITH (2) #5 CONT, GROUT SOLID (REFER TO STRUCTURAL)
- 44 CMU FOUNDATION WALL (REFER TO STRUCTURAL) 45 ROOF LADDER - ATTACH AND FLASH AS REQUIRED
- PER MANUFACTURER'S RECOMMENDATIONS (REFER TO REFERENCE ONLY DETAIL)
- 46 WALL MOUNTED ELECTRICAL ITEM (REFER TO
- ELECTRICAL) 47 CEILING MOUNTED ELECTRICAL ITEM (REFER TO
- 48 PLUMBING FIXTURE AND ACCESSORIES (REFER TO MECHANICAL & STANDARD MOUNTING HEIGHTS
- 49 BASE MATERIAL (REFER TO SCHEDULE) 50 CONTROL JOINT

).	REVISION	DATE

STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION

DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

491/20167.SDW

FUNDING CODE 171CODHHS7255



WTAARCH.COM

CONTRACT NO.

Y22003

WTA ARCHITECTS

100 S Jefferson Ave, Suite 601

Saginaw, Michigan 48607 989 752 8107 COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500: CENTER FOR FORENSIC PSYCHIATRY - CREATE


KITCHEN SALINE, MICHIGAN

SHEET TITLE

PLAN DETAILS

PROJECT NUMBER 2021094 SHEET NUMBER

PROJECT DATE A2.31 SEPTEMBER 6, 202 CHECKED BY C.D.S.



SCHEDULE GENERAL NOTES:

1. FINAL LOCATIONS OF DOOR CARD READERS, DOOR INTERCOMS AND PUSH BUTTONS TO BE

FIELD VERIFIED WITH OWNER.

 REFER TO SHEET A0.01 AND MATERIAL SCHEDULE (THIS SHEET) FOR ABBREVIATIONS.

3. WALL TYPES ARE INDICATED w/ A DIAMOND AND A NUMBER. REFER TO SHEET A0.01 FOR DESCRIPTION OF WALL TYPES.

SCHEDULE OF REMARKS:

A. PROVIDE DOOR CLOSER.

B. PROVIDE HOLD OPEN w/ CLOSER TIED INTO FIRE

C. PROVIDE A CARD READER INSIDE AND OUTSIDE.

D. PROVIDE A DOOR INTERCOM w/ PUSH BUTTON INSIDE AND OUTSIDE.

(E. REINFORCED DETENTION DOOR.)

F. PROVIDE A DOOR INTERLOCKS INSIDE AND OUTSIDE

G. PROVIDE AN ELECTRIC LOCK.

H. PROVIDE A MORTISE LOCK.

NOT USED.

....

J. PROVIDE A CARD READER OUTSIDE.K. PROVIDE A PUSH BAR ON INSIDE.

L. PROVIDE HOLD-DOWN CLIPS FOR S.A.T. CEILING IN AREA NEAR EXTERIOR DOORS IN QUANTITY AND SPACING REQUIRED TO PREVENT MOVEMENT / UPLIFT OF CEILING TILES.

M. CEILING HEIGHT VARIES (REFER TO CEILING PLAN).
 N. RSF FLOORING INCLUDES: Z-BAR COVE CAP, S.S. CORNER GUARDS @ COVE BASE CORNERS, AND S.S. TRANSITIONS STRIPS AT ALL FLOOR MATERIAL

O. PATCH AND REPAIR AT DEMOLITION POINTS.

P. PROVIDE AN INTERLOCK INSIDE.

TRANSITIONS; BY FLR'G MFR.

Q. PROVIDED AN INTERCOM w/ PUSH BUTTON INSIDER. DOOR LITE TO BE GL-1 (REFER TO SPECS).

S. DOOR LITE TO BE GL-2 (REFER TO SPECS).

T. DOOR LITE TO BE GL-3 (REFER TO SPECS).

U. DOOR LITE TO BE GL-4 (REFER TO SPECS).

(V. `DOOR LITE TO BE GL-5 (RÉFER TÓ SPECS).

W. DOOR LITE TO BE GL-6 (REFER TO SPECS).

X. PROVIDE DOOR STOP (REFER TO SPECS).

Y. PROVIDE CLOSER AND HOLD OPEN.

A3	ADDENDUM NO. 3	09/28/23
NO.	REVISION	DATE

DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION
DESIGN AND CONSTRUCTION DIVISION
ADAM LACH, RA, DIRECTOR

STATE OF MICHIGAN

FILE NO. 491/20167.SDW

FUNDING CODE

FUNDING CODE CONTRACT NO. 171CODHHS7255 Y22003

WTAARCH.COM

WTA ARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607

989 752 8107 COPYRIGHT © 2023

PROJECT TITLE
491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE

KITCHEN
SALINE, MICHIGAN


ROOM FINISH & DOOR SCHEDS, DOOR & WDW


TYPES, AND DOOR DTLS

PROJECT NUMBER SHEET NUMBER 2021094


C.D.S.

PROJECT DATE
SEPTEMBER 6, 2023
CHECKED BY









STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

CONTRACT NO.

Y22003

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255

WTAARCH.COM

WTA ARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607

989 752 8107 COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN


SALINE, MICHIGAN


C.D.S.


SHEET TITLE VERTICAL CIRCULATION


PROJECT NUMBER 2021094 SHEET NUMBER PROJECT DATE SEPTEMBER 6, 2023


A4.01 CHECKED BY













PERSPECTIVE VIEW - NORTHEAST ELEVATION



PERSPECTIVE VIEW - SOUTHEAST VIEW




MATERIAL KEYNOTES

- 1 EXISTING TO REMAIN 2 FULLY ADHEARED SINGLE PLY MEMBRANE
- ROOFING
- 3 3/4" ROOFING BOARD

4 RIDGID ROOF INSULATION R-30

- 5 METAL DECK (REFER TO STRUCTURAL) 6 2x PRESSURE TREATED WOOD BLOCKING
- 7 SPRAY INSULATION IN METAL DECK FLUTES TO ALLOW FOR CONTINUOUS INSULATION 8 STEEL LINTEL - EXTERIOR STEEL LINTELS TO BE
- GALVANIZED PAINT (REFER TO STRUCTUAL)
- 9 GROUT SOLID 10 THRU WALL FLASHING
- 11 MORTAR NET
- 12 FACE BRICK MATCH EXISTING 13 8x24 BURNISHED BLOCK ACCENT BAND - MATCH
- EXISTING 14 8x24 SPLIT FACE BLOCK WAINSCOT - MATCH
- EXISTING
- 15 SEALANT OVER BACKER ROD EXTERIOR / CAULK
- INTERIOR TYPICAL AT ALL WINDOWS AND DOORS
- 16 ALUMINIUM WINDOW SYSTEM WITH INSULATED GLAZING
- 17 BRICK VENT 18 BULLNOSE
- 19 BOND BREAK
- 20 4" CONCRETE SLAB ON VAPOR BARRIER (REFER
- TO STRUCTURAL) 21 PERIMETER INSULATION - EXTEND 2'-0" IN BOTH
- DIRECTIONS 22 COMPACTED GRANULAR FILL
- 23 GRADE (REFER TO CIVIL)
- 24 POURED CONCRETE FOUNDATION WALL (REFER
- TO STRUCTURAL)
- 25 BITUMINOUS DAMPPROOFING 26 STEEL COLUMN (REFER TO STRUCTURAL)
- 27 RIGID INSULATION
- 28 CONTINUOUS METAL ROOF EDGE MATCH
- EXISTING PROFILE AT CONNECTION POINTS ALSO
- MATCH EXISTING HEIGHT (V.I.F.)
- 29 NEW FENCE (REFER TO CIVIL AND ELECTRICAL).
- 30 CONCRETE MASONRY UNIT
- 31 COLD FORMED METAL FRAMING
- 32 DOOR AND FRAME (REFER TO SCHEDULE)
- 33 2" EXPANSION JOINT / CONTROL JOINT AS REQUIRED - FIRE RATE AS REQUIRED (REFER TO
- CODE PLAN) 34 LIGHT FIXTURE (REFER TO ELECTRICAL)
- 35 MECHANICAL ITEM (REFER TO MECHANICAL)
- 36 POURED CONCRETE FOOTING (REFER TO STRUCTURAL)
- 37 STEEL ANGLE (REFER TO STRUCTURAL) 38 STEEL TUBE (REFER TO STRUCTURAL)
- 39 STEEL JOIST (REFER TO STRUCTURAL)
- 40 STEEL BEAM (REFER TO STRUCTURAL)
- 41 SUSPENDED CEILING SYSTEM (REFER TO SCHEDULE)
- 42 LOUVER (REFER TO MECHANICAL) 43 BOND BEAM WITH (2) #5 CONT, GROUT SOLID (REFER TO STRUCTÚRAL)
- 44 CMU FOUNDATION WALL (REFER TO STRUCTURAL)
- 45 ROOF LADDER ATTACH AND FLASH AS REQUIRED PER MANUFACTURER'S RECOMMENDATIONS
- (REFER TO REFERENCE ONLY DETAIL) 46 WALL MOUNTED ELECTRICAL ITEM (REFER TO
- ELECTRICAL) 47 CEILING MOUNTED ELECTRICAL ITEM (REFER TO
- ELECTRICAL)
- 48 PLUMBING FIXTURE AND ACCESSORIES (REFER TO MECHANICAL & STANDARD MOUNTING HEIGHTS
- 49 BASE MATERIAL (REFER TO SCHEDULE) 50 CONTROL JOINT



DESIGN AND CONSTRUCTION DIVISION

CONTRACT NO.


STATE OF MICHIGAN DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET

ADAM LACH, RA, DIRECTOR


FILE NO. 491/20167.SDW

FUNDING CODE

171CODHHS7255 Y22003







WTA ARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

SHEET TITLE EXTERIOR ELEVATIONS

PROJECT NUMBER 2021094


PROJECT DATE


A5.01


SHEET NUMBER


SEPTEMBER 6, 202 CHECKED BY C.D.S.

WEST EXTERIOR ELEVATION 25/A5.01 SCALE: 1/8" = 1'-0"









(#) MATERIAL KEYNOTES

1 EXISTING TO REMAIN 2 FULLY ADHEARED SINGLE PLY MEMBRANE

ROOFING

3 3/4" ROOFING BOARD 4 RIDGID ROOF INSULATION R-30

5 METAL DECK (REFER TO STRUCTURAL) 6 2x PRESSURE TREATED WOOD BLOCKING

7 SPRAY INSULATION IN METAL DECK FLUTES TO

ALLOW FOR CONTINUOUS INSULATION

8 STEEL LINTEL - EXTERIOR STEEL LINTELS TO BE GALVANIZED - PAINT (REFER TO STRUCTUAL)

9 GROUT SOLID

10 THRU WALL FLASHING 11 MORTAR NET

12 FACE BRICK - MATCH EXISTING 13 8x24 BURNISHED BLOCK ACCENT BAND - MATCH

EXISTING 14 8x24 SPLIT FACE BLOCK WAINSCOT - MATCH

EXISTING

15 SEALANT OVER BACKER ROD EXTERIOR / CAULK

INTERIOR - TYPICAL AT ALL WINDOWS AND DOORS

16 ALUMINIUM WINDOW SYSTEM WITH INSULATED GLAZING

17 BRICK VENT 18 BULLNOSE

19 BOND BREAK 20 4" CONCRETE SLAB ON VAPOR BARRIER (REFER

TO STRUCTURAL) 21 PERIMETER INSULATION - EXTEND 2'-0" IN BOTH

DIRECTIONS 22 COMPACTED GRANULAR FILL

23 GRADE (REFER TO CIVIL) 24 POURED CONCRETE FOUNDATION WALL (REFER

TO STRUCTURAL) 25 BITUMINOUS DAMPPROOFING

26 STEEL COLUMN (REFER TO STRUCTURAL)

27 RIGID INSULATION

28 CONTINUOUS METAL ROOF EDGE - MATCH

EXISTING PROFILE - AT CONNECTION POINTS ALSO

MATCH EXISTING HEIGHT (V.I.F.) 29 NEW FENCE (REFER TO CIVIL AND ELECTRICAL).

31 COLD FORMED METAL FRAMING 32 DOOR AND FRAME (REFER TO SCHEDULE)

33 2" EXPANSION JOINT / CONTROL JOINT AS REQUIRED - FIRE RATE AS REQUIRED (REFER TO

30 CONCRETE MASONRY UNIT

CODE PLAN) 34 LIGHT FIXTURE (REFER TO ELECTRICAL)

35 MECHANICAL ITEM (REFER TO MECHANICAL) 36 POURED CONCRETE FOOTING (REFER TO

STRUCTURAL) 37 STEEL ANGLE (REFER TO STRUCTURAL)

38 STEEL TUBE (REFER TO STRUCTURAL) 39 STEEL JOIST (REFER TO STRUCTURAL) 40 STEEL BEAM (REFER TO STRUCTURAL)

41 SUSPENDED CEILING SYSTEM (REFER TO SCHEDULE) 42 LOUVER (REFER TO MECHANICAL)

43 BOND BEAM WITH (2) #5 CONT, GROUT SOLID (REFER TO STRUCTURAL) 44 CMU FOUNDATION WALL (REFER TO STRUCTURAL) 45 ROOF LADDER - ATTACH AND FLASH AS REQUIRED

PER MANUFACTURER'S RECOMMENDATIONS (REFER TO REFERENCE ONLY DETAIL) 46 WALL MOUNTED ELECTRICAL ITEM (REFER TO

ELECTRICAL) 47 CEILING MOUNTED ELECTRICAL ITEM (REFER TO

ELECTRICAL) 48 PLUMBING FIXTURE AND ACCESSORIES (REFER TO MECHANICAL & STANDARD MOUNTING HEIGHTS

49 BASE MATERIAL (REFER TO SCHEDULE)

50 CONTROL JOINT

NO.	REVISION	DATE

STATE OF MICHIGAN DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION

ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE Y22003 171CODHHS7255

CONTRACT NO.



WTAARCH.COM

WTA ARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607

989 752 8107 COPYRIGHT © 2023

PROJECT TITLE 491/20167.SDW - PHASE 500:


CENTER FOR FORENSIC PSYCHIATRY - CREATE

KITCHEN SALINE, MICHIGAN

SHEET TITLE **BUILDING SECTIONS**


PROJECT NUMBER 2021094 SHEET NUMBER PROJECT DATE

A5.11 SEPTEMBER 6, 202 CHECKED BY C.D.S.



ROOF PLAN GENERAL NOTES:

I. PROVIDE FLASHING PER MANUFACTURER'S RECOMMENDATIONS AT WALLS, ROOF PENETRATIONS (MECHANICAL AND ELECTRICAL),



NOTE: WALL TYPES ARE INDICATED w/ A MATERIAL KEYNOTES

EXISTING PROFILE - AT CONNECTION POINTS ALSO

REQUIRED - FIRE RATE AS REQUIRED (REFER TO

45 ROOF LADDER - ATTACH AND FLASH AS REQUIRED PER MANUFACTURER'S RECOMMENDATIONS

COPYRIGHT © 2023

NOTE: WALL TYPES ARE INDICATED w/ A DIAMOND AND A NUMBER - REFER TO A0.01 FOR DESCRIPTION OF WALL TYPES NOTE: ALL EXISTING ROOF WARRANTIES MUST BE MAINTAINED AT CONNECTION POINTS GALVANIZED - PAINT (REFER TO STRUCTUAL) EXISTING EXISTING 16 ALUMINIUM WINDOW SYSTEM WITH INSULATED GLAZING 17 BRICK VENT 18 BULLNOSE 19 BOND BREAK TO STRUCTURAL) DIRECTIONS 27 RIGID INSULATION —PATCH & REPAIR EXISTING ROOF CONSTRUCTION AS REQUIRED AT REMOVAL OF EXISTING METAL EDGE. THE EXISTING ROOF WARRANTY MUST BE MAINTAINED FOR PATCH & 32 DOOR AND FRAME (REFER TO SCHEDULE) 33 2" EXPANSION JOINT / CONTROL JOINT AS —PLY WOOD ON BOTH SIDES OF PRESSURE TREATED WOOD FRAMING WITH SPRAY INSULATION BEYOND \sim 27angleSLOPED ∕──⟨27⟩R-30 SCHEDULE) W. CONN. B.O. DECK 118' - 8" 44 CMU FOUNDATION WALL (REFER TO STRUCTURAL) ELECTRICAL) ELECTRICAL) 49 BASE MATERIAL (REFER TO SCHEDULE) ADAM LACH, RA, DIRECTOR FILE NO. FUNDING CODE ___(32)PORTAL EQUAL Saginaw, Michigan 48607 989 752 8107 PROJECT TITLE 1ST FLOOR 100' - 0" SHEET TITLE 4 4 4 PROJECT DATE SEPTEMBER 6, 202 CHECKED BY C.D.S.

18 ROOF DETAIL
A7.02 SCALE: 1 1/2" = 1'-0"

PROVIDE RATED EXPANSION — JOINT AND REGLET FLASHING BETWEEN EXISTING AND NEW BUILDINGS **BUILDING** BEYOND (28)— These documents are approved for compliance with the STATE OF MICHIGAN BUILDING CODE subject to field inspection and the conditions of approval. $SLOPED\langle 27 \rangle$ W. CONN. B.O. DECK 118' - 8" R-30(27)— S. CONN. B.O. DECK 113' - 4" **40**> PATCH & REPAIR EXISTING WALL -CONSTRUCTION PATCH & REPAIR EXISTING — WALL CONSTRUCTION AS REQUIRED AT REMOVAL OF CONCRETE HEADER FOR PORTAL -FRAME (REFER TO STRUCTURAL) EXISTING WINDOW SECOND FLOOR 114' - 0" ROOF DETAIL
SCALE: 1 1/2" = 1'-0" S. CONN. B.O. DECK 113' - 4"

> ∕—IF DAMAGED DURING CONSTRUCTION - PATCH AND REPAIR 2.0 —PATCH & REPAIR EXISTING WALL CONSTRUCTION AS REQUIRED

> > HEAD DETAIL
> > SCALE: 1 1/2" = 1'-0"

REMOVE EXISTING SOFFIT CONSTRUCTION AND INSULATION AND CONTINUE RATED MASONRY CONSTRUCTION TIGHT TO UNDERSIDE OF FLOOR STRUCTURE ABOVE

1ST FLOOR 100' - 0"

B.O.FOOTING REFER TO STRUC.

WALL SECTION SOUTH CONNECTOR

SCALE: 1/2" = 1'-0"

33

UNIT-E B.O.SOFFIT 109' - 4"

PATCH & REPAIR EXISTING ——CONSTRUCTION AT REMOVAL OF EXISTING WALL - GRIND 1 SMOOTH (REFER TO STRUCTURAL) (2) 5/8" DOWELS 8" LONG w/ 4" -1ST FLOOR 100' - 0"

B.O.FOOTING REFER TO STRUC.

WALL SECTION WEST CONNECTOR

30 SILL DETAIL
A7.02 SCALE: 1 1/2" = 1'-0"

MATERIAL KEYNOTES

EXISTING TO REMAIN

2 FULLY ADHEARED SINGLE PLY MEMBRANE

3/4" ROOFING BOARD 4 RIDGID ROOF INSULATION R-30

5 METAL DECK (REFER TO STRUCTURAL)

6 2x PRESSURE TREATED WOOD BLOCKING 7 SPRAY INSULATION IN METAL DECK FLUTES TO

ALLOW FOR CONTINUOUS INSULATION 8 STEEL LINTEL - EXTERIOR STEEL LINTELS TO BE

9 GROUT SOLID 10 THRU WALL FLASHING

11 MORTAR NET 12 FACE BRICK - MATCH EXISTING

13 8x24 BURNISHED BLOCK ACCENT BAND - MATCH

14 8x24 SPLIT FACE BLOCK WAINSCOT - MATCH

15 SEALANT OVER BACKER ROD EXTERIOR / CAULK INTERIOR - TYPICAL AT ALL WINDOWS AND DOORS

20 4" CONCRETE SLAB ON VAPOR BARRIER (REFER

21 PERIMETER INSULATION - EXTEND 2'-0" IN BOTH

22 COMPACTED GRANULAR FILL 23 GRADE (REFER TO CIVIL)

24 POURED CONCRETE FOUNDATION WALL (REFER TO STRUCTURAL)

25 BITUMINOUS DAMPPROOFING

26 STEEL COLUMN (REFER TO STRUCTURAL)

28 CONTINUOUS METAL ROOF EDGE - MATCH EXISTING PROFILE - AT CONNECTION POINTS ALSO

MATCH EXISTING HEIGHT (V.I.F.) 29 NEW FENCE (REFER TO CIVIL AND ELECTRICAL).

30 CONCRETE MASONRY UNIT 31 COLD FORMED METAL FRAMING

REQUIRED - FIRE RATE AS REQUIRED (REFER TO CODE PLAN)

34 LIGHT FIXTURE (REFER TO ELECTRICAL) 35 MECHANICAL ITEM (REFER TO MECHANICAL)

36 POURED CONCRETE FOOTING (REFER TO STRUCTURAL) 37 STEEL ANGLE (REFER TO STRUCTURAL)

38 STEEL TUBE (REFER TO STRUCTURAL) 39 STEEL JOIST (REFER TO STRUCTURAL)

40 STEEL BEAM (REFER TO STRUCTURAL) 41 SUSPENDED CEILING SYSTEM (REFER TO

42 LOUVER (REFER TO MECHANICAL) 43 BOND BEAM WITH (2) #5 CONT, GROUT SOLID (REFER TO STRUCTURAL)

45 ROOF LADDER - ATTACH AND FLASH AS REQUIRED PER MANUFACTURER'S RECOMMENDATIONS (REFER TO REFERENCE ONLY DETAIL) 46 WALL MOUNTED ELECTRICAL ITEM (REFER TO

47 CEILING MOUNTED ELECTRICAL ITEM (REFER TO

48 PLUMBING FIXTURE AND ACCESSORIES (REFER TO MECHANICAL & STANDARD MOUNTING HEIGHTS

50 CONTROL JOINT

REVISION

STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION

491/20167.SDW

CONTRACT NO. 171CODHHS7255 Y22003

WTA ARCHITECTS

WTAARCH.COM

100 S Jefferson Ave, Suite 601

COPYRIGHT © 2023

491/20167.SDW - PHASE 500:


CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

WALL SECTIONS & DETAILS

PROJECT NUMBER 2021094 SHEET NUMBER

A7.02



REFLECTED CEILING LEGEND: LIGHT FIXTURES (REFER TO ELECTRICAL) SUPPLY AIR GRILLE (REFER TO MECHANICAL) RETURN AIR GRILLE / EXHAUST FAN (REFER TO MECHANICAL) CEILING ACCESS PANEL - COORDINATE LOCATIONS WHERE CEILING ACCESS IS **GENERAL CEILING NOTES:** . COORDINATE INSTALLATION OF SUSPENDED CEILING SYSTEM WITH MECHANICAL AND ELECTRICAL SYSTEMS. POSITION LIGHT FIXTURES IN CENTER OF CEILING TILES UNLESS NOTED OR DIMENSIONED OTHERWISE. . REFERENCE SPECIFICATIONS FOR SUSPENDED CEILING SYSTEM DESCRIPTION AND LOCATION REQUIREMENTS. . ELECTRICAL FIXTURES ARE SHOWN FOR LOCATION REFERENCE ONLY, REFER TO ELECTRICAL DRAWINGS AND SPECIFICATIONS FOR DETAILS. FIRE DEVICES AND EXIT LIGHTING NOT INDICATED ON ARCHITECTURAL DRAWINGS. REFER TO ELECTRICAL DRAWINGS FOR LOCATION, DETAILS, AND SPECIFICATIONS. . PROVIDE S.A.T. HOLD DOWN CLIPS AT EXTERIOR DOORS. REVISION STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR FILE NO. 491/20167.SDW FUNDING CODE CONTRACT NO. 171CODHHS7255 Y22003 KEY PLAN NOT TO SCALE WTAARCH.COM WTA ARCHITECTS 100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107 COPYRIGHT © 2023 PROJECT TITLE 491/20167.SDW - PHASE 500: CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN SALINE, MICHIGAN


SHEET TITLE FIRST & SECOND FLOOR REFLECTED CEILING PLAN


PROJECT NUMBER 2021094 SHEET NUMBER PROJECT DATE

C.D.S.

A9.01

SEPTEMBER 6, 2023 CHECKED BY





SALINE, MICHIGAN

KITCHEN EQUIPMENT PLAN

SEPTEMBER 6, 2023 FS2.01

SHEET NUMBER


SHEET TITLE


PROJECT NUMBER

2021094


PROJECT DATE

CHECKED BY T.M.M.





			VENT	ILA	TIO	N SCHE	DULE			
ITEM NO		' EQUIPMENT CATEGORY	HVAC EXHAUST DUCT SI ZE (I N)	HVAC EXHAUST CFM	HVAC EXHAUST SPWG	HVAC MAKE-UP DUCT SI ZE (I N)	HVAC MAKE-UP CFM	HVAC MAKE-UP SPWG	HVAC AFF (I N)	HVAC REMARKS
39.1	1	VENTILATION SYSTEM	16"DI A	2350	-0.764				DFA @ 113"-AFF	
39.1A						(4)12" X 20"	637(EA)	0.217	DFA @ 113"-AFF	
39.2			16"DI A	2750	-1.046				DFA @ 113"-AFF	
39.2A						(4)12" X 20"	637(EA)	0.217	DFA @ 113"-AFF	
39.3			14"DI A	1800	-0.666				DFA @ 113"-AFF	
39.3A						(3)10" X 24"	566(EA)	0.174	DFA @ 113"-AFF	
39.4			14"DI A	1800	-0.666				DFA @ 113"-AFF	
39.4A						(3)10" X 24"	633(EA)	0.215	DFA @ 113"-AFF	



Saginaw, Michigan 48607 989 752 8107 COPYRIGHT © 20 STAFFORD-SMITH, Inc.

WTAARCHITECTS

100 S Jefferson Ave, Suite 601

491/20167.SDW CFP - CREATE KITCHEN BID AND CONSTRUCTION:

CENTER FOR FORENSIC PSYCHIATRY


SALINE, MICHIGAN


SHEET TITLE

KITCHEN VENTILATION PLAN

PROJECT NUMBER SHEET NUMBER 2021094 PROJECT DATE

SEPTEMBER 6, 2023 FS2.04 CHECKED BY T.M.M.





A3 ADDENDUM NO. 3 09/28/23


M.T. TO EXTEND EVAPORATOR COIL DRAIN TO FUNNEL TYPE FLOOR DRAIN

STATE OF MICHIGAN DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255

CONTRACT NO. Y22003



WTAARCH.COM

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 COPYRIGHT © 20 989 752 8107

STAFFORD-SMITH, Inc

491/20167.SDW CFP - CREATE KITCHEN BID AND CONSTRUCTION: CENTER FOR FORENSIC **PSYCHIATRY**

SALINE, MICHIGAN


SHEET TITLE


KITCHEN PLUMBING PLAN


SHEET NUMBER PROJECT NUMBER 2021094


PROJECT DATE SEPTEMBER 6, 2023 **FS2.03** CHECKED BY

T.M.M.









STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET
FACILITIES AND BUSINESS SERVICES ADMINISTRATION
DESIGN AND CONSTRUCTION DIVISION
ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255

B G KEY PLAN NOT TO SCALE

CONTRACT NO.

Y22003



WTAARCH.COM

| WTA ARCHITECTS |

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607

989 752 8107 COPYRIGHT © 2023

MACMILLAN ASSOCIATES

MACMILLAN ASSOCIATES
CONSULTING ENGINEERS
714 EAST MIDLAND STREET • BAY CITY, MICHIGAN 48706
(989) 894-4300 F (989) 894-9930 WWW.MACMILLANASSOCIATES.COM

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE

KITCHEN

SALINE, MICHIGAN


FOUNDATION PLAN


PROJECT NUMBER
2021094

PROJECT DATE

SEPTEMBER 6, 2023

CHECKED BY
JAG





DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

491/20167.SDW

FUNDING CODE 171CODHHS7255

Y22003 KEY PLAN NOT TO SCALE

CONTRACT NO.

WTAARCH.COM



WTA A RCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607

COPYRIGHT © 2023 MACMILLAN ASSOCIATES CONSULTING ENGINEERS

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE

SALINE, MICHIGAN

ROOF FRAMING PLAN

PROJECT NUMBER SHEET NUMBER 2021094

- 1. VERIFY DIMENSIONS BEFORE COMMENCING WORK. REPORT DISCREPANCIES TO THE
- 2. VERIFY OPENINGS IN THE FRAMING PLANS WITH THE ARCHITECTURAL, MECHANICAL AND ELECTRICAL DRAWINGS.
- 3. ALL WORK SHALL CONFORM TO MICHIGAN BUILDING CODE 2015.

4. DESIGN LOADS

A. DESIGNED IN ACCORDANCE WITH MICHIGAN BUILDING CODE 2015. B. ROOF SNOW LOAD: GROUND SNOW LOAD PG = 20 PSF FLAT ROOF SNOW LOAD, PF = 20 PSF

SNOW EXPOSURE FACTOR, CE = 1.0 SNOW LOAD IMPORTANCE FACTOR, I = 1.1 THERMAL FACTOR, CT = 1.0 DRIFTED SNOW LOAD, SEE DIAGRAM THIS SHEET

C. FLOOR LIVE LOADS:

CORRIDOR, KITCHEN 100 PSF MECHANICAL ROOMS 125 PSF

D. WIND LOADS: BASIC WIND SPEED, VULT = 120 MPH WIND EXPOSURE C

INTERNAL PRESSURE COEFFICIENT, GC PI = +/-0.18 WALL COMPONENTS & CLADDING: **EFFECTIVE** POSITIVE

	WIND AREA (FT2)	PRESSURE (PSF)	PRESSURE (PS
-END ZONE	,	,	•
	10	33	-44
	20	32	-41
	50	30	-38
	100	29	-35
-INTERIOR Z	ZONE		
	10	33	-36
	20	32	-35
	50	30	-33
	100	29	-31

E. EARTHQUAKE DESIGN DATA: SEISMIC RISK CATEGORY, III

SEISMIC IMPORTANCE FACTOR, I = 1.25 SPECTRAL RESPONSE COEFFICIENTS: SDS = 0.104, SD1 = .08

BASIC SEISMIC - FORCE - RESISTING SYSTEM: SHEAR WALL, MOMENT FRAME SEISMIC DESIGN CATEGORY, B

SPECIAL INSPECTIONS:

- A. SPECIAL INSPECTIONS SHALL BE IN ACCORDANCE WITH THE MICHIGAN BUILDING CODE 2015 SECTION 1700. B. THE FOLLOWING TYPES OF WORK REQUIRE SPECIAL INSPECTIONS: (REFER TO THE BUILDING CODE AND SPECIFICATIONS FOR DETAILED INSPECTION REQUIREMENTS).
 - PREPARED FILL CONCRETE CONSTRUCTION.
 - 3. STEEL CONSTRUCTION. 4. MASONRY CONSTRUCTION

SPRAYED FIRERESISTIVE MATERIALS. **FOUNDATION NOTES**

- 1. FOUNDATIONS ARE DESIGNED BASED ON SOIL BEARING OF 2000 PSF. IF SOIL OF THIS CAPACITY IS NOT FOUND AT THE ELEVATION NOTED, ENLARGE OR LOWER FOOTINGS AT THE DIRECTION OF THE ARCHITECT/ENGINEER.
- 2. PLACE STRUCTURAL BACKFILL MEETING OR EXCEEDING MDOT CLASS II IN LAYERS NOT EXCEEDING 9" LOOSE THICKNESS. COMPACT EACH LAYER TO AT LEAST 95% OF THE MAXIMUM DENSITY PER ASTM D-1557. COMPACTING BY FLOODING IS NOT PERMITTED.
- 3. CENTER FOOTINGS UNDER WALL LOCATION AND COLUMNS UNLESS NOTED.
- 4. EARTH FORMS ARE NOT PERMITTED UNLESS SPECIFICALLY NOTED.
- 5. DISTURBANCE OF THE FOUNDATION BEARING SOILS SHALL BE AVOIDED.
- 6. EXISTING FOUNDATIONS OR FLOOR SLAB ENCOUNTERED DURING SITE GRADINGS AND EXCAVATION SHALL BE REMOVED TO A DEPTH OF TWO (2) FEET BELOW NEW CONSTRUCTION. REPLACE WITH STRUCTURAL BACKFILL.
- 7. PROVIDE BOND BREAK MATERIAL BETWEEN ALL GRADE SLABS AND VERTICAL
- 8. BACKFILL AND EXCAVATION PER SPECIFICATIONS.
- 9. FOLLOWING DEMOLITION OF STRUCTURES AND STRIPPING OF TOPSOIL, PREPARE SOILS IN ACCORDANCE WITH SOILS REPORT BY SME DATED FEBRUARY 9, 2022.

CONCRETE NOTES

- 1. ACI BUILDING CODE (318-14); MANUAL OF STANDARD PRACTICE FOR DETAILING (315) FOR THE MIXING, FABRICATION AND PLACEMENT OF CONCRETE, REINFORCING STEEL,
- 2. CONCRETE STRENGTH STANDARD WEIGHT CONCRETE: FOOTINGS, WALLS, PIERS: F'C = 3000 MINIMUM PSI F'C = 3500 MINIMUM PSI **CONCRETE SLABS ON GRADE:** EXTERIOR CONCRETE SLABS EXPOSED TO DE-ICING: F'C = 4500 MINIMUM PSI
- 3. REINFORCING BARS: ASTM A-615 GRADE 60 WELDED WIRE FABRIC: ASTM A-1064
- 4. CONCRETE SLABS ON GRADE REINFORCING: 6X6 W1.4XW1.4 WWF UNLESS NOTED. LOCATED IN THE UPPER 1/3 OF SLAB THICKNESS.
- 5. PROVIDE SAWCUT CONTROL JOINTS AT APPROXIMATELY 20' ON CENTER EACH WAY IN SLABS ON GRADE, SEE DETAILS. LOCATE JOINTS UNDER PARTITIONS WHENEVER POSSIBLE. CONSTRUCTION JOINTS AT CONTRACTOR'S OPTION.
- 6. DEPRESS SLABS AS REQUIRED FOR FLOOR FINISHES, SEE ARCHITECT.
- 7. SLOPE FLOORS AS REQUIRED TO FLOOR DRAINS, SEE ARCHITECT.
- 8. FORM ALL CONCRETE.
- 10. EXPOSED EDGES OF CONCRETE BEAMS, COLUMNS, ETC. SHALL BE CHAMFERED 3/4".
- 11. PROVIDE CORNER BARS FOR ALL CONTIGUOUS CORNERS.
- 12. WATER/CEMENT RATIO LIMITS: F'C = 3000 PSI 0.68 NON-AIR ENTRAINED, 0.50 AIR ENTRAINED F'C = 3500 PSI 0.62 NON-AIR ENTRAINED, 0.50 AIR-ENTRAINED F'C = 4500 PSI 0.4 AIR-ENTRAINED
- 13. SLUMP LIMITS: 3" FOR FOUNDATIONS, 4" FOR SLABS AND WALLS
- 14. PROVIDE AIR ENTRAINED CONCRETE FOR EXTERIOR EXPOSURES.
- 15. CONTRACTOR TO SUBMIT SIZE AND LAYOUT OF CONCRETE WALL SLEEVES, OPENINGS, ETC. FOR REVIEW PRIOR TO CONCRETE PLACEMENT.
- 16. REINFORCING LAP LENGTH: 45 BAR DIAMETERS (36 IF STAGGERED) FOR BARS UP TO #5, 60 BAR DIAMETERS (48 IF STAGGERED) FOR BARS LARGER THAN #5.

MASONRY NOTES

- 1. WORK SHALL BE PERFORMED IN ACCORDANCE WITH ACI 530 SPECIFICATIONS.
- 2. MORTAR: AS SPECIFIED.
- 3. GROUT: ASTM C476, F'C=2000 PSI, TESTED PER ASTM C1019.
- 4. REINFORCING BARS SHALL BE ASTM A-615, GRADE 60, LAP MINIMUM 40 BAR DIAMETERS FOR #5 BARS AND SMALLER, LAP MINIMUM 60 BAR DIAMETERS FOR BARS LARGER THAN #5 UNLESS NOTED OTHERWISE.
- HORIZONTAL WALL REINFORCING: PER ASTM A-82, 9 GA, HOT DIPPED GALVANIZED PER ASTM A-153 (1.5 OZ PER SF.), LADDER TYPE, EQUAL TO DUR-A-WAL. BED JOINTS AT 16" O.C. AND AT 1ST AND 2ND BED JOINTS AT BOTTOM OF WALL, TOP OF WALL, ABOVE LINTELS AND BELOW SILLS. REINFORCING CONTINUOUS EXCEPT AT VERTICAL CONTROL JOINTS. SIDE RODS LAPPED A MINIMUM OF 6" AT SPLICES. PROVIDE PREFABRICATED CORNERS AND TEES.
- 6. CONCRETE MASONRY UNITS: ASTM C-90, GRADE N, TWO CORE TYPE FOR REINFORCED MASONRY. DESIGN BASED ON F'M = 2000 PSI.
- VERTICAL WALL REINFORCING: 1 #5 EACH SIDE OF MASONRY OPENINGS, CONTROL JOINTS AND AS SHOWN, IN GROUT FILLED BLOCK CORES.
- B. VERTICAL BAR REINFORCING: PLACE ACCURATELY AND MECHANICALLY HOLD IN POSITION WHILE GROUTING. GROUTING SHALL BE DONE IN LIFTS NOT EXCEEDING 4'-0" AND MECHANICALLY CONSOLIDATED IN PLACE; CONSOLIDATION BY RODDING NOT ACCEPTABLE.
- 9. PROVIDE COMPLETELY GROUTED UNITS: A. UNDER PRECAST FLOOR PLANK BEARING UNDER CAST-IN-PLACE CONCRETE FLOOR BEARING

F.UNDER STEEL JOIST OR BEAM BEARING.

- UNDER PRECAST ARCHITECTURAL CONCRETE PANEL BEARING D. UNDER BRICK VENEER BEARING E. UNDER ANY CHANGE OF WALL THICKNESS, I.E.: 8" ON TOP OF 12"
- 10. PROVIDE LINTELS FOR OPENINGS IN MASONRY WALLS OVER 8" WIDE. SEE SCHEDULE(S).
- 11. RUNNING BOND MASONRY SHALL BE BUILT INTEGRALLY AT WALL CORNERS UNLESS INDICATED OTHERWISE.
- 12. BLOCK CONTROL JOINTS SHALL BE "MICHIGAN" TYPE UNLESS NOTED OTHERWISE. HORIZONTAL REINFORCING SHALL BE DISCONTINUOUS AT CONTROL JOINTS.
- 13. TEMPORARY WALL BRACING IS THE CONTRACTORS RESPONSIBILITY. CONFORM TO APPLICABLE CODES AND STANDARDS.

14. CONTRACTOR SHALL KEEP THE AIR SPACE CAVITY BETWEEN THE CONCRETE MASONRY AND VENEER COMPLETELY CLEAR OF MORTAR AND DEBRIS.

STRUCTURAL STEEL

1. STRUCTURAL STEEL: FABRICATED AND ERECTED PER THE AISC MANUAL OF STEEL CONSTRUCTION.

W-BEAMS: ASTM A-992 GR. 50. ASTM A-500 GRADE B. ASTM A53, TYPE E, GRADE B. STEEL PIPE: ALL OTHER SHAPES: ASTM A-36.

2. ANCHOR RODS: 36 KSI, ASTM F-1554.

- 3. WELDS: TO BE 70 KSI LOW HYDROGEN FILLER METAL PLACED BY WELDERS CERTIFIED IN WELD AND POSITION BY AWS D1.1. STRUCTURAL WELDING CODE, ALL WELDS SHALL BE APPLIED TO SURFACES FREE OF GREASE, PAINT, DIRT, OR OTHER HARMFUL MATERIAL.
- 4. BOLTED CONNECTIONS: 3/4" DIAMETER A-325 BOLTS WITH HEAVY HEX NUTS UNLESS NOTED. DESIGNED FOR BEARING CONNECTIONS, TIGHTENED TO **SNUG TIGHT** CRITERIA UNLESS NOTED OTHERWISE.
- 5. STEEL PRIMER: RUST INHIBITING ALKYD INDUSTRIAL PRIMER, SSPC 6, 1.5 MIL MINIMUM THICKNESS EXCEPT STEEL WHICH WILL RECEIVE SPRAYED-ON FIRE PROOFING.
- 6. BEAM CONNECTIONS SHALL BE DESIGNED TO SUPPORT ONE-HALF THE TOTAL UNIFORM LOAD CAPACITY PER AISC. WHEREVER POSSIBLE, EXTEND CONNECTIONS
- SHEAR TAB CONNECTIONS TO STEEL BEAMS ARE NOT ACCEPTABLE UNLESS BEAMS OF EQUAL DEPTHS ARE FASTENED ON OPPOSITE SIDES OF THE STEEL BEAM.
- 8. BEAM BEARING PLATES ARE TO BE LOCATED ON CENTER OF WALL UNLESS NOTED OTHERWISE. BEAR BEAM FULL LENGTH OF BEARING PLATES. 9. WHERE BEAMS BEAR ON COLUMNS, BEAMS BEAR ON BEAMS, BEAMS HANG FROM
- BEAMS, OR COLUMNS BEAR ON BEAMS, STIFFENER PLATES MINIMUM 1/4" THICK. 10. TEMPORARY BRACING IS TO BE MAINTAINED UNTIL PERMANENT CONNECTIONS ARE
- COMPLETED, APPROVED, AND SUPPORTED SLABS ARE CAST AND CURED. 11. INSTALL BRICK SUPPORT SHELF MEMBERS AFTER ALL SUPPORTED CONCRETE FLOOR

SLABS AND ROOF DECK WITH ROOFING IS IN PLACE.

- 12. BEAMS AND GIRDERS HAVE BEEN DESIGNED WITHOUT SHORING REQUIRED. INSTALLATION OF SHORING IS PERMITTED AT CONTRACTOR'S OPTION. ANTICIPATED
- BEAM DEFLECTION UNDER WET CONCRETE LOAD IS SPAN/360, 3/4" MAX.
- 13. DO NOT ALLOW LOADS ON SLAB UNTIL CONCRETE HAS ATTAINED A MINIMUM OF 75% OF THE 28-DAY SPECIFIED STRENGTH.

STEEL JOISTS


- 1. OPEN WEB STEEL JOIST: DESIGN, FABRICATE AND ERECT PER STEEL JOIST INSTITUTE (SJI) SPECIFICATIONS.
- 2. ITEMS SUPPORTED BY JOISTS SHALL BE ATTACHED AT PANEL POINTS WHERE POSSIBLE. SEE JOIST REINFORCEMENT DETAIL FOR NON-PANEL POINT LOADING.
- 3. WELDING OF SUPPORTS TO JOISTS WILL NOT BE PERMITTED UNLESS SPECIFICALLY
- 4. NO STRUCTURAL MEMBER INCLUDING OPEN WEB STEEL JOIST SHALL BE CUT OR MODIFIED WITHOUT PRIOR WRITTEN APPROVAL OF THE JOIST MANUFACTURER AND THE ARCHITECT/ENGINEER.
- 5. BRIDGING: SIZED NOT LESS THAN MINIMUM REQUIREMENT OF SJI.
- 6. SPECIAL LOADING CONDITIONS ARE SHOWN ON THE DRAWINGS AND SHALL BE USED IN THE DESIGN OF THE STEEL JOIST AS INDICATED ON THE PLANS.
- 7. PROVIDE UPLIFT BRIDGING PER SJI. STEEL JOISTS SHALL BE DESIGNED FOR A NET UPLIFT PRESSURE OF 7 PSF.
- 8. JOIST GIRDERS TO BE DESIGNED FOR L/600 DEFLECTION UNLESS NOTED OTHERWISE. METAL DECK
- 1. ROOF DECK: 11/2", 20 GAUGE, WIDE RIB, MINIMUM 3 SPANS. DESIGNED AND FABRICATED PER STEEL DECK INSTITUTE SPECIFICATIONS (SDI). WELD TO SUPPORTS WITH 5/8" DIAMETER PUDDLE WELDS 12" SPACING. FASTEN SIDE LAPS WITH #10 SCREWS AT 3'-0" MAXIMUM.
- FORM DECK: 1.0C20: S MIN = .167 IN3/FT, I MIN = .088 IN4/FT GALVANIZED 1.5C20: S MIN = .224 IN3/FT, I MIN = .197 IN4/FT GALVANIZED. CAPABLE OF SUPPORTING WET CONCRETE LOAD WITHOUT SHORING WELD TO STEEL PER MANUFACTURER'S RECOMMENDATIONS.
- 3. DECK FINISH: AS SPECIFIED.
- 4. ROOF DECK OPENINGS LARGER THAN 12" SHALL BE REINFORCED WITH A STEEL ROOF FRAME. SEE ROOF FRAME DETAIL ON DRAWINGS.


LIGHT GAGE METAL FRAMING

- 1. ALL STUDS SHALL BE FORMED FROM HOT-DIPPED GALVANIZED STEEL, G-60 COATING, CORRESPONDING TO THE REQUIREMENTS OF ASTM A653, STRUCTURAL QUALITY, GRADE 33, WITH A MINIMUM YIELD OF 33 KSI. MEMBERS DESIGNED PER AMERICAN IRON AND STEEL INSTITUTE (AISI) "SPECIFICATION FOR THE DESIGN OF COLD FORMED STEEL STRUCTURAL MEMBERS". MEMBER DESIGNATIONS IN ACCORDANCE WITH THE STEEL STUD MANUFACTURERS ASSOCIATION (SSMA) I.E. 600-S-162-33.
- 2. MEMBER SIZES INDICATED ON THE DRAWINGS AND CAPABLE OF SUPPORTING THE AS INDICATED IN GENERAL NOTE "GENERAL 1.D" FOR WALL COMPONENTS AND
- 3. MAX. ALLOWABLE DEFLECTION: L/600: BRICK VENEER SUPPORT.
- 4. CONTRACTOR TO BE RESPONSIBLE FOR FINAL DESIGN OF LIGHT GAGE FRAMING MEMBERS, CONNECTIONS AND COMPONENTS. SHOP DRAWINGS SHALL BE PREPARED UNDER THE SUPERVISION OF A REGISTERED PROFESSIONAL ENGINEER IN THE STATE OF MICHIGAN AND SUBMITTED TO THE ARCHITECT/ENGINEER FOR


PLYWOOD SHEATHING


- 1. PLYWOOD FOR WALLS SHALL BE 1/2" THICK APA RATED SHEATHING. (24/16)
- 2. ROOF SHEATHING FASTENED WITH #8 SCREWS AT 6" O.C. AT PANEL EDGES AND INTERMEDIATE SUPPORTS UNLESS NOTED OTHERWISE.
- 3. PANELS SHALL BE LAID IN A STAGGERED PATTERN, CONTINUOUS OVER TWO SPANS.







ANCHOR ROD LAYOUTS







VERTICAL REINFORCEMENT LAYOUT



FOOTING SCHEDULE Fy=60 KSI fc=3000 PS

9' - 0" x 9' - 0" 1' - 6"

(8) #6

PIER SCHEDULE Fy=60ksi f'c=3000 psi

SEE VERTICAL REINFORCEMENT LAYOUT THIS SHEET

MARK | SIZE | BASE PL | CAP PL

C1 HSS4x4x1/4 3/4"x10"x10" 1/2"

C2 HSS6x6x1/2 1 1/8"x12"x12" 1 1/4"x8"x1'-

1' - 0"

1' - 6"

(2) #5 CONT

(5) #5 EACH WAY

(6) #5 EACH WAY

(8) #5 EACH WAY

(10) #6 EW, T&B

REMARKS

REMARKS

1' - 8" x CONT

2' - 0" x CONT

4' - 0" x 4' - 0"

7' - 0" x 7' - 0"


| MARK | SIZE | VERT REINF


P1 20"x20"

TOP OF PIER = 99'-4" (UNO)

- 4. PROVIDE STEEL LINTELS AT ALL MASONRY WALL OPENINGS, INCLUDING MECHANICAL AND ELECTRICAL GREATER THAN 8" WIDE.

MARK	SIZE	MIN BEARING
H1	(2) 600\$162-68	(2) STUDS
H2	(2) 800\$300-97	(2) STUDS





3. DEAD LOADS DO NOT INCLUDE JOIST SELF-WEIGHT. 4. VERIFY ALL DIMENSIONS. 5. COORDINATE SIZE AND LOCATION OF MECHANICAL RTU WITH MECHANICAL CONTRACTOR. 6. SL = SNOW LOAD

DL = DEAD LOAD RLL = ROOF LIVE LOAD PDL = CONCENTRATED DEAD LOAD WD = DRIFTED SNOW LOAD

DATE REVISION STATE OF MICHIGAN DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET

FACILITIES AND BUSINESS SERVICES ADMINISTRATION

DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR FILE NO. 491/20167.SDW

FUNDING CODE CONTRACT NO. 171CODHHS7255 Y22003 KEY PLAN

100 S Jefferson Ave, Suite 601

Saginaw, Michigan 48607

KITCHEN

WTA A RCHITECTS

WTAARCH.COM

COPYRIGHT © 2023 989 752 8107 CONSULTING ENGINEERS

714 EAST MIDLAND STREET • BAY CITY, MICHIGAN 48706 (989) 894-4300 F (989) 894-9930 www.macmillanassociates. PROJECT TITLE 491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC **PSYCHIATRY - CREATE**

SALINE, MICHIGAN NOTES AND SCHEDULES

PROJECT NUMBER SHEET NUMBER 2021094 PROJECT DATE SEPTEMBER 6, 202

These documents are approved for compliance with the STATE OF MICHIGAN BUILDING CODE

BUILDING

subject to field inspection and the

conditions of approval.

SNOW DRIFTING DIAGRAM - PLAN

LOW ROOF

SPECIAL JOIST DIAGRAM

7. MECHANICAL UNIT WEIGHTS HAVE BEEN INCLUDED DL DESIGNATIONS UNO. 8. JOIST WEB CONFIGURATION BY JOIST MANUFACTURER.

- SIZE JOIST GIRDER

TO ACCOMMODATE

30"x28" DUCT


PENETRATION


COORDINATE


LOCATION WITH


MECH TRADES


CHECKED BY JAG































7 INTERIOR COLUMN FOOTING

8 NEW FOOTING AT EXISTING















12 CONTROL/CONSTRUCTION JOINTS











REVISION

ADAM LACH, RA, DIRECTOR

DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET

CONTRACT NO.

KEY PLAN
NOT TO SCALE

WTAARCH.COM

Y22003

FACILITIES AND BUSINESS SERVICES ADMINISTRATION

DESIGN AND CONSTRUCTION DIVISION

STATE OF MICHIGAN

FILE NO.

491/20167.SDW

171CODHHS7255

FUNDING CODE

DATE

Saginaw, Michigan 48607 989 752 8107 COPYRIGHT © 2023

MACMILLAN ASSOCIATES
CONSULTING ENGINEERS
714 EAST MIDLAND STREET • BAY CITY, MICHIGAN 48706
(989) 894-4300 F (989) 894-9930 WWW.MACMILLANASSOCIATES.COM

PROJECT TITLE 491/20167.SDW - PHASE 500:


CENTER FOR FORENSIC PSYCHIATRY - CREATE


KITCHEN SALINE, MICHIGAN


FOUNDATION DETAILS


PROJECT NUMBER SHEET NUMBER 2021094 PROJECT DATE S5.01 SEPTEMBER 6, 202 CHECKED BY

JAG









K" JOIST END BEARING

— CMU WALL, SEE PLAN


LOW ROOF DECK SUPPORT


- BRICK VENEER, SEE


- METAL DECK, SEE PLAN


- STEEL BEAM, SEE PLAN


- L4x3x1/4 LLH

















— STRUCTURE ABOVE, SEE PLAN


1. SEE ARCH FOR TOP OF WALL INFILL REQUIREMENTS 2. BRACING NOT REQUIRED 4 FEET FROM INTEGRAL WALL INTERSECTIONS OR CORNERS. 3. ANCHORS SHALL BE #10 TEK SCREWS WHERE FASTENING TO METAL OR 3/16"x1 1/4" TAPCONS WHERE FASTENING TO CONCRETE OR MASONRY. PREDRILL ANGLE METAL 4. EXTERIOR CLADDING SHALL HAVE FLEXIBLE CONNECTIONS TO ALLOW FOR 3/4" DEFLECTION. 5. LIGHT FRAMED ALTERNATES SHALL BE DESIGNED BY THE FABRICATOR AND APPROVED PRIOR














- STEEL LINTEL,

AND SCHEDULE

-8" CAST IN PLACE

CONCRETE SLAB

W/#5 AT16" O.C.

EACH WAY TOP

AND BOTTOM

#5 DOWELS

AT 16" O.C.

- MASONRY PIER, SEE

PLAN

15 MC1 - MOMENT CONNECTION

SEE PLAN

+**--- ---**

SECTION A-A


(2) 3/4" DIA A325 BOLTS TOP AND BOTTOM ——

COLUMN SCHEDULE —

STEEL BEAM, SEE PLAN -

CAP PLATE, SEE

T.O. STEEL SEE PLAN









A3 ADDENDUM NO. 3

FILE NO.

491/20167.SDW

171CODHHS7255

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607

FUNDING CODE

REVISION

ADAM LACH, RA, DIRECTOR

DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET

CONTRACT NO.

KEY PLAN NOT TO SCALE

WTAARCH.COM

COPYRIGHT © 2023

Y22003

FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION

STATE OF MICHIGAN

09/28/23

DATE

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN SALINE, MICHIGAN

WTA A RCHITECTS

MACMILLAN ASSOCIATES CONSULTING ENGINEERS

ROOF FRAMING DETAILS

PROJECT NUMBER 2021094	SHEET NUMBER
PROJECT DATE SEPTEMBER 6, 2023	S7.01
CHECKED BY	

ABBREVIATION DESCRIPTION

COMPRESSED AIR

COMPRESSED AIR (SPECIFIC PSIG)

ABBREVIATION DESCRIPTION

FLOOR DRAIN

FUNNEL FLOOR DRAIN


NOTE: LIST OF ADDITIONAL SYMBOLS & ABBREVIATIONS ASSOCIATED WITH
TEMPERATURE CONTROLS ARE IDENTIFIED ON TC DRAWINGS.

NATCHANICAL CVAADOL LICT

ABBREVIATION DESCRIPTION

OXYGEN OUTSIDE AIR


PIPING SYMBO	<u>.s</u>	DUCTWORK SY	MBOLS .
SYMBOL A AV	DESCRIPTION	SYMBOL	DESCRIPTION
—	AIR VENT - AUTOMATIC	TU-101	AIR TERMINAL UNIT
M∨ <mark>↓</mark> ¬	AIR VENT - MANUAL	<u>10-101</u>	AIR TERMINAL UNIT WITH HEATING COIL
BFP	BACKFLOW PREVENTER	TU-101	AIN TERMINAE ONLY WITTHEATING GOIL
—— —	CATCH BASIN	\(\tag{\text{VTU-101}} \)	VENTURI AIR TERMINAL UNIT
—————	CIRCULATING PUMP	<u> </u>	VENTURI AIR TERMINAL UNIT WITH HEATING COIL
o	CLEAN OUT - IN FLOOR	VTU-101	VENTORIA MICHERINIA CONTINUE MITTIES CONTINUE CO
———II co	CLEAN OUT - FLANGE		DAMPER - HORIZONTAL FIRE (EXISTING, NEW)
—	DIRECTION OF FLOW	_6 _•	· · · · · · · · · · · · · · · · · · ·
	DIRECTION OF PITCH - DOWN		DAMPER - HORIZONTAL FIRE / SMOKE (EXISTING, NEW
	FINNED TUBE RADIATION	o•	DAMPER - SMOKE (EXISTING, NEW)
ď,	FIRE PROTECTION - SIAMESE CONNECTION - FREE STANDING	^	DAINIFER - SWORE (EXISTING, NEW)
	FIRE PROTECTION - SIAMESE CONNECTION - WALL MOUNTED		DAMPER - VERTICAL FIRE (EXISTING, NEW)
·	FIRE PROTECTION - SPRINKLER HEAD, CONCEALED	_&_ ^	DAMPED VEDTICAL FIRE / CMOVE (EVICTING NEW)
	FIRE PROTECTION - SPRINKLER HEAD, PENDANT		DAMPER - VERTICAL FIRE / SMOKE (EXISTING, NEW)
	FIRE PROTECTION - SPRINKLER HEAD, UPRIGHT	BDD 	DAMPER - BACK DRAFT
─	FIRE PROTECTION - SPRINKLER HEAD, SIDEWALL	M	DAMPER - MOTORIZED
——J <u>O</u>	FLOOR DRAIN		
X	FLOOR DRAIN - ELEVATION	, , , , , , , , , , , , , , , , , , ,	DAMPER - VOLUME (MANUALLY ADJUSTABLE)
 ⊃ ●	FLOOR DRAIN - FUNNEL		DIFFUSER - BLANK OFF
₹	FLOOR DRAIN - FUNNEL, ELEVATION		
	FLOW MEASURING DEVICE (FOR TEST AND BALANCING)		DIFFUSER - LINEAR SLOT
Fs	FLOW SWITCH		DIFFUSER - SQUARE OR RECTANGULAR
FM	FLOW METER		
HB	HOSE BIBB		DUCT CROSS SECTION - SUPPLY
MH			DUCT CROSS SECTION - RETURN
	MANHOLE OPEN SITE DRAIN		255. SAGGO GEOTION - RETURN
— ⊃ ⊚	OPEN SITE DRAIN		DUCT CROSS SECTION - EXHAUST
	PIPE - ANCHOR	<u> </u>	DUCT ELEVIDLE COMMECTION
	PIPE - CAP OR PLUG	1 1 1	DUCT - FLEXIBLE CONNECTION
 5	PIPE - ELBOW DOWN		DUCT - FLEXIBLE DUCT
o	PIPE - ELBOW UP	\leftarrow	
	PIPE - EXPANSION JOINT OR COMPENSATOR	Ĺ	DUCT TAKE-OFF - ROUND CONICAL
 	PIPE - FLANGE	\ \ \ \	DUCT TAKE-OFF - RECTANGULAR WITH SHOE TAP
——————————————————————————————————————	PIPE - HOSE AND BRAID FLEXIBLE CONNECTION	<i>✓</i>	
— 	PIPE - RUBBER FLEXIBLE CONNECTION	, T	ELBOW - RECTANGULAR WITH TURNING VANES
	PIPE - GUIDE	\leftarrow	ELBOW - RECTANGULAR/ ROUND SMOOTH RADIUS
	PIPE - TEE DOWN	7	
————	PIPE - TEE UP	\longrightarrow	ELBOW DOWN - RECTANGULAR
	PIPE - UNION	\leftarrow	ELBOW DOWN - ROUND
<u> </u>	PRESSURE AND TEMPERATURE TEST PLUG	,)	LLBOW BOWN TROUB
φ 	PRESSURE CALLOE AND COOK		ELBOW UP - RECTANGULAR
	PRESSURE GAUGE AND COCK	\leftarrow	ELBOW UP - ROUND
	REDUCER - CONCENTRIC	,	ELBOW OF TROOMS
	REDUCER - ECCENTRIC		FAN - AXIAL
(Ô;	ROOF/OVERFLOW DRAIN		FANL CENTRIFICAL (FLEVATION)
	STEAM TRAP - FLOAT AND THERMOSTATIC		FAN - CENTRIFUGAL (ELEVATION)
	STRAINER	├──	HEATING COIL
	STRAINER WITH VALVE AND BLOW-OFF	(_ D, (
	THERMOMETER) - - -	INCLINED DROP IN DIRECTION OF AIRFLOW
	TRAP	\ 	INCLINED RISE IN DIRECTION OF AIRFLOW
本	· · · ·	Г <u>-</u>	
	VALVE - ANGLE		INTAKE OR RELIEF HOOD
<u>—ф</u>	VALVE - BALL	<u> </u>	REGISTER - RETURN OR EXHAUST
——————————————————————————————————————	VALVE - BALANCE (i.e. BALANCE VALVE TO 0.5 GPM)		
0.5	VAI VF - COMBINATION BAI ANCF & FLOW MEASURING (i.e. BALANCE VALVE TO 0.5 GPM)	VI	REGISTER - RETURN WITH BOOT
—— / ——	VALVE - BUTTERFLY		REGISTER - TRANSFER GRILLE
——N ——	VALVE - CHECK	<u> </u>	
 \$\$	VALVE - SPRING CHECK	$\langle \square \rangle$	ROOF EXHAUST FAN
<u> </u>	VALVE - GAS (MANUAL)	<u> </u>	TRANSITION - CONCENTRIC
——M——	VALVE - GLOBE	,	TO MICHIEL TO MOLIVITATO
——₩——	VALVE - ISOLATION	\leftarrow	TRANSITION - ECCENTRIC
──₩ ──	VALVE - NEEDLE	□-	LINIT HEATER HORIZONTAL TURCAL
		4J 	UNIT HEATER - HORIZONTAL THROW
\Y	VALVE - OS&Y		UNIT HEATER - VERTICAL THROW
——— V ——— }	VALVE - PLUG		
——————————————————————————————————————	VALVE - PRESSURE REGULATING	·	UCTWORK SYMBOLS
——————————————————————————————————————	VALVE - PRESSURE REDUCING	SYMBOL I————I	DESCRIPTION DUST TAKE OFF DESTANGLE ARMST ARMS TAR
\$	VALVE - PRESSURE RELIEF	 	DUCT TAKE-OFF - RECTANGULAR WITH SHOE TAP
 \$	VALUE I REGOOKE RELEE	廿十	
	VALVE - PRESSURE & TEMPERATURE RELIEF	 	DUCT TAKE-OFF - ROUND CONICAL
—— © VTR	VENT THROUGH ROOF		
———	WALL HYDRANT	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	ELBOW - RECTANGULAR WITH TURNING VANES
•			
DOUBLE LINE P	IPING SYMBOLS	{	ELROW DECTANCIII AD CHODE DADING MITH OF ITT
	DESCRIPTION	——————————————————————————————————————	ELBOW - RECTANGULAR SHORT RADIUS WITH SPLITTE
SYMBOL	FLANGE		ELBOW - ROUND
	FLEX CONNECTION	, H	
			ELBOW - RECTANGULAR SMOOTH RADIUS
	STRAINER - BASKET	】	
	STRAINER - Y TYPE	<u> </u>	ELBOW DOWN - RECTANGULAR
		 X	ELDOVV DOVVIN - RECTANGULAK
	VALVE - 2 WAY CONTROL		ELBOW DOWN - ROUND
	VALVE - 3 WAY CONTROL		
		<u> </u>	ELBOW UP - RECTANGULAR
	VALVE - BUTTERFLY		ELBOW UP - ROUND
		<u> </u>	
	VALVE - CHECK	 	HEATING COIL
	VALVE - DETECTOR CHECK		NOUNED DECD WEST TO THE STATE OF THE STATE O
<u> </u>		<u>} </u>	INCLINED DROP IN DIRECTION OF AIRFLOW
//\		₹ R	INCLINED RISE IN DIRECTION OF AIRFLOW
_/ _			
	VALVE - OS&Y HORIZONTAL STEM		
	VALVE - OS&Y HORIZONTAL STEM VALVE - OS&Y VERTICAL STEM		TRANSITION - CONCENTRIC




MECHANICAL DRAWING INDEX

SHEET NO.	SHEET TITLE
M0.01	MECHANICAL STANDARDS AND DRAWING INDEX
M1.01	FIRE PROTECTION ZONING PLAN
M2.00	UNDERGROUND PLUMBING PLAN
M2.01	FIRST FLOOR PLUMBING AND FIRE PROTECTION PLAN - UNIT H
M2.02	FIRST FLOOR PLUMBING AND FIRE PROTECTION PLAN - UNIT J
M2.03	PENTHOUSE PLUMBIN PLAN
M3.01	FIRST FLOOR HVAC PIPING PLAN - UNIT H
M3.03	PENTHOUSE HVAC PIPING PLAN
M4.01	FIRST FLOOR SHEET METAL PLAN - UNIT H
M4.03	PENTHOUSE SHEET METAL PLAN
M4.04	MECHANICAL ROOF PLAN
M5.01	PLUMBING ENLARGED PLAN
M6.01	MECHANICAL DETAILS
M6.02	MECHANICAL DETAILS
M6.03	MECHANICAL DETAILS
M6.04	MECHANICAL DETAILS
M7.01	MECHANICAL SCHEDULES
M7.02	MECHANICAL SCHEDULES
M7.03	MECHANICAL SCHEDULES
M7.04	MECHANICAL SCHEDULES
M8.01	TEMPERATURE CONTROL STANDARDS AND GENERAL NOTES
M8.02	TEMPERATURE CONTROLS
M8.03	TEMPERATURE CONTROLS
M8.04	TEMPERATURE CONTROLS


STANDARD METHODS OF NOTATION



NOTE: SOME SYMBOLS AND ABBREVIATIONS SHOWN MAY NOT APPLY TO THIS PROJECT.







DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255

CONTRACT NO.

WTAARCH.COM

COPYRIGHT © 2023

Y22003



WTAARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607

989 752 8107

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC

PSYCHIATRY - CREATE **KITCHEN**

SALINE, MICHIGAN

MECHANICAL STANDARDS AND DRAWING INDEX

SHEET NUMBER PROJECT NUMBER 2021094 PROJECT DATE M0.01SEPTEMBER 6, 2023 CHECKED BY WEK


REFER TO SHEETS M2.01 AND M2.02 FOR MAIN ROUTING AND TIE-IN LOCATIONS AT EXISTING SYSTEM ASR1-1A EXISTING AREA = 26000 ADDITIONAL AREA = 12530 TOTAL ZONE AREA = 38530 J.8) K (K.3) FIRST FLOOR FIRE PROTECTION ZONING PLAN SCALE: 1/8" = 1'-0"

FIRE PROTECTION GENERAL NOTES:

- 1 THESE DRAWINGS ARE DIAGRAMMATIC, AND REPRESENT THE GENERAL INTENT AND ARRANGEMENT OF SYSTEMS. THEY ARE NOT TO BE CONSIDERED FABRICATION/COORDINATION/SHOP DRAWINGS, COORDINATION WITH OTHER TRADES IS REQUIRED. PROVIDE THE ADDITIONAL FITTINGS AND OFFSETS THAT WILL BE REQUIRED TO COMPLETE EACH SYSTEM AND TO AVOID INTERFERENCES WITH ALL OTHER SYSTEMS INCLUDING THE STRUCTURE, SHEET METAL, OTHER PIPING SYSTEMS, ELECTRICAL CONDUITS, BUS DUCTS, CABLE TRAY, LIGHT FIXTURES, ETC. AND/OR OTHER SPACE
- 2 INSTALL SYSTEMS SUCH THAT REQUIRED CLEARANCE AND SERVICE ACCESS SPACE IS PROVIDED AROUND ALL MECHANICAL AND ELECTRICAL EQUIPMENT, AND AROUND ANY COMPONENTS WHICH REQUIRE SERVICE ACCESS.
- 3 NO SPRINKLER PIPING SHALL BE ROUTED THROUGH ELECTRICAL EQUIPMENT ROOMS. TELECOMMUNICATION EQUIPMENT ROOMS, ELEVATOR EQUIPMENT ROOMS OR SIMILAR ROOMS. ONLY SPRINKLER PIPING SERVING SPRINKLERS HEADS IN THOSE ROOMS SHALL BE
- 4 PIPING SHALL NOT BE INSTALLED ABOVE ELECTRICAL TRANSFORMERS, SWITCHBOARDS, PANELBOARDS OR MOTOR CONTROL CENTERS.
- 5 MINIMUM RUN-OUT PIPE SIZE TO SPRINKLER HEADS SHALL BE 1".
- 6 PROVIDE AN AUTOMATIC WET PIPE SPRINKLER SYSTEM IN ACCORDANCE WITH NFPA 13 <><LIGHT HAZARD>>> CLASSIFICATION. HYDRAULIC CALCULATIONS SHALL BE BASED ON DENSITY OF <<<0.10>>> GPM/SQ FT. OVER THE MOST REMOTE <<<1500>>> SQ. FT.
- 7 ACCORDING TO THE MOST RECENT FLOW TEST INFORMATION, THE STATIC PRESSURE AVAILABLE AT THE CITY WATER MAIN AT THE STREET IS <<<XX>>> PSIG. RESIDUAL PRESSURE WITH <<<XXX>>> GPM FLOWING IS <<<XX>>>> PSIG. CONTRACTOR SHALL MAKE HIS OWN PRESSURE AND FLOW TEST PRIOR TO SYSTEM DESIGN.
- 8 FIRE PROTECTION WATER SERVICE ENTRANCE PIPING SHALL BE BURIED WITH DEPTH OF COVER OVER TOP OF PIPE OF AT LEAST <<<72">>>>, OR WITH TOP OF PIPE AT LEAST 12" BELOW LEVEL OF MAXIMUM FROST PENETRATION, OR AS REQUIRED BY AUTHORITIES HAVING JURISDICTION, WHICHEVER IS DEEPEST.


CONSTRUCTION KEY NOTES:

PROVIDE FULLY FUNCTIONING SPRINKLER SYSTEM IN ACCORDANCE WITH NFPA13, OWNERS INSURING AGENCY AND AUTHORITY HAVING JURISDICTION IN AREA INDICATED.






Peter Basso Associates Inc CONSULTING ENGINEERS 5145 Livernois, Suite 100 Troy, Michigan 48098-3276 Tel: 248-879-5666 Fax: 248-879-0007 www.PeterBassoAssociates.com PBA Project No.: 2021-0402




DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

491/20167.SDW

CONTRACT NO. **FUNDING CODE** 171CODHHS7255 Y22003





WTAARCHITECTS

COPYRIGHT © 2023

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607

PROJECT TITLE

491/20167.SDW - PHASE 500:


CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN


SALINE, MICHIGAN

FIRE PROTECTION ZONING

SHEET NUMBER PROJECT NUMBER PROJECT DATE SEPTEMBER 6, 2023 CHECKED BY

WEK







DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

491/20167.SDW

CONTRACT NO. FUNDING CODE 171CODHHS7255 Y22003





WTA A RCHITECTS

COPYRIGHT © 2023

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN


SALINE, MICHIGAN


UNDERGROUND PLUMBING PLAN

SHEET NUMBER PROJECT NUMBER PROJECT DATE M2.00SEPTEMBER 6, 2023

PBA Project No.: 2021-0402

CHECKED BY WEK





FIRST FLOOR PLUMBING AND FIRE PROTECTION PLAN - UNIT J SCALE: 1/8" = 1'-0"

FIRE PROTECTION GENERAL NOTES:

- 1 THESE DRAWINGS ARE DIAGRAMMATIC, AND REPRESENT THE GENERAL INTENT AND ARRANGEMENT OF SYSTEMS. THEY ARE NOT TO BE CONSIDERED FABRICATION/COORDINATION/SHOP DRAWINGS. COORDINATION WITH OTHER TRADES IS REQUIRED. PROVIDE THE ADDITIONAL FITTINGS AND OFFSETS THAT WILL BE REQUIRED TO COMPLETE EACH SYSTEM AND TO AVOID INTERFERENCES WITH ALL OTHER SYSTEMS INCLUDING THE STRUCTURE, SHEET METAL, OTHER PIPING SYSTEMS, ELECTRICAL CONDUITS, BUS DUCTS, CABLE TRAY, LIGHT FIXTURES, ETC. AND/OR OTHER SPACE CONSTRAINTS.
- 2 INSTALL SYSTEMS SUCH THAT REQUIRED CLEARANCE AND SERVICE ACCESS SPACE IS PROVIDED AROUND ALL MECHANICAL AND ELECTRICAL EQUIPMENT, AND AROUND ANY COMPONENTS WHICH REQUIRE SERVICE ACCESS.
- 3 NO SPRINKLER PIPING SHALL BE ROUTED THROUGH ELECTRICAL EQUIPMENT ROOMS, TELECOMMUNICATION EQUIPMENT ROOMS, ELEVATOR EQUIPMENT ROOMS OR SIMILAR ROOMS. ONLY SPRINKLER PIPING SERVING SPRINKLERS HEADS IN THOSE ROOMS SHALL BE
- 4 PIPING SHALL NOT BE INSTALLED ABOVE ELECTRICAL TRANSFORMERS, SWITCHBOARDS, PANELBOARDS OR MOTOR CONTROL CENTERS.
- 5 MINIMUM RUN-OUT PIPE SIZE TO SPRINKLER HEADS SHALL BE 1".
- 6 PROVIDE AN AUTOMATIC WET PIPE SPRINKLER SYSTEM IN ACCORDANCE WITH NFPA 13 <><LIGHT HAZARD>>> CLASSIFICATION. HYDRAULIC CALCULATIONS SHALL BE BASED ON DENSITY OF <<<0.10>>> GPM/SQ FT. OVER THE MOST REMOTE <<<1500>>> SQ. FT.
- 7 ACCORDING TO THE MOST RECENT FLOW TEST INFORMATION, THE STATIC PRESSURE AVAILABLE AT THE CITY WATER MAIN AT THE STREET IS <<<XX>>> PSIG. RESIDUAL PRESSURE WITH <<<XXX>>> GPM FLOWING IS <<<XX>>> PSIG. CONTRACTOR SHALL MAKE HIS OWN PRESSURE AND FLOW TEST PRIOR TO SYSTEM DESIGN.
- 8 FIRE PROTECTION WATER SERVICE ENTRANCE PIPING SHALL BE BURIED WITH DEPTH OF COVER OVER TOP OF PIPE OF AT LEAST <<<72">>>>, OR WITH TOP OF PIPE AT LEAST 12" BELOW LEVEL OF MAXIMUM FROST PENETRATION, OR AS REQUIRED BY AUTHORITIES HAVING JURISDICTION, WHICHEVER IS DEEPEST.

PLUMBING GENERAL NOTES:


- 1 THESE DRAWINGS ARE DIAGRAMMATIC, AND REPRESENT THE GENERAL INTENT AND ARRANGEMENT OF SYSTEMS. THEY ARE NOT TO BE CONSIDERED FABRICATION/COORDINATION/SHOP DRAWINGS. COORDINATION WITH OTHER TRADES IS REQUIRED. PROVIDE THE ADDITIONAL FITTINGS AND OFFSETS THAT WILL BE REQUIRED TO COMPLETE EACH SYSTEM AND TO AVOID INTERFERENCES WITH ALL OTHER SYSTEMS INCLUDING THE STRUCTURE, SHEET METAL, OTHER PIPING SYSTEMS, ELECTRICAL CONDUITS, BUS DUCTS, CABLE TRAY, LIGHT FIXTURES, ETC. AND/OR OTHER SPACE CONSTRAINTS.
- INSTALL SYSTEMS SUCH THAT REQUIRED CLEARANCE AND SERVICE ACCESS SPACE IS PROVIDED AROUND ALL MECHANICAL AND ELECTRICAL EQUIPMENT, AND AROUND ANY COMPONENTS WHICH REQUIRE SERVICE ACCESS.
- 3 PIPING SHALL NOT BE INSTALLED ABOVE ELECTRICAL TRANSFORMERS, SWITCHBOARDS, PANELBOARDS OR MOTOR CONTROL CENTERS.
- 4 COORDINATE AND PROVIDE ACCESS DOORS WITHIN INACCESSIBLE CEILING, SHAFT, AND CHASE AREAS FOR ALL COMPONENTS WHICH REQUIRE SERVICE ACCESS. REFER TO ARCHITECTURAL DRAWINGS FOR CEILING TYPES.
- 5 PROVIDE SUPPLEMENTARY STEEL AS REQUIRED FOR THE PROPER SUPPORT OF ALL SYSTEMS.
- 6 REFER TO ARCHITECTURAL PLANS FOR DIMENSIONED LOCATIONS OF PLUMBING FIXTURES.
- 7 HOT AND COLD WATER PIPING RUN-OUTS TO LAVATORIES AND SINKS SHALL BE 1/2" UNLESS OTHERWISE NOTED.
- PLUMBING VENT PIPING THROUGH ROOF SHALL BE LOCATED A MINIMUM OF 10'-0" FROM ANY FRESH AIR INTAKE LOCATION AND A MINIMUM OF 18" CLEAR FROM THE INSIDE FACE OF
- 9 PROVIDE CODE REQUIRED CLEARANCE FOR ALL CLEANOUTS INSTALLED IN SANITARY WASTE
- 10 MINIMUM UNDERGROUND PIPE SIZE SHALL BE 3".

CONSTRUCTION KEY NOTES:

- 1 3 SAN TO LAV/SINK.
- 2 3 SAN TO FLOOR DRAIN/SINK.
- 3 3 GSAN TO SINK.
- 4 4 SAN TO WC.
- 5 4 GSAN TO FLOOR TROUGH.
- 6 3 SAN TO FLOOR TROUGH.
- 7 1/2 CW TO DRAIN COOLER.

9 4 SAN TO FLOOR DRAIN/SINK.


- 8 4 SAN TO FLOOR TROUGH.
- 10 ROUTE IN CEILING SPACE OF GYM. ROUTE ALONG SIDE NEW MECHANICAL PIPING. COORIDINATE FINAL ROUTING WITH MECHANICAL TRADES.
- 11 PIPING IN THIS AREA ROUTED WITHIN SECOND FLOOR CEILING SPACE.





FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255



CONTRACT NO.





WTAARCH.COM

COPYRIGHT © 2023

WTA A RCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

Peter Basso Associates Inc

CONSULTING ENGINEERS 5145 Livernois, Suite 100

Troy, Michigan 48098-3276

Tel: 248-879-5666 Fax: 248-879-0007 www.PeterBassoAssociates.com

PBA Project No.: 2021-0402


FIRST FLOOR PLUMBING AND FIRE PROTECTION PLAN - UNIT J

SHEET NUMBER PROJECT NUMBER 2021094 PROJECT DATE SEPTEMBER 6, 2023 CHECKED BY

WEK

M2.02







- 1 THESE DRAWINGS ARE DIAGRAMMATIC, AND REPRESENT THE GENERAL INTENT AND ARRANGEMENT OF SYSTEMS. THEY ARE NOT TO BE CONSIDERED FABRICATION/COORDINATION/SHOP DRAWINGS. COORDINATION WITH OTHER TRADES IS REQUIRED. PROVIDE THE ADDITIONAL FITTINGS AND OFFSETS THAT WILL BE REQUIRED TO COMPLETE EACH SYSTEM AND TO AVOID INTERFERENCES WITH ALL OTHER SYSTEMS INCLUDING THE STRUCTURE, SHEET METAL, OTHER PIPING SYSTEMS, ELECTRICAL CONDUITS, BUS DUCTS, CABLE TRAY, LIGHT FIXTURES, ETC. AND/OR OTHER SPACE CONSTRAINTS.
- INSTALL SYSTEMS SUCH THAT REQUIRED CLEARANCE AND SERVICE ACCESS SPACE IS PROVIDED AROUND ALL MECHANICAL AND ELECTRICAL EQUIPMENT, AND AROUND ANY COMPONENTS WHICH REQUIRE SERVICE ACCESS.
- 3 NO SPRINKLER PIPING SHALL BE ROUTED THROUGH ELECTRICAL EQUIPMENT ROOMS, TELECOMMUNICATION EQUIPMENT ROOMS, ELEVATOR EQUIPMENT ROOMS OR SIMILAR ROOMS. ONLY SPRINKLER PIPING SERVING SPRINKLERS HEADS IN THOSE ROOMS SHALL BE
- 4 PIPING SHALL NOT BE INSTALLED ABOVE ELECTRICAL TRANSFORMERS, SWITCHBOARDS, PANELBOARDS OR MOTOR CONTROL CENTERS.
- 5 MINIMUM RUN-OUT PIPE SIZE TO SPRINKLER HEADS SHALL BE 1".
- 6 PROVIDE AN AUTOMATIC WET PIPE SPRINKLER SYSTEM IN ACCORDANCE WITH NFPA 13 <><LIGHT HAZARD>>> CLASSIFICATION. HYDRAULIC CALCULATIONS SHALL BE BASED ON DENSITY OF <<<0.10>>> GPM/SQ FT. OVER THE MOST REMOTE <<<1500>>> SQ. FT.
- 7 ACCORDING TO THE MOST RECENT FLOW TEST INFORMATION, THE STATIC PRESSURE AVAILABLE AT THE CITY WATER MAIN AT THE STREET IS <<<XX>>> PSIG. RESIDUAL PRESSURE WITH <<<XXX>>> GPM FLOWING IS <<<XX>>> PSIG. CONTRACTOR SHALL MAKE HIS OWN PRESSURE AND FLOW TEST PRIOR TO SYSTEM DESIGN.
- 8 FIRE PROTECTION WATER SERVICE ENTRANCE PIPING SHALL BE BURIED WITH DEPTH OF COVER OVER TOP OF PIPE OF AT LEAST <<<72">>>>, OR WITH TOP OF PIPE AT LEAST 12" BELOW LEVEL OF MAXIMUM FROST PENETRATION, OR AS REQUIRED BY AUTHORITIES HAVING JURISDICTION, WHICHEVER IS DEEPEST.

PLUMBING GENERAL NOTES:


- 1 THESE DRAWINGS ARE DIAGRAMMATIC, AND REPRESENT THE GENERAL INTENT AND ARRANGEMENT OF SYSTEMS. THEY ARE NOT TO BE CONSIDERED FABRICATION/COORDINATION/SHOP DRAWINGS. COORDINATION WITH OTHER TRADES IS REQUIRED. PROVIDE THE ADDITIONAL FITTINGS AND OFFSETS THAT WILL BE REQUIRED TO COMPLETE EACH SYSTEM AND TO AVOID INTERFERENCES WITH ALL OTHER SYSTEMS INCLUDING THE STRUCTURE, SHEET METAL, OTHER PIPING SYSTEMS, ELECTRICAL CONDUITS, BUS DUCTS, CABLE TRAY, LIGHT FIXTURES, ETC. AND/OR OTHER SPACE
- INSTALL SYSTEMS SUCH THAT REQUIRED CLEARANCE AND SERVICE ACCESS SPACE IS PROVIDED AROUND ALL MECHANICAL AND ELECTRICAL EQUIPMENT, AND AROUND ANY COMPONENTS WHICH REQUIRE SERVICE ACCESS.
- 3 PIPING SHALL NOT BE INSTALLED ABOVE ELECTRICAL TRANSFORMERS, SWITCHBOARDS, PANELBOARDS OR MOTOR CONTROL CENTERS.
- 4 COORDINATE AND PROVIDE ACCESS DOORS WITHIN INACCESSIBLE CEILING, SHAFT, AND CHASE AREAS FOR ALL COMPONENTS WHICH REQUIRE SERVICE ACCESS. REFER TO ARCHITECTURAL DRAWINGS FOR CEILING TYPES.
- 5 PROVIDE SUPPLEMENTARY STEEL AS REQUIRED FOR THE PROPER SUPPORT OF ALL SYSTEMS.
- 6 REFER TO ARCHITECTURAL PLANS FOR DIMENSIONED LOCATIONS OF PLUMBING FIXTURES.
- 7 HOT AND COLD WATER PIPING RUN-OUTS TO LAVATORIES AND SINKS SHALL BE 1/2" UNLESS OTHERWISE NOTED.
- PLUMBING VENT PIPING THROUGH ROOF SHALL BE LOCATED A MINIMUM OF 10'-0" FROM ANY FRESH AIR INTAKE LOCATION AND A MINIMUM OF 18" CLEAR FROM THE INSIDE FACE OF
- 9 PROVIDE CODE REQUIRED CLEARANCE FOR ALL CLEANOUTS INSTALLED IN SANITARY WASTE AND VENT PIPING.
- 10 MINIMUM UNDERGROUND PIPE SIZE SHALL BE 3".

CONSTRUCTION KEY NOTES:

- 1 3 SAN TO LAV/SINK.
- 2 3 SAN TO FLOOR DRAIN/SINK.
- 3 3 GSAN TO SINK.
- 4 4 SAN TO WC.
- 5 4 GSAN TO FLOOR TROUGH.
- 6 3 SAN TO FLOOR TROUGH.
- 7 1/2 CW TO DRAIN COOLER.
- 8 4 SAN TO FLOOR TROUGH.

9 4 SAN TO FLOOR DRAIN/SINK.


- 10 ROUTE IN CEILING SPACE OF GYM. ROUTE ALONG SIDE NEW MECHANICAL PIPING.
- COORIDINATE FINAL ROUTING WITH MECHANICAL TRADES. 11 PIPING IN THIS AREA ROUTED WITHIN SECOND FLOOR CEILING SPACE.



STATE OF MICHIGAN
DEPARTMENT OF TECHNOLO DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE CONTRACT NO. 171CODHHS7255





WTAARCHITECTS

COPYRIGHT © 2023

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

PENTHOUSE PLUMBIN PLAN


SHEET NUMBER


M2.03

PROJECT NUMBER PROJECT DATE SEPTEMBER 6, 2023 CHECKED BY

WEK







HVAC PIPING GENERAL NOTES:


THESE DRAWINGS ARE DIAGRAMMATIC, AND REPRESENT THE GENERAL INTENT AND ARRANGEMENT OF SYSTEMS. THEY ARE NOT TO BE CONSIDERED FABRICATION/COORDINATION/SHOP DRAWINGS. COORDINATION WITH OTHER TRADES IS REQUIRED. PROVIDE THE ADDITIONAL FITTINGS AND OFFSETS THAT WILL BE REQUIRED TO COMPLETE EACH SYSTEM AND TO AVOID INTERFERENCES WITH ALL OTHER SYSTEMS INCLUDING THE STRUCTURE, SHEET METAL, OTHER PIPING SYSTEMS, ELECTRICAL CONDUITS, BUS DUCTS, CABLE TRAY, LIGHT FIXTURES, ETC. AND/OR OTHER SPACE CONSTRAINTS.


- INSTALL SYSTEMS SUCH THAT REQUIRED CLEARANCE AND SERVICE ACCESS SPACE IS PROVIDED AROUND ALL MECHANICAL AND ELECTRICAL EQUIPMENT, AND AROUND ANY COMPONENTS WHICH REQUIRE SERVICE ACCESS.
- PIPING AND DUCTWORK SHALL NOT BE INSTALLED ABOVE ELECTRICAL TRANSFORMERS, SWITCHBOARDS, PANELBOARDS OR MOTOR CONTROL CENTERS. 4 COORDINATE AND PROVIDE ACCESS DOORS WITHIN INACCESSIBLE CEILING, SHAFT, AND CHASE AREAS FOR ALL COMPONENTS WHICH REQUIRE SERVICE ACCESS. REFER TO ARCHITECTURAL DRAWINGS FOR CEILING TYPES.
- PROVIDE SUPPLEMENTARY STEEL AS REQUIRED FOR THE PROPER SUPPORT OF ALL SYSTEMS.
- 6 SUBMIT PROPOSED METHODS OF ANCHORING AND GUIDING PIPING SYSTEMS TO STRUCTURAL ENGINEER FOR APPROVAL.
- 7 COORDINATE LOCATION OF DUCT-MOUNTED HYDRONIC DEVICES WITH SHEET METAL
- 8 BRANCH PIPING SERVING TERMINAL UNIT HEATING COILS OR RADIANT CEILING PANELS SHALL BE 3/4" UNLESS OTHERWISE NOTED. BRANCH PIPING SERVING MORE THAN ONE TERMINAL UNIT HEATING COIL SHALL BE 1" UNLESS OTHERWISE NOTED. BRANCH PIPING SERVING HOT WATER UNIT HEATERS AND CABINET UNIT HEATERS SHALL BE 1" UNLESS OTHERWISE NOTED.
- REFER TO TEMPERATURE CONTROLS STANDARD MOUNTING HEIGHTS DETAIL FOR ELEVATIONS OF WALL MOUNTED TEMPERATURE CONTROL DEVICES.


CONSTRUCTION KEY NOTES:


1 EMERGENCY BOILER SHUT OFF GLYCOL MAKEUP UNIT

- 3 LENGTHS SHOWN ARE ACTIVE ELEMENT LENGTH. CONTRACTOR TO SUPPLY FULL LENGTH
- 4 ROUTE CHWS, CHWR, AND STEAM UP TO CEILING SPACE AND ROUTE THRUOGH JOIST SPACE.
- 5 3" CHWS, 3" CHWR, 1" STEAM UP TO PENTHOUSE. REFER TO SHEET M3.03 FOR CONTINUATION.
- 6 3" HWHS AND HWHR UP TO PENTHOUSE. REFER TO SHEET M3.03 FOR CONTINUATION.
- 7 3" CHWS, 3" CHWR, 1" STEAM DOWN TO FIRST FLOOR. REFER TO SHEET M3.01 FOR CONTINUATION.
- 8 3" HWHS AND HWHR DOWN TO FIRST FLOOR. REFER TO SHEET M3.01 FOR CONTINUATION.
- 9 ROUTE MECHANICAL PIPING IN CEILING SPACE OF GYM. COORIDINATE FINAL ROUTING WITH MECHANICAL TRADES.
- 10 EXISTING LINES THAT NEW MECHANICAL PIPING WILL TIE INTO ARE LOCATED ON SECOND










SHEET NUMBER

M3.03



PENTHOUSE SHEET METAL PLAN

SCALE: 1/4" = 1'-0"

SHEET METAL GENERAL NOTES:

COMPONENTS WHICH REQUIRE SERVICE ACCESS.

THESE DRAWINGS ARE DIAGRAMMATIC, AND REPRESENT THE GENERAL INTENT AND ARRANGEMENT OF SYSTEMS. THEY ARE NOT TO BE CONSIDERED FABRICATION/COORDINATION/SHOP DRAWINGS. COORDINATION WITH OTHER TRADES IS REQUIRED. PROVIDE THE ADDITIONAL FITTINGS AND OFFSETS THAT WILL BE REQUIRED TO COMPLETE EACH SYSTEM AND TO AVOID INTERFERENCES WITH ALL OTHER SYSTEMS INCLUDING THE STRUCTURE, PIPING SYSTEMS, ELECTRICAL CONDUITS, BUS DUCTS, CABLE TRAY, LIGHT FIXTURES, ETC. AND/OR OTHER SPACE CONSTRAINTS.


- 2 INSTALL SYSTEMS SUCH THAT REQUIRED CLEARANCE AND SERVICE ACCESS SPACE IS PROVIDED AROUND ALL MECHANICAL AND ELECTRICAL EQUIPMENT, AND AROUND ANY
- 3 PIPING AND DUCTWORK SHALL NOT BE INSTALLED ABOVE ELECTRICAL TRANSFORMERS,
- 4 COORDINATE AND PROVIDE ACCESS DOORS WITHIN INACCESSIBLE CEILING, SHAFT, AND CHASE AREAS FOR ALL COMPONENTS WHICH REQUIRE SERVICE ACCESS. REFER TO ARCHITECTURAL DRAWINGS FOR CEILING TYPES.


SWITCHBOARDS, PANELBOARDS OR MOTOR CONTROL CENTERS.


- 5 PROVIDE SUPPLEMENTARY STEEL AS REQUIRED FOR THE PROPER SUPPORT OF ALL
- 6 REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR DIMENSIONED LOCATION OF GRILLES, REGISTERS, AND DIFFUSERS.
- 7 REFER TO TEMPERATURE CONTROLS STANDARD MOUNTING HEIGHTS DETAIL FOR ELEVATIONS OF WALL MOUNTED TEMPERATURE CONTROL DEVICES.

CONSTRUCTION KEY NOTES:


- 1 10x10 EXHAUST DUCT UP TO EF-8H
- 2 10x10 EXHAUST DUCT UP TO EF-7H
- 3 10x10 EXHAUST DUCT UP TO EF-6H
- 3 TOXTO EXTINGOT DOCT OF TO
- 4 20x20 DUCT UP TO EF-10H
 5 18x18 EXHAUST UP TO EF-9H
- 6 58x16 UP TO AHU-21H. REFER TO SHEET M4.03 FOR CONTINUATION.
- 7 REFER TO DUCT SYSTEM APPLICATION SCHEDULE FOR DUCT TYPE.
- 8 30"x30" RETURN DUCT WITH BELLMOUTH AT END.
- 9 16"x58" RETURN AIR DUCT UP TO AHU-21H. REFER TO SHEET M4.03 FOR CONTINUATION.
- 10 16"x16" MAKEUP AIR TO EXHAUST HOODS. (TYP. x 4)
- 11 10"x12" MAKEUP AIR TO EXHAUST HOODS. (TYP. x 4)
- 12 60"X16" UP TO AHU-22H. REFER TO SHEET M4.03 FOR CONTINUATION.
- 13 RECOMMENDED LOCATION FOR PIPE PORTAL.
- 14 60"x16" SUPPLY AIR DUCT DOWN TO FIRST FLOOR. REFER TO SHEET M4.01 FOR CONTINUATION.
- 15 58"x16" RETURN AIR DOWN TO FIRST FLOOR. REFER TO SHEET M4.01 FOR CONTINUATION.
- 16 58"x16" SUPPLY AIR DOWN TO FIRST FLOOR. REFER TO SHEET M4.01 FOR CONTINUATION.
- 17 EVACUATE SYSTEM. RELOCATE EXISTING CONDENSING UNITS TO LOCATION SHOWN. PROVIDE NEW REFRIGERANT LINES. RECHARGE AND RECOMMISION UNITS.







Peter Basso Associates Inc CONSULTING ENGINEERS 5145 Livernois, Suite 100 Troy, Michigan 48098-3276 Tel: 248-879-5666 Fax: 248-879-0007 www.PeterBassoAssociates.com PBA Project No.: 2021-0402




DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION

DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

491/20167.SDW

FILE NO.

FUNDING CODE CONTRACT NO. Y22003



WTAARCH.COM

COPYRIGHT © 2023



WTAARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN


SALINE, MICHIGAN

PENTHOUSE SHEET METAL PLAN

PROJECT NUMBER
2021094

PROJECT DATE
SEPTEMBER 6, 2023

CHECKED BY
WEK



PLUMBING GENERAL NOTES:


- THESE DRAWINGS ARE DIAGRAMMATIC, AND REPRESENT THE GENERAL INTENT AND ARRANGEMENT OF SYSTEMS. THEY ARE NOT TO BE CONSIDERED FABRICATION/COORDINATION/SHOP DRAWINGS. COORDINATION WITH OTHER TRADES IS REQUIRED. PROVIDE THE ADDITIONAL FITTINGS AND OFFSETS THAT WILL BE REQUIRED TO COMPLETE EACH SYSTEM AND TO AVOID INTERFERENCES WITH ALL OTHER SYSTEMS INCLUDING THE STRUCTURE, SHEET METAL, OTHER PIPING SYSTEMS, ELECTRICAL CONDUITS, BUS DUCTS, CABLE TRAY, LIGHT FIXTURES, ETC. AND/OR OTHER SPACE
- INSTALL SYSTEMS SUCH THAT REQUIRED CLEARANCE AND SERVICE ACCESS SPACE IS PROVIDED AROUND ALL MECHANICAL AND ELECTRICAL EQUIPMENT, AND AROUND ANY COMPONENTS WHICH REQUIRE SERVICE ACCESS.
- 3 PIPING SHALL NOT BE INSTALLED ABOVE ELECTRICAL TRANSFORMERS, SWITCHBOARDS, PANELBOARDS OR MOTOR CONTROL CENTERS.
- 4 COORDINATE AND PROVIDE ACCESS DOORS WITHIN INACCESSIBLE CEILING, SHAFT, AND CHASE AREAS FOR ALL COMPONENTS WHICH REQUIRE SERVICE ACCESS. REFER TO ARCHITECTURAL DRAWINGS FOR CEILING TYPES.
- 5 PROVIDE SUPPLEMENTARY STEEL AS REQUIRED FOR THE PROPER SUPPORT OF ALL
- 6 REFER TO ARCHITECTURAL PLANS FOR DIMENSIONED LOCATIONS OF PLUMBING FIXTURES.
- 7 HOT AND COLD WATER PIPING RUN-OUTS TO LAVATORIES AND SINKS SHALL BE 1/2" UNLESS
- 8 PLUMBING VENT PIPING THROUGH ROOF SHALL BE LOCATED A MINIMUM OF 10'-0" FROM ANY FRESH AIR INTAKE LOCATION AND A MINIMUM OF 18" CLEAR FROM THE INSIDE FACE OF
- 9 PROVIDE CODE REQUIRED CLEARANCE FOR ALL CLEANOUTS INSTALLED IN SANITARY WASTE AND VENT PIPING.
- 10 MINIMUM UNDERGROUND PIPE SIZE SHALL BE 3".

SHEET METAL GENERAL NOTES:

- 1 THESE DRAWINGS ARE DIAGRAMMATIC, AND REPRESENT THE GENERAL INTENT AND ARRANGEMENT OF SYSTEMS. THEY ARE NOT TO BE CONSIDERED FABRICATION/COORDINATION/SHOP DRAWINGS. COORDINATION WITH OTHER TRADES IS REQUIRED. PROVIDE THE ADDITIONAL FITTINGS AND OFFSETS THAT WILL BE REQUIRED TO COMPLETE EACH SYSTEM AND TO AVOID INTERFERENCES WITH ALL OTHER SYSTEMS INCLUDING THE STRUCTURE, PIPING SYSTEMS, ELECTRICAL CONDUITS, BUS DUCTS, CABLE TRAY, LIGHT FIXTURES, ETC. AND/OR OTHER SPACE CONSTRAINTS.
- INSTALL SYSTEMS SUCH THAT REQUIRED CLEARANCE AND SERVICE ACCESS SPACE IS PROVIDED AROUND ALL MECHANICAL AND ELECTRICAL EQUIPMENT, AND AROUND ANY COMPONENTS WHICH REQUIRE SERVICE ACCESS.
- 3 PIPING AND DUCTWORK SHALL NOT BE INSTALLED ABOVE ELECTRICAL TRANSFORMERS, SWITCHBOARDS, PANELBOARDS OR MOTOR CONTROL CENTERS.
- 4 COORDINATE AND PROVIDE ACCESS DOORS WITHIN INACCESSIBLE CEILING, SHAFT, AND CHASE AREAS FOR ALL COMPONENTS WHICH REQUIRE SERVICE ACCESS. REFER TO ARCHITECTURAL DRAWINGS FOR CEILING TYPES.
- 5 PROVIDE SUPPLEMENTARY STEEL AS REQUIRED FOR THE PROPER SUPPORT OF ALL
- 6 REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR DIMENSIONED LOCATION OF
- 7 REFER TO TEMPERATURE CONTROLS STANDARD MOUNTING HEIGHTS DETAIL FOR ELEVATIONS OF WALL MOUNTED TEMPERATURE CONTROL DEVICES.

CONSTRUCTION KEY NOTES:


- 1 10x10 EXHAUST DUCT UP TO EF-8H
- 2 10x10 EXHAUST DUCT UP TO EF-7H
- 3 10x10 EXHAUST DUCT UP TO EF-6H
- 4 20x20 DUCT UP TO EF-10H
- 5 18x18 EXHAUST UP TO EF-9H
- 6 58x16 UP TO AHU-21H. REFER TO SHEET M4.03 FOR CONTINUATION.
- 7 REFER TO DUCT SYSTEM APPLICATION SCHEDULE FOR DUCT TYPE.
- 8 30"x30" RETURN DUCT WITH BELLMOUTH AT END.
- 9 16"x58" RETURN AIR DUCT UP TO AHU-21H. REFER TO SHEET M4.03 FOR CONTINUATION.
- 10 16"x16" MAKEUP AIR TO EXHAUST HOODS. (TYP. x 4)
- 11 10"x12" MAKEUP AIR TO EXHAUST HOODS. (TYP. x 4)
- 12 60"X16" UP TO AHU-22H. REFER TO SHEET M4.03 FOR CONTINUATION.
- 13 RECOMMENDED LOCATION FOR PIPE PORTAL.
- CONTINUATION.
- 15 58"x16" RETURN AIR DOWN TO FIRST FLOOR. REFER TO SHEET M4.01 FOR CONTINUATION.
- 16 58"x16" SUPPLY AIR DOWN TO FIRST FLOOR. REFER TO SHEET M4.01 FOR CONTINUATION.
- 17 EVACUATE SYSTEM. RELOCATE EXISTING CONDENSING UNITS TO LOCATION SHOWN. PROVIDE NEW REFRIGERANT LINES. RECHARGE AND RECOMMISION UNITS.




STATE OF MICHIGAN DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE CONTRACT NO. 171CODHHS7255 Y22003





WTA A RCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500: CENTER FOR FORENSIC

PSYCHIATRY - CREATE

KITCHEN

SALINE, MICHIGAN

MECHANICAL ROOF PLAN

PROJECT NUMBER 2021094 PROJECT DATE

SHEET NUMBER M4.04SEPTEMBER 6, 2023 CHECKED BY WEK


Peter Basso Associates Inc CONSULTING ENGINEERS 5145 Livernois, Suite 100 Troy, Michigan 48098-3276 Tel: 248-879-5666 Fax: 248-879-0007 www.PeterBassoAssociates.com PBA Project No.: 2021-0402

PLUMBING GENERAL NOTES:

- THESE DRAWINGS ARE DIAGRAMMATIC, AND REPRESENT THE GENERAL INTENT AND ARRANGEMENT OF SYSTEMS. THEY ARE NOT TO BE CONSIDERED FABRICATION/COORDINATION/SHOP DRAWINGS. COORDINATION WITH OTHER TRADES IS REQUIRED. PROVIDE THE ADDITIONAL FITTINGS AND OFFSETS THAT WILL BE REQUIRED TO COMPLETE EACH SYSTEM AND TO AVOID INTERFERENCES WITH ALL OTHER SYSTEMS INCLUDING THE STRUCTURE, SHEET METAL, OTHER PIPING SYSTEMS, ELECTRICAL CONDUITS, BUS DUCTS, CABLE TRAY, LIGHT FIXTURES, ETC. AND/OR OTHER SPACE CONSTRAINTS.
- 2 INSTALL SYSTEMS SUCH THAT REQUIRED CLEARANCE AND SERVICE ACCESS SPACE IS PROVIDED AROUND ALL MECHANICAL AND ELECTRICAL EQUIPMENT, AND AROUND ANY COMPONENTS WHICH REQUIRE SERVICE ACCESS.
- 3 PIPING SHALL NOT BE INSTALLED ABOVE ELECTRICAL TRANSFORMERS, SWITCHBOARDS, PANELBOARDS OR MOTOR CONTROL CENTERS.
- 4 COORDINATE AND PROVIDE ACCESS DOORS WITHIN INACCESSIBLE CEILING, SHAFT, AND CHASE AREAS FOR ALL COMPONENTS WHICH REQUIRE SERVICE ACCESS. REFER TO ARCHITECTURAL DRAWINGS FOR CEILING TYPES.
- 5 PROVIDE SUPPLEMENTARY STEEL AS REQUIRED FOR THE PROPER SUPPORT OF ALL
- 6 REFER TO ARCHITECTURAL PLANS FOR DIMENSIONED LOCATIONS OF PLUMBING FIXTURES.
- 7 HOT AND COLD WATER PIPING RUN-OUTS TO LAVATORIES AND SINKS SHALL BE 1/2" UNLESS OTHERWISE NOTED.
- 8 PLUMBING VENT PIPING THROUGH ROOF SHALL BE LOCATED A MINIMUM OF 10'-0" FROM ANY FRESH AIR INTAKE LOCATION AND A MINIMUM OF 18" CLEAR FROM THE INSIDE FACE OF
- 9 PROVIDE CODE REQUIRED CLEARANCE FOR ALL CLEANOUTS INSTALLED IN SANITARY WASTE AND VENT PIPING.
- 10 MINIMUM UNDERGROUND PIPE SIZE SHALL BE 3".


CONSTRUCTION KEY NOTES:

- 1 3 SAN, 2 V, 1/2 CW, 1/2 HW, AND 1/2 HWR TO SINK.
- 2 3 SAN, 1 1/2 V, 1/2 CW, 1/2 HW TO SINK.
- 3 3/4 CW AND 3/4 HW THROUGHT CODE REQUIRED BACKFLOW PREVENTER AND CONNECT TO HOSE REAL MIXING VALVE.
- 4 1/2 CW TO OULETBOX FOR ICE MAKER.
- 5 3/4 CW, 3/4 HW TO 3 COMPARTMENT SINK. ROUTE 3 GSAN FROM WASH COMPARTMENT. ROUTE IW FROM RINSE AND SANITIZE COMPARTMENT AND TERMINATE AT CODE REQUIRED DISTANCE ABOVE FLOOR SINK.
- 6 3/4 CW, 3/4 HW TO PRE-SPRAY AND FOOD GRINDER.
- 7 1/2 CW, 1/2 HW(140), AND 1/2 HWR(140) THROUGH CODE REQUIRED BACKFLOW PREVENTER. ROUTE 1/2 CW, 1/2 HW(140) FROM BACKFLOW PREVENTER TO DISHMACHINE. ROUTE IW FROM BACKFLOW PREVENTER AND DISHMACHINE AND TERMINATE AT CODE REQUIRED DISTANCE ABOVE FLOOR SINK.
- 8 3/4 CW, 3/4 HW, 1/2 HWR, AND 3 GAS TO UTILITY DISTRIBUTIONS SYSTEM.
- 9 1 CW AND 1 HW TO PENTHOUSE ABOVE.
- 10 4 SAN TO FLOOR DRAIN/SINK.
- 11 TERMINATE CONDENSATE AT CODE REQUIRED DISTANCE ABOVE FLOOR DRAIN/SINK.
- 12 3 SAN FOR FLOOR DRIAN/SINK.



491/20167.SDW

FUNDING CODE CONTRACT NO. Y22003



WTAARCH.COM

COPYRIGHT © 2023



WTAARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

SHEET TITLE
PLUMBING ENLARGED PLAN

Peter Basso Associates Inc CONSULTING ENGINEERS 5145 Livernois, Suite 100 Troy, Michigan 48098-3276 Tel: 248-879-5666 Fax: 248-879-0007 www.PeterBassoAssociates.com


PBA Project No.: 2021-0402

PROJECT NUMBER
2021094


PROJECT DATE
SEPTEMBER 6, 2023

CHECKED BY
WEK


BOILER PIPING DIAGRAM NO SCALE



IN-LINE CLOSE COUPLED (BELL AND GOSSETT SERIES 80 AND 90) TYPE CIRCULATING PUMP PIPING DIAGRAM
NO SCALE








1	ADDENDUM #3	09/29/23
NO.	REVISION	DATE

DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET

FACILITIES AND BUSINESS SERVICES ADMINISTRATION



FUNDING CODE

171CODHHS7255

FILE NO. 491/20167.SDW

STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY

CONTRACT NO.
Y22003



WTAARCH.COM

WTAARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

WEK

MECHANICAL DETAILS

PROJECT NUMBER
2021094

PROJECT DATE
AUGUST 23, 2023

CHECKED BY


PROJECT DATE
AUGUST 23, 2023

NO SCALE


DETAIL INDICATES THE INSTALLATION REQUIREMENTS FOR A FIRE RATED ASSEMBLY. FOR A NON-FIRE RATED ASSEMBLY PACK SLEEVED OPENING WITH INSULATION MATERIAL AND CAULK WITH NON-HARDENING SEALANT.

FIRE RATED AND NON-FIRE RATED METAL STUD AND

DRYWALL PARTITION WALL PIPE PENETRATION DETAIL



FIRE RATED AND NON-FIRE RATED POURED CONCRETE OR BLOCK WALL PIPE PENETRATION DETAIL



MECHANICAL

These documents are approved


for compliance with the

subject to field inspection and the


conditions of approval.

ATE OF MICHIGAN MECHANICAL CODE

NEW SLAB ON GRADE FLOOR PIPE PENETRATION DETAIL




NEW FLOOR PIPE PENETRATION DETAIL




EXTERIOR WALL ___ STORM COLLAR COMBUSTION AIR WITH SEALANT PIPE, REFER TO SPECIFICATIONS FOR FLASHING ~ MATERIAL PROVIDE VENT SCREEN OVER OPENING -

COMBUSTION AIR INTAKE DETAIL




BRANCH CONNECTION OFF TOP APPLIES TO THE FOLLOWING SYSTEMS: DOMESTIC WATER NATURAL GAS



APPLIES TO THE FOLLOWING SYSTEMS: HOT WATER HEATING

NOTE: BOTTOM AS INDICATED OR SIDE CONNECTION IS ACCEPTABLE. CONNECTION ABOVE CENTERLINE OF MAINS IS NOT ACCEPTABLE.


TYPICAL BRANCH TAKE-OFF CONNECTION PIPING DETAIL NO SCALE







↔

SUPPLY DUCT






RECTANGULAR DUCT BRANCH TAKE-OFF DETAILS



RETURN OR EXHAUST DUCT




EYEWASH HEAD DUCT

COVER (TYP)——

STAINLESS STEEL RECEPTOR———


FLOOR FLANGE—

FLOOR LINE \




ELECTRIC ACTUATOR - VERTICAL STEAM DISPERSION TUBE HUMIDIFIER~ — BLANK TUBLET FOR CONDENSATE DRAINAGE 3/4 LPC —— —SELF MODULATING 1 1/2 DRAIN~ ___ THERMOSTATIC CONTROL VALVE 3/4 BLOW ~3/4 NPCW DOWN — 1 1/2 DRAIN -CONDENSATE DRAIN COOLER TO OVER FLOOR (SET THERMOSTATIC VALVE AT 135°F) DRAIN ----


VERTICAL STEAM DISPERSION TUBE HUMIDIFIER PANEL PIPING DIAGRAM




OUTDOOR AIR INTAKE OR EXHAUST/RELIEF PLENUM DETAIL NO SCALE




FLOOR MOUNTED EMERGENCY EYEWASH PIPING DIAGRAM



ROOF CONDUCTOR AND SANITARY STACK BASE CONNECTION DETAIL
NO SCALE







OWNER REVIEW

REVISION

DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET

CONTRACT NO.

Y22003

FACILITIES AND BUSINESS SERVICES ADMINISTRATION

DESIGN AND CONSTRUCTION DIVISION

STATE OF MICHIGAN

FILE NO.

491/20167.SDW

171CODHHS7255

FUNDING CODE

ADAM LACH, RA, DIRECTOR

DATE

KEY PLAN

NO SCALE

PSYCHIATRY - CREATE KITCHEN
SALINE, MICHIGAN

CENTER FOR FORENSIC

491/20167.SDW - PHASE 500:


SHEET TITLE MECHANICAL DETAILS


tes Inc ERS	PROJECT NUMBER 2021094	SHEET NUMBER
00 276	PROJECT DATE AUGUST 23, 2023	M6.02
s.com	CHECKED BY	


WEK

RETURN OR EXHAUST AIR DEVICE INSTALLATION DETAIL NO SCALE

NOTE: PAINT INTERIOR SURFACE OF PLENUM BOX FLAT BLACK.












SUPPLY TU CONFIGURATION

AIR DEVICE—








STAINLESS STEEL UNISTRUT WITH CLAMPS SUPPORTED FROM WALL (TYP) WALL OF BUILDING — REFER TO ARCH. DRAWINGS FOR WALL MATERIALS — REFER TO ROOF MOUNTED PIPING SUPPORT APPLICATION SCHEDULE AIR TERMINAL UNIT (TU) DETAIL



-EXTERIOR FINISHED WALL

(REFER TO ARCH. DWGS)



1. SUPPORT ELBOW INDEPENDENT

DIMENSIONS ARE INSIDE CLEAR

1. RETURN AIR CANOPY. GALVANIZED STEEL WITH

OF CEILING GRID

LINE SHEET METAL DUCT WITH

1" THICK ACOUSTICAL

MULTIPLE COIL BANK BRANCH

PIPE SIZING SCHEDULE

INDIVIDUAL COIL PIPE

7 – 12.5 | 1 1/4

12.6 - 19 1 1/2

FLOW GPM

1.4 - 3.4

45 - 69

70 – 117

118 – 230 4

3.5 - 6.9

0 - 1.3

INSULATION —

NO TURNING

VANES-

AHU CHILLED WATER COOLING COIL WITH TWO-WAY CONTROL VALVE PIPING DIAGRAM

TO OTHER COILS

IN COIL BANK—

CHILLED WATER

COOLING COIL -

OFFSET PIPING TO

PROVIDE CLEARANCE

FOR COIL PULL (TYP)—

PRESSURE DEPENDENT CONTROL VALVE

TO OTHER COIL BANK

1. VERIFY NUMBER OF COILS AND

2. UNIONS MAY BE DELETED AT

COIL CONNECTION

-HOSE END DRAIN


CONNECTION (TYP)

COIL BANKS FOR EACH AHU WITH


MANUFACTURER. PROVIDE PIPING AS INDICATED FOR EACH COIL

FLANGED CONNECTIONS TO VALVES


3. PROVIDE REDUCER/INCREASER AT




AHU HOT WATER HEATING COIL PIPING DIAGRAM




ROUND NECK SUPPLY AIR DIFFUSER DETAIL



DOWNFEED CONV. OR CUH WITH THREE WAY CONTROL VALVE PIPING DIAGRAM




HOT WATER TEMPERING COIL WITH THREE-WAY CONTROL VALVE PIPING DIAGRAM



PROVIDE MANUAL VENT AT ALL





OWNER REVIEW	08/02/23
REVISION	DATE

STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

> CONTRACT NO. **FUNDING CODE** 171CODHHS7255 Y22003



WTA A RCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

SHEET TITLE MECHANICAL DETAILS


ROJECT NUMBER PROJECT DATE AUGUST 23, 2023 CHECKED BY

WEK


M6.03

SHEET NUMBER


HOT WATER UNIT HEATER WITH THREE-WAY CONTROL VALVE PIPING DIAGRAM
NO SCALE




END FEED LINEAR RADIANT CEILING
PANEL WITH THREE-WAY CONTROL VALVE
PIPING DIAGRAM
NO SCALE




ROOF MOUNTED POWER VENTILATOR EXHAUST FAN DETAIL




FIN TUBE RADIATION WITH THREE-WAY CONTROL VALVE PIPING DIAGRAM
NO SCALE



TYPICAL SPRINKLER PIPING DETAIL



ROOF MOUNTED UPBLAST KITCHEN **EXHAUST FAN DETAIL**




AIR TRANSFER DUCT DETAILS


			Ti	RAP DI	MENSIO	N TABL	.E							
T./DE 05	S.P. AT DRAIN	DIMENSION "A"	DIMENSION "B"	DIMENSION "C"	DIMENCION "D"	DIMENCION "E"		DIMENSION '	'F" (INCHES)					
TYPE OF SYSTEM	PAN (IN.)	(INCHES)	(INCHES)	(INCHES)	DIMENSION "D" (INCHES)	DIMENSION "E" (INCHES)	DRAIN PIPE SIZE (INCHES)							
0.0.2	(NOTE A)	MIN.	((TRAP SEAL)	()	()	1 1/2	2	2 1/2, 3	4				
	−5.1 TO −6	5.0	5.0	2	6	2	13.0	14.0	15.0	16.0				
OUGH	-4.1 TO -5	4.5	4.5	2	5	2	12.0	13.0	14.0	15.0				
DRAW THROUGH	-3.1 TO -4	4.0	4.0	2	4	2	11.0	12.0	13.0	14.0				
DRAW	-2.1 TO -3	3.5	3.5	2	3	2	10.0	11.0	12.0	13.0				
	UP TO −2	3.0	3.0	2	2	2	9.0	10.0	11.0	12.0				
	UP TO +2	4.0	2.0	2	2	4	9.0	10.0	11.0	12.0				
ЭОСН	+2.1 TO +3	5.0	2.0	2	3	5	10.0	11.0	12.0	13.0				
BLOW THROUGH	+3.1 TO +4	6.0	2.0	2	4	6	11.0	12.0	13.0	14.0				
BLOW	+4.1 TO +5	7.0	2.0	2	5	7	12.0	13.0	14.0	15.0				
	+5.1 TO +6	8.0	2.0	2	6	8	13.0	14.0	15.0	16.0				


NOTES: A. REFER TO AIR HANDLING UNIT SCHEDULE FOR (-) OR (+) STATIC PRESSURE AT DRAIN PAN.

B. DIMENSION "G" IS MIN: 3" FOR UP TO 1 1/2" DRAIN PIPE 4" FOR 2" DRAIN PIPE 5" FOR 2 1/2" OR 3" DRAIN PIPE 6" FOR 4" DRAIN PIPE



INDOOR AIR HANDLING UNIT CONDENSATE DRAIN PAN TRAP DETAIL





1	OWNER REVIEW	08/02/23
NO.	REVISION	DATE

STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

> FUNDING CODE CONTRACT NO. 171CODHHS7255 Y22003





WTA A RCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

MECHANICAL DETAILS

PROJECT NUMBER Peter Basso Associates Inc CONSULTING ENGINEERS 5145 Livernois, Suite 100 PROJECT DATE Troy, Michigan 48098-3276 AUGUST 23, 2023 Tel: 248-879-5666 Fax: 248-879-0007 CHECKED BY

WEK

M6.04

SHEET NUMBER

									PI	_UN	ИВI	NG	P	PIN	IG	&	VA	LV	E	API		CA	TIC	N	SC	HE	DU	ILE											
	T							MATE											<u> </u>					CTIONS							/ITY D				ISOLA ⁷	TION V	ALVES		
	PE K	TYPE L	TYPE M	(SCHED. 40)	(ടന്.)	HED. 40)	(SCHED. 10)			CARBON STEEL PIPE				E	Λ	ш										ORMED TEE	T						STESS			: Butterfly			
PIPE SIZE (INCHES)	SOFT COPPER TYPE	HARD COPPER TY	HARD COPPER TY	CARBON STEEL (9	CARBON STEEL (GALV. STEEL (SCHED.	STAINLESS STEEL	PEX	PE PIPE	PE SHEATHED CA	CSST	NO-HUB CISP	PVC TYPE DWV	PP DRAINAGE PIPE	COPPER TYPE DWV	DUCTILE IRON PIPE	SOLDERED	BRAZED	WELDED	THREADED	FLANGED	GROOVED	INSERT & CRIMP	FUSION	PRESSURE-SEAL	MECHANICALLY-FORMED	MECHANICAL JOINT	PUSH-ON-JOINT	SOLVENT WELDED	SOLDERED	FUSION	CISP HUBLESS	HEAVY—DUTY HUBLESS	BALL	AGA BALL	GENERAL SERVICE	LUBRICATED PLUG	GATE	KEYED NOTES
ABOVEGROUND DOM	_	•			•	•																		•		DEG F						_							
UP TO 4		Х															Х	Х			Х													Х		Х			А
4 AND LARGER							Х																													Х			Α
UNDERGROUND DOME	STIC	WATE	R (PC	TABL	E AN	ID NO	N-PO	TABLE	E) ON	DIST	RIBUT	ION S	IDE C	OF ME	TER	- MIN.	WOF	RKING	PRES	SS. &	TEMF	P.: 125	PSIG	AT	150 DI	EG F													•
UP TO 1-1/2	Х																																						В
ABOVEGROUND SANI	TARY	WAST	E&\	VENT	- MIN	ı. WO	RKING	3 PRE	SS.: 1	0-FOC	OT HE	AD O	F WA	TER																									
1-1/2 TO 15												Х																				Χ							
ABOVEGROUND PUMI	PED SA	ANITAI	RY W	ASTE	- MI	N. WO	RKIN	G PRE	E88.•	125 PS	SIG																												
UP TO 2		Х															Х	Х																Х					
ABOVEGROUND INDIR	ECT S	ANITA	RY W	VASTI	E - M	IN. W	ORKIN	NG PR	ESS.	10-FC	от н	EAD	OF W	ATER			•							•						•									•
UP TO 8			Х												Х															Х									
ABOVEGROUND PUMI	PED INI	DIREC	T SAI	NITAR	RY W	ASTE	- MIN	ı. WOI	RKING	PRES	38. _' 12	25 PS	IG																										
JP TO 2		Х															Х	Х																Х					
UNDERGROUND SANI	TARY \	WAST	E&V	ENT	- MIN	I. WOF	RKING	PRE	88. _' 10)-F00	T HE	AD O	F WA	TER																									
3 TO 12												Х																					Х						
3 TO 12													Х																Χ										
ABOVEGROUND COLI	CON	DENS	ATE D	RAIN	- MIN	I. WO	RKING	9 PRE	SSUR	E: 10	FT. H	EAD (OF W	ATER								•	i	•	i	•				•								i	
ALL SIZES			Х												Х		Χ	Χ																					
ABOVEGROUND PUMI	PED CO	OLD C	ONDE	NSAT	TE DF	RAIN -	MIN.	WORI	KING	PRES	SURE:	125 I	PSIG																	•									,
JP TO 2			Х														Х	Х																Х					
2-1/2 TO 4			Х															Х																		Х			
ABOVEGROUND STO	RM DR	AINAG	E - M	IIN. W	ORKI	NG PF	RESS.	• 10-F	OOT	HEAD	OF W	VATE	R			ı				ı		_		1	1	_						1							T
2	_											Х																				Х							ļ
3 TO 15												Χ																				Χ							
UNDERGROUND STOF	M DRA	AINAGI	E - M	IN. W	ORKI	NG PR	ESS.•	10-F0	OOT I	HEAD	OF W		}											1	1					<u> </u>	-							i	
3 TO 12												Х																					Х						
3 TO 12													Х											<u> </u>					Х										
15												Х																					Х						
ABOVEGROUND FUEL	GAS	- MIN.	WOR		PRE	88.: 10 T	O PS	SIG T	1											ı		1	1	1	1	1				1				ı				1	1
UP TO 2	—	_		X				_	_										Х	Х			_												Х				E _
2-1/2 TO 3	1			Х		1		1	Ĭ										Х		Χ	I	1	1	1	I		Ī							Х			1	E

- 1. 'X' INDICATES ACCEPTABLE SELECTION. IF MORE THAN ONE SELECTION IS INDICATED FOR A PIPING SYSTEM, CONTRACTOR MAY SELECT FROM THOSE INDICATED SELECTIONS.
- 2. DISSIMILAR-METAL PIPING JOINTS: CONSTRUCT JOINTS USING DIELECTRIC FITTINGS COMPATIBLE WITH BOTH PIPING MATERIALS.
 - a. NPS 2 AND SMALLER: USE DIELECTRIC NIPPLE/WATERWAY.
- b. NPS 2-1/2 AND LARGER: USE DIELECTRIC FLANGE KITS.
- 3. USE UNIONS OR FLANGES AT VALVE AND EQUIPMENT CONNECTIONS. 4. PLUMBING EQUIPMENT DRAINS, VENTS, SAFETY VALVE PIPING, BLOWDOWN PIPING AND THE LIKE SHALL BE SAME PIPING MATERIAL AS ASSOCIATED

KEYED NOTES

- A. FLANGED FITTINGS, JOINTS, AND COUPLINGS, IF INDICATED AS AN ACCEPTABLE SELECTION, MAY BE USED IN ACCESSIBLE LOCATIONS ONLY FOR THIS PIPING SYSTEM. ACCESSIBLE LOCATIONS ARE DEFINED AS EXPOSED CONSTRUCTION OR ABOVE LAY-IN CEILINGS.
- B. JOINTS ARE NOT PERMITTED ON UNDERGROUND WATER PIPING. C. USE CAST IRON DRAINAGE PATTERN (DURHAM) FITTINGS.
- D. INSTALL IN CONTAINMENT JACKET, REFER TO SPECIFICATIONS.
- E. VALVES, UNIONS, AND FLANGED JOINTS MAY BE USED IN ACCESSIBLE LOCATIONS ONLY, EXCLUDING CEILINGS USED AS AIR PLENUMS. ACCESSIBLE LOCATIONS ARE DEFINED AS EXPOSED CONSTRUCTION OR ABOVE LAY-IN CEILINGS. USE ONLY STEEL WELDED FITTINGS AND WELDED JOINTS IN CEILING USED AS AIR PLENUMS.
- F. NO JOINTS ALLOWED UNDERGROUND.

	PIPE PRESSU	JRE REQ	UIREME	NT SCHED	JLE		
PIPE SYSTEM	MINIMUM DESIGN PRESSURE	MINIMUM DESIGN TEMPERATURE (DEG. F)	WORKING PRESSURE	TEST PRESSURE	TEST FLUID	TEST TIME	ALLOWABLE LEAKAGE
CHILLED WATER	125 PSIG	200	<70 PSIG	150 PSIG	WATER	2 HOURS	NONE
HEATING HOT WATER	125 PSIG	200	<70 PSIG	150 PSIG	WATER	2 HOURS	NONE
LOW PRESSURE STEAM	125 PSIG	350	<15 PSIG	150 PSIG	WATER	2 HOURS	NONE
STEAM CONDENSATE	125 PSIG	250	<90 PSIG	150 PSIG	WATER	2 HOURS	NONE

ALL TESTS MUST BE WITNESSED AND SIGNED BY CMU. IF NOT, TEST WILL NEED TO BE REDONE AT CONTRACTOR'S EXPENSE.

TH	IERMOS	TATIC	MIXING VAL	VE SCHEDU	JLE
UNIT IDENTIFICATION	MINIMUM FLOW GPM	MAXIMUM FLOW GPM	PRESSURE DROP AT MAXIMUM FLOW PSIG	MODEL NUMBER	KEYED NOTES
MV-1	2	5	15	S19-2000	

GENERAL NOTES:

1. MODEL NUMBERS ARE BRADLEY UNLESS OTHERWISE NOTED.

	NAT	URAL	. GAS F	REGULA	TOR SCHE	DULE
	MARK	FLOW SCFH	PRES INLET	Sure Outlet	MAXIMUM ALLOWABLE DOWNSTREAM PRESSURE	KEYED NOTES
			(IN. W.C.)	(IN. W.C.)	(IN. W.C.)	
L	NGR-1	4000	14	7	7	

			S	UPPOF	RT TYF	PΕ			SHI	ELD T	YPE	
PIPE TYPE & SIZE	LOW FIXED—HEIGHT SINGLE—BASE STAND	LOW ADJUSTABLE-HEIGHT SINGLE-BASE STAND	HIGH ADJUSTABLE—HEIGHT SINGLE—BASE STAND	LOW FIXED HEIGHT SINGLE—BASE ROLLER STAND	LOW ADJUSTABLE—HEIGHT SINGLE—BASE ROLLER STAND	HIGH MULTIPLE-BASE PIPE STAND	CUSTOM MULTIPLE BASE PIPE STAND	CURB-MOUNTING PIPE STAND	MSS TYPE 39 PROTECTION SADDLE	MSS TYPE 40 INSULATION PROTECTION SHIELD	THERMAL—HANGER SHIELD	KEYED NOTES
SINGLE PIPES												
ATURAL GAS NPS 5 AND SMALLER				Χ	Χ			Χ				
ATURAL GAS NPS 6 AND NPS 8					Х			Χ				

1. "X" INDICATES APPROVED HANGER OR SUPPORT ELEMENTS. IF MORE THAN ONE HANGER OR SUPPORT ELEMENT IS INDICATED, SELECTION FROM APPROVED ELEMENTS IS CONTRACTOR'S OPTION. 2. REFER TO HANGER AND SUPPORT SECTION FOR APPROVED MANUFACTURERS. 3. SUPPORT ELEMENTS IN CONTACT WITH BARE COPPER PIPE SHALL BE COPPER PLATED, PLASTIC OR PLASTIC COATED, FELT LINED, OR USE

MANUFACTURED COPPER TUBE ISOLATORS <u>KEYED NOTES</u>

A. TYPE 40 SHIELD MAY BE USED ON INSULATED PIPE SIZED NPS 2 AND SMALLER. B. CONSULT WITH SUPPORT MANUFACTURER FOR CUSTOM SUPPORT REQUIREMENTS.

C. USE THERMAL HANGER SHIELD FOR INSULATED RING. D. TYPE 39 PROTECTION SADDLE MAY BE USED IF INSULATION WITHOUT VAPOR BARRIER IS INDICATED. FILL INTERIOR VOIDS WITH INSULATION MATCHING ADJOINING INSULATION.

ABOVE	3R(OUI	ND	Н١	/A(C F	PIPI	NG	&	٧	٩L١	/E	ΑP	PL	IC <i>F</i>	ATI	ON	S	CH	EDULE
			M	IATERIA	AL						CONNE	ECTION				ISC	DLATION	VAL\	/ES	
PIPE SIZE (INCHES)	SOFT COPPER TYPE K	HARD COPPER TYPE L	HARD COPPER TYPE M	CARBON STEEL (SCHED. 40)	CARBON STEEL (SCHED. 80)	CARBON STEEL (STD.)	COPPER TYPE DWV	SOLDERED	BRAZED	WELDED	THREADED	FLANGED	GROOVED	Pressure seal	MECHANICALLY FORMED TEE	ВАLL	GENERAL SERVICE BUTTERFLY	HI—PERF BUTTERFLY	GATE	KEYED NOTES
CHILLED WATER	SUPF	LY &	RETU	JRN -	MIN.	WOR	KING	PRES	S. & ⁻	ГЕМР.	125	PSIG	AT 20	00 DE	G F					
UP TO 2				Х							Х					Χ				
UP TO 2		Х						Х	Х							Χ				
2-1/2 TO 4				Х						Х		Х					Χ			
2-1/2 TO 4		Х							Х								Χ			
6 TO 8				Х						Х		Х					Х			
6 TO 8		Х							Х								Χ			
HEATING HOT W	ATER	SUPF	LY &	RET	URN -	MIN.	WOR	KING	PRES	S. &	TEMP.	125	PSIG	AT 2	00 DE	G F			•	
UP TO 2				Х							Х					Χ				
UP TO 2		Х						Х	Х							Х				
2-1/2 TO 4				Х						Х		Х					Х			
2-1/2 TO 4		Х							Х								Χ			
6 TO 8				Х						Х		Х					Χ			
6 TO 8		Х							Х								Χ			
LOW PRESSURE	STEA	M - V	AAX.	15 PS	IG ST	EAM	WOR	KING I	PRES	SURE		•							•	
UP TO 2-1/2				Х							Х					Χ				С
3 TO 4				Х						Х		Х						Х		
6 TO 8				Х						Х		Х						Χ		
10				Х						Х		Х						Х		
HIGH PRESSURE	STEA	M - M	AAX. 1	125 P	SIG S	TEAM	WOF	RKING	PRES	SSURI										
UP TO 2-1/2				Х							Х					Χ				С
3 TO 4				Х						Х		Х						Х		
6 TO 8				Х						Х		Х						Х		
STEAM CONDENS	SATE	- MIN	. WOI	RKING	PRE	SS. &	TEMI	P.: 125	PSIG	AT	250 D	EG F								
UP TO 2					Х						Х					Х				В
2-1/2 TO 4					Х					Х		Х						Х		
6 TO 8					Х					Х		Х						Х		
GENERAL NOTES																				
1. 'X' INDICATES ACC	CEPTAE	BLE SE	LECTIO	N. IF	MORE	THAN	ONE S	ELECTI	ON IS	INDICA	TED FO	OR A F	PIPING	SYSTE	M, CON	ITRACT	OR MA	Y		

- 1. 'X' INDICATES ACCEPTABLE SELECTION. IF MORE THAN ONE SELECTION IS INDICATED FOR A PIPING SYSTEM, CONTRACTOR MAY SELECT FROM THOSE INDICATED SELECTIONS.
- 2. DISSIMILAR-METAL PIPING JOINTS: CONSTRUCT JOINTS USING DIELECTRIC FITTINGS COMPATIBLE WITH BOTH PIPING MATERIALS. IF A BRONZE VALVE CONNECTS THE DISSIMILAR METALS NO FURTHER DIELECTRIC ISOLATION IS REQUIRED.
 - a. NPS 2 AND SMALLER: USE BRASS COUPLING, NIPPLE, OR UNION. b. NPS 2-1/2 AND LARGER: USE DIELECTRIC FLANGE KITS.
- 3. USE UNIONS OR FLANGES AT VALVE AND EQUIPMENT CONNECTIONS. 4. HVAC EQUIPMENT DRAINS, VENTS, SAFETY VALVE PIPING, BLOWDOWN PIPING AND THE LIKE SHALL BE SAME PIPING MATERIAL AS ASSOCIATED PIPING SYSTEM.

<u>KEYED NOTES</u>

A. NOT USED. B. BALL VALVE WITH 250 PSIG STEAM TRIM. C. BALL VALVE WITH 150 PSIG STEAM TRIM.

PLUM	IBING	CONNE	ECTION	N SCHE	EDULE
UNIT IDENTIFICATION	CW INCHES	HW INCHES	SAN INCHES	VENT INCHES	KEYED NOTES
UR-1	-	-	2	1 1/2	
WC-1	1 1/2	-	4	2	
LAV-1	1/2	1/2	1 1/2	1 1/2	
SK-1	3/4	3/4	1 1/2	1 1/2	
SS-1	3/4	3/4	3	-	
EWC-1	1/2	-	1 1/2	1 1/2	
FD-1	_	_	3	_	
FS-1	_	_	3	_	

GENERAL NOTES: 1. INDIVIDUAL WATER LINE BRANCHES, WASTE LINES, VENTS, AND TRAPS FOR CONNECTION TO INDIVIDUAL FIXTURES, FIXTURE FITTINGS, AND SPECIALTIES SHALL BE IN ACCORDANCE WITH THE FOLLOWING SCHEDULE OR AS INDICATED ON DRAWINGS, WHICHEVER IS GREATER.

DUC				141	<i>,</i>			1 1	<i>-</i> 11		/		/ 	•				
		_				DI	UCT M	ATERIA	_									
AIR SYSTEMS	G90 GALV. SHEET METAL	DOUBLE—WALL LINED G90 GALV. SHEET METAL (SOLID INNER WALL)	DOUBLE-WALL LINED G90 GALV. SHEET METAL (PERF. INNER WALL)	G90 GALV. SHEET METAL WITH 1-INCH LINING	GALVANNEALED SHEET METAL	ALUMINUM	TYPE 304 STAINLESS STEEL	TYPE 316 STAINLESS STEEL	PVC COATED GALV. SHEET METAL (4X1)	PVC COATED GALV. SHEET METAL (1X4)	PVC COATED GALV. SHEET METAL (4X4)	16 GA. CARBON STEEL	ZERO-CLEARANCE PREFABRICATED RANGE HOOD EXHAUST DUCT	FABRIC	DESIGN PRESSURE CLASS (INCHES WG)	SEAL CLASS	MAX. ALLOWABLE LEAKAGE RATE (PERCENT)	KEYED NOTES
SUPPLY AIR WITHOUT TERMINAL UNITS	х														+2	A	5	
SUPPLY AIR UPSTREAM OF TERMINAL UNITS	Х														+6	A	5	
SUPPLY AIR DOWNSTREAM OF TERMINAL UNITS	Х														+2	Α	5	
RETURN AIR WITHOUT TERMINAL UNITS	Х														-2	Α	5	
RETURN AIR UPSTREAM OF TERMINAL UNITS	Х														-2	Α	5	
RETURN AIR DOWNSTREAM OF TERMINAL UNITS	Х														-6	Α	5	
EXHAUST AIR WITHOUT TERMINAL UNITS	Х														-2	Α	5	
EXHAUST AIR UPSTREAM OF TERMINAL UNITS	Х														-2	Α	5	
EXHAUST AIR DOWNSTREAM OF TERMINAL UNITS	Х														-6	Α	5	
KITCHEN EXHAUST (TYPE I HOOD)												Х	Х		N/A	N/A	N/A	C, D
DISHWASHER EXHAUST						Х									-2	N/A	N/A	С
AIR TRANSFER DUCT				Х											+2	Α	5	
RELIEF AIR DOWNSTREAM OF FANS	Х														+6	Α	5	
OUTSIDE AIR AND MIXED AIR DUCT	Х														-6	Α	5	
OUTSIDE AIR, RELIEF AIR AND EXHAUST AIR PLENUMS ADJACENT TO EXTERIOR LOUVERS		Х													+/-6	А	5	

SCHEDULES GENERAL NOTES:

SCHEDULES FOR ADDITIONAL ELECTRICAL INFORMATION

SHALL BE FOR THE REMAINDER OF THE UNIT.

1. REFER TO ELECTRICAL STANDARD SCHEDULES, ONE LINE DIAGRAM AND PANEL

2. PROVIDE THE FOLLOWING FACTORY-WIRED ELECTRICAL OPTIONS/ACCESSORIES WHERE

B - UNIT SHALL BE SINGLE POINT ELECTRICAL CONNECTION WITH FACTORY INSTALLED DISCONNECTING MEANS AND ALL REQUIRED STARTERS AND

F - UNIT SHALL HAVE (2) SINGLE POINT CONNECTIONS WITH FACTORY INSTALLED DISCONNECTING MEANS AND ALL REQUIRED STARTERS AND CONTROLS. (1) CONNECTION SHALL BE FOR CONDENSING SECTION AND (1) CONNECTION

3. FOR MODULATION/CONTROL TYPE COLUMN, "VFC" INDICATES VARIABLE FREQUENCY CONTROLLERS, "AUTO" INDICATES AUTOMATIC OPERATION (CONTROLLED BY TEMPERATURE CONTROLS OR SELF CONTAINED CONTROLS), "MANUAL" INDICATES

4. IF VARIABLE FREQUENCY CONTROLLERS ARE INDICATED TO BE PROVIDED AND ARE NOT INSTALLED INTEGRAL TO THE UNIT, VARIABLE FREQUENCY CONTROLLERS SHALL BE SUPPLIED BY THE MECHANICAL CONTRACTOR (UNLESS OTHERWISE NOTED) AND INSTALLED BY THE ELECTRICAL CONTRACTOR INCLUDING THE LINE SIDE AND LOAD SIDE WIRING TO THE MOTOR AND INCLUDING MISCELLANEOUS STEEL REQUIRED FOR THE SUPPORT AND MOUNTING OF THE VFC. REFER TO FLOOR PLANS FOR

5. WHERE EQUIPMENT IS INDICATED TO HAVE A SINGLE POINT ELECTRICAL CONNECTION, THAT EQUIPMENT SHALL COME COMPLETE WITH FACTORY INSTALLED STARTERS, MOTOR OVERLOAD PROTECTION, CONTACTORS, FUSING AND ALL NECESSARY INTERNAL WIRING AND CONTROLS. PROVIDE A FACTORY MOUNTED UNIT

DISCONNECTING MEANS WHERE THE ELECTRICAL CONTRACTOR SHALL MAKE SINGLE POINT CONNECTION. INSTALL PACKAGED EQUIPMENT SUCH THAT THE ELECTRICAL CONNECTION AND CONTROLS ARE ACCESSIBLE AND HAVE CLEARANCES MEETING THE

6. WHERE PACKAGED EQUIPMENT IS PROVIDED, NAMEPLATE MUST INDICATE MAXIMUM

7. WHERE EQUIPMENT IS DESIGNATED BY MANUFACTURER AND MODEL NUMBER, THIS IS THE BASIS OF DESIGN. IF THE CONTRACTOR ELECTS TO PROVIDE EQUIPMENT BY OTHER SPECIFIED MANUFACTURERS OR PROPOSED ALTERNATE EQUIPMENT BY THE BASIS OF DESIGN MANUFACTURER, THE CONTRACTOR SHALL BE RESPONSIBLE FOR

8. WHERE EQUIPMENT IS SCHEDULED TO INCLUDE A SERVICE RECEPTACLE, PROVIDE A FACTORY MOUNTED SERVICE RECEPTACLE WITH APPROPRIATE FUSES AND

9. SIZE ALL EQUIPMENT FEEDERS BASED ON THE LISTED MOP (MAXIMUM OVERCURRENT PROTECTION). REFER TO THE FEEDER AND BRANCH CIRCUIT SIZING SCHEDULE ON

THE ELECTRICAL STANDARD SCHEDULES SHEET.

TRANSFORMERS CONNECTED ON THE LINE SIDE OF THE UNIT DISCONNECT. PROVIDE A NAMEPLATE ON THE DISCONNECT SWITCH INDICATING THE PRESENCE OF LIVE POWER TO THE SERVICE RECEPTACLE WHEN THE UNIT DISCONNECT IS IN THE OFF

ANY REVISIONS TO ELECTRICAL REQUIREMENTS, STRUCTURAL LOADING, OR ARCHITECTURAL APPURTENANCES AND SHALL INCLUDE THE COST OF SUCH

OVERCURRENT PROTECTION BY HACR RATED CIRCUIT BREAKERS OR FUSES. IF FUSE PROTECTION ONLY IS INDICATED, PROVIDE A FUSIBLE DISCONNECT AND FUSES WITH

TYPICAL FOR ALL SCHEDULE SHEETS:

INDICATED IN SCHEDULE:

CONTROLS C - SERVICE RECEPTACLE D - FUSED DISCONNECT SWITCH E - COMBINATION STARTER

HAND OPERATION.

NATIONAL ELECTRICAL CODE.

revisions in his bid.

A - NON-FUSED DISCONNECT SWITCH

1. 'X' INDICATES ACCEPTABLE SELECTION. IF MORE THAN ONE SELECTION IS INDICATED FOR A DUCT SYSTEM, CONTRACTOR MAY SELECT FROM THOSE INDICATED SELECTIONS. 2. 4 X 1 PVC-COATED GALVANIZED STEEL: FACTORY-APPLIED PVC COATINGS SHALL BE 4 MILS (0.10 MM) THICK ON EXTERIOR SHEET METAL SURFACES OF DUCTS AND FITTINGS EXPOSED TO CORROSIVE CONDITIONS AND MINIMUM 1 MIL (0.025 MM) THICK ON INTERIOR SURFACES.

SHEET METAL SURFACES OF DUCTS AND FITTINGS EXPOSED TO CORROSIVE CONDITIONS AND MINIMUM 1 MIL (0.025 MM) THICK ON EXTERIOR SURFACES. 4. 4 X 4 PVC-COATED GALVANIZED STEEL: FACTORY-APPLIED PVC COATINGS SHALL BE 4 MILS (0.10 MM) THICK ON SHEET METAL SURFACES OF DUCTS

3. 1 X 4 (4 X 1 REVERSE COATED) PVC—COATED GALVANIZED STEEL: FACTORY—APPLIED PVC COATINGS SHALL BE 4 MILS (0.10 MM) THICK ON INTERIOR

AND FITTINGS EXPOSED TO CORROSIVE CONDITIONS AND 4 MILS (0.10 MM) THICK ON OPPOSITE SURFACES.

KEYED NOTES

A. SCREWS, DAMPERS, OR PROJECTIONS OF ANY TYPE ON INTERIOR OF DUCT SURFACE ARE PROHIBITED. B. DUCT SHALL BE LINED WITHIN 25 FEET UPSTREAM OF FANS.

C. ALL WELDED CONSTRUCTION. D. PROVIDE ZERO CLEARANCE KITCHEN GREASE DUCT, REFER TO SPECIFICATIONS

Peter Basso Associates Inconsulting Engineers
5145 Livernois, Suite 100 Troy, Michigan 48098-3276 Tel: 248-879-5666 Fax: 248-879-0007 www.PeterBassoAssociates.com PBA Project No.: 2021-0402

1	ADDENDUM #3	09/29/23
NO.	REVISION	DATE
September 1	STATE OF MICHIGAN	VD D.V.D 0.D.W

DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE

171CODHHS7255 Y22003

CONTRACT NO.



WTA A RCHITECTS

COPYRIGHT © 2023

100 S Jefferson Ave, Suite 601

Saginaw, Michigan 48607 989 752 8107

PROJECT TITLE

491/20167.SDW - PHASE 500: CENTER FOR FORENSIC PSYCHIATRY - CREATE

KITCHEN SALINE, MICHIGAN

SHEET TITLE

MECHANICAL SCHEDULES

PROJECT NUMBER SHEET NUMBER PROJECT DATE AUGUST 23, 2023 CHECKED BY WEK

ABOVEGROUND HVAC PIPE 8	& AC				RY	INS	SUI	_A ⁻	ΓΙΟ	N A	AP	PLI	CA	TION
	11	ISULAT		ATERIAL INCHES		HICKNE	SS	FIEL	.D—APP	LIED .	JACKET	MATE	RIAL	
	FLEXIBLE ELASTOMERIC	FIBERGLASS	MINERAL WOOL	POLYISOCYANURATE	PHENOLIC	CELLULAR GLASS	CALCIUM SILICATE	ALUMINUM	STAINLESS STEEL	PVC	SELF-ADHESIVE (FOR OUTDOOR APPLICATIONS)	PVDC (INDOOR)	PVDC (OUTDOOR)	KEYED NOTES
INDOOR PIPE SYSTEM AND SIZE (INCHES)														
CHILLED WATER & BRINE BELOW 40 DEG F:														
NPS 6 AND SMALLER		1						Х		Х				Α
NPS 8 AND LARGER		1.5						Х		Х				Α
CHILLED WATER & BRINE 40 DEG F to 60 DEG F:	1	1						Х		Х				А
HEATING HOT WATER SUPPLY & RETURN 200 DEG F AND LOWER														
NPS 1-1/4 AND SMALLER		1.5						Х		Х				Α
NPS 1-1/2 AND LARGER		2						Х		Х				Α
LOW PRESS. STEAM, CONDENSATE & PUMPED CONDENSATE:														
NPS 1-1/4 AND SMALLER		2.5	2.5				3	Х						Α
NPS 1-1/2 AND LARGER		3	3				3	Х						Α
MED. & HIGH PRESS. STEAM, CONDENSATE & PUMPED CONDENSATE:														
NPS 3/4 AND SMALLER		3	3				5	Х						А
NPS 1 TO 1-1/4		4	4				5	Х						А
NPS 1-1/2 AND LARGER		4.5	4.5				5	Х						А
REFRIGERANT SUCTION & HOT GAS (RIGID COPPER)														
NPS 6 AND SMALLER	1	1						Х		Х				
NPS 8 AND LARGER	1.5	1.5						Х		Х				
REFRIGERANT SUCTION & HOT GAS (SOFT COPPER)	1							Х		Х				

UNLESS OTHERWISE INDICATED OR SCHEDULED, THE FOLLOWING DO NOT REQUIRE INSULATION:

DIRECT BURIED COOLING SYSTEM PIPING PIPING THAT CONVEYS FLUIDS HAVING DESIGN OPERATING TEMPERATURE RANGE BETWEEN 60 DEG F. AND 105 DEG F., INCLUSIVE.

<u>GENERAL NOTES</u>

- 1. 'X' OR THICKNESS IN INCHES INDICATES ACCEPTABLE SELECTION. IF MORE THAN ONE SELECTION IS INDICATED, CONTRACTOR MAY SELECT FROM
- 2. INSULATE PIPING WITHIN AIR HANDLING EQUIPMENT THE SAME AS INDOOR PIPING. PROVIDE ALUMINUM OR STAINLESS STEEL JACKET.
- 3. FOR PIPING NPS 1-1/4 AND SMALLER WITHIN PARTITIONS IN CONDITIONED SPACES INSULATION MAY BE REDUCED BY ONE-INCH THICKNESS, BUT NOT TO LESS THAN ONE-INCH 4. FOR PIPING NPS 1 AND SMALLER, INSULATION IS NOT REQUIRED FOR STRAINERS, CONTROL VALVES, AND BALANCING VALVES.

KEYED NOTES

- A. PROVIDE FIELD APPLIED JACKET FOR PIPING EXPOSED IN EQUIPMENT ROOMS, STORAGE ROOMS, JANITORS CLOSETS, RECEIVING ROOMS, TEST AREAS, CIRCULATION
- AREAS AND SUCH AREAS SUBJECT TO DAMAGE WITHIN 10 FEET (3 METERS) OF FINISHED FLOOR. B. PROVIDE MANUFACTURER'S RECOMMENDED PROTECTIVE COATING FOR FLEXIBLE ELASTOMERIC THERMAL INSULATION.
- C. STEAM AND CONDENSATE PIPING JACKET SHALL BE STUCCO EMBOSSED. D. PIPING WITHIN ENERGY RECOVERY UNITS SHALL BE TYPE 304 STAINLESS STEEL, SMOOTH; 0.010 INCH THICK. SEAMS AND JOINTS CAULKED WITH CHEMICALLY RESISTANT SEALER.

DUCT SYSTEM INSULATION A	PP	LIC	AT	101	1 8	SCH	HED	UL	E.	
	IN	ISULAT		ATERIAL INCHES		HICKNE	SS	API	ELD PLIED	
						BLANKET			CKET ERIAL	
	FIBERGLASS BLANKET 0.75 LB/CU FT	FIBERGLASS BLANKET 1.0 LB/CU FT	FIBERGLASS BOARD 2.25 LB/CU FT	FIBERGLASS BOARD 6.0 LB/CU FT	FLEXIBLE ELASTOMERIC	ASTM E2336 2-HOUR FIRE RATED BLA	2-Hour fire rated blanket	ALUMINUM	SELF—ADHESIVE (FOR OUTDOOR APPLICATIONS)	KEYED NOTES
DUCT SYSTEMS LOCATED INDOORS	İ	İ	İ	İ	i	İ	i	i	i	
SUPPLY AIR, EXCEPT AS NOTED BELOW		1.5								A, E
RECTANGULAR SUPPLY AIR IN MECHANICAL ROOMS			1.5							
ROUND & FLAT OVAL SUPPLY AIR IN MECHANICAL ROOMS		1.5								
RECTANGULAR RETURN AIR IN MECHANICAL EQUIPMENT ROOMS			1.5							
ROUND RETURN AIR IN MECHANICAL ROOMS		1.5								
OUTSIDE AIR AND MIXED AIR, EXCEPT AS NOTED BELOW		1.5								
RECTANGULAR OUTSIDE AIR AND MIXED AIR IN MECHANICAL ROOMS			1.5							
ROUND OUTSIDE AIR AND MIXED AIR IN MECHANICAL ROOMS		1.5								
EXHAUST AND RELIEF AIR BETWEEN ISOLATION DAMPER AND PENETRATION OF BUILDING EXTERIOR, EXCEPT AS NOTED BELOW		1.5								
RECTANGULAR EXHAUST AND RELIEF AIR BETWEEN ISOLATION DAMPER AND PENETRATION OF BUILDING EXTERIOR, IN MECHANICAL ROOMS			1.5							
ROUND & FLAT OVAL EXHAUST AND RELIEF AIR BETWEEN ISOLATION DAMPER AND PENETRATION OF BUILDING EXTERIOR, IN MECHANICAL ROOMS		1.5								
DUCT SYSTEMS LOCATED IN ATTICS, CRAWL SPACES, OR PARKING GARAGE	S HAV	/ING I	NATU	RAL C	OR ME	ECHAI	NICAL	VEN	ΓΙLΑΤΙ	ON
RECTANGULAR DUCTS AND AIR PLENUMS, ALL TYPES	3			2						<u>-</u> -
ROUND & FLAT OVAL SUPPLY AIR	3									
ROUND & FLAT OVAL RETURN & EXHAUST AIR	3									

PLENUMS, DUCTS, AND DUCT ACCESSORIES NOT REQUIRING INSULATION:

- DOUBLE-WALL METAL DUCTS WITH INSULATION OF SUFFICIENT THICKNESS TO COMPLY WITH ENERGY CODE AND ASHRAE/IESNA 90.1 2013 METAL DUCTS WITH DUCT LINER OF SUFFICIENT THICKNESS TO COMPLY WITH ENERGY CODE AND ASHRAE/IESNA 90.1 - 2013
- FABRIC SUPPLY DUCTS FACTORY-INSULATED FLEXIBLE DUCTS FACTORY-INSULATED PLENUMS AND CASINGS
- FLEXIBLE CONNECTORS
- VIBRATION-CONTROL DEVICES FACTORY-INSULATED ACCESS PANELS AND DOORS

GENERAL NOTES

- 1. 'X' OR THICKNESS IN INCHES INDICATE ACCEPTABLE SELECTION. IF MORE THAN ONE SELECTION IS INDICATED FOR A DUCT SYSTEM, CONTRACTOR MAY SELECT FROM
- THOSE INDICATED SELECTIONS. 2. REFER TO METAL DUCT SECTION OF SPECIFICATIONS FOR DUCT LINING AND DOUBLE-WALL INSULATED DUCT. 3. REFER TO HVAC CASINGS SECTION OF SPECIFICATIONS FOR DOUBLE-WALL INSULATED PLENUMS.

KEYED NOTES

- A. INCLUDE INSULATION AROUND DUCT MOUNTED COILS AND AIR TERMINAL UNIT COILS.
- B. NUMBER OF LAYERS AND TOTAL INSULATION THICKNESS AS RECOMMENDED BY SELECTED MANUFACTURER. C. DOES NOT APPLY TO PREFABRICATED, ZERO-CLEARANCE GREASE DUCT.
- D. PROVIDE MANUFACTURER'S RECOMMENDED PROTECTIVE COATING FOR FLEXIBLE ELASTOMERIC THERMAL DUCT INSULATION. E. EXPOSED SUPPLY DUCTWORK LOCATED IN CONDITIONED SPACE SERVED BY THAT SYSTEM IS NOT REQUIRED TO BE INSULATED.

	INSULATION MATERIAL & THICKNESS FIELD—APPLIED JACKET MATERIAL													
	IN	SULAT		INCHES		IICKNES	5 5	FIEL	D-APF	PLIED .	IACKET	MATE	RIAL	
	FLEXIBLE ELASTOMERIC	FIBERGLASS	MINERAL WOOL	POLYISOCYANURATE	PHENOLIC	CELLULAR GLASS	CALCIUM SILICATE	ALUMINUM	STAINLESS STEEL	PVC	SELF-ADHESIVE (FOR OUTDOOR APPLICATIONS)	PVDC (INDOOR)	PVDC (OUTDOOR)	Keyed Notes
INDOOR PIPE SYSTEM AND SIZE (INCHES)			•			•					•	•	•	
DOMESTIC COLD WATER	1	1						Х		Х				А
DOMESTIC HOT WATER SUPPLY & RETURN 140 DEG F AND LESS:														
NPS 1-1/4 AND SMALLER	1	1						Х		Х				А
NPS 1-1/2 AND LARGER	1.5	1.5						Х		Х				A
STORM WATER & OVERFLOW	1	1						Х		Χ				A
ROOF DRAIN AND OVERFLOW DRAIN BODIES	1	1												
CONDENSATE AND EQUIPMENT DRAIN PIPING BELOW 60 DEG F	0.75	1												
FLOOR DRAINS, TRAPS AND SANITARY DRAIN PIPING WITHIN 10 FEET OF DRAIN RECEIVING CONDENSATE AND EQUIPMENT DRAIN WATER BELOW 60 DEG F	0.75	1						X		Х				A
OUTDOOR (ABOVEGROUND) AND TUNNEL PIPE SYSTEM AND	SIZE	(INC)	HES)											
DOMESTIC COLD WATER	2	2						Х		Х	Х			В
DOMESTIC HOT WATER SUPPLY & RETURN	2	2						Х		Х	Х			В
SANITARY WHERE HEAT TRACING IS INSTALLED		2						х		Х	х			В
STORM WATER AND OVERFLOW WHERE HEAT TRACING IS INSTALLED		2						Х		Х	Х			В

UNLESS OTHERWISE INDICATED OR SCHEDULED, DO NOT INSULATE THE FOLLOWING: FIRE SUPPRESSION PIPING

UNDERGROUND PIPING LABORATORY GAS AND VACUUM PIPING MEDICAL GAS AND VACUUM PIPING FUEL GAS PIPING

GENERAL NOTES

FUEL OIL PIPING

- 1. 'X' OR THICKNESS IN INCHES INDICATES ACCEPTABLE SELECTION. IF MORE THAN ONE SELECTION IS INDICATED FOR A SYSTEM, CONTRACTOR MAY SELECT
- 2. INSULATE PIPING WITHIN AIR HANDLING EQUIPMENT THE SAME AS INDOOR PIPING. PROVIDE ALUMINUM OR STAINLESS STEEL JACKET. <u>KEYED NOTES</u>
- A. PROVIDE FIELD APPLIED JACKET FOR PIPING EXPOSED IN EQUIPMENT ROOMS, STORAGE ROOMS, JANITORS CLOSETS, RECEIVING ROOMS, TEST AREAS, CIRCULATION AREAS AND SUCH AREAS SUBJECT TO DAMAGE, WITHIN 10 FEET (3 METERS) OF FINISHED FLOOR. B. PROVIDE MANUFACTURER'S RECOMMENDED PROTECTIVE COATING FOR FLEXIBLE ELASTOMERIC THERMAL INSULATION.

HORIZONTAL PIPING AND SUPPORT APPLICATION SCHEDULE													
	ŀ	HANGEF	R OR S	SUPPOR	RT TYP	E	SHI	ELD T	YPE				
	TYPE 1 CLEVIS HANGER	TYPE 10 SWIVEL RING BAND HANGER	PE 41 DOUBLE ROD PIPE ROLLER	PE 43 SINGLE ROD ROLLER HANGER	PE 44 PIPE ROLLER & STAND	PE 46 ADJUSTABLE PIPE ROLL STAND	PE 39 PROTECTION SADDLE	PE 40 INSULATION PROTECTION SHIELD	THERMAL—HANGER SHIELD				
METAL PIPE TYPE & SIZE	MSS TYF	MSS TYF	MSS TYPE	MSS TYPE	MSS TYPE	MSS TYPE	MSS TYPE	MSS TYPE	HERMAI	KEYED NOT			
UNINSULATED SINGLE PIPE										KETED NOT			
UP TO 2 INCH	Х	Х											
2-1/2 INCH TO 4 INCH	Х	Х											
6 INCH TO 8 INCH	Х												
10 INCH	Х												
12 INCH			Х										
14 INCH AND LARGER			Х										
INSULATED SINGLE COLD PIPES													
UP TO 2 INCH	X	Х						Х	Х	A			
2-1/2 INCH TO 4 INCH	Х								Х				
6 INCH TO 8 INCH	Х								Х				
10 INCH	Х								Х				
12 INCH	Х								Х				
14 INCH AND LARGER	Х								Х				
INSULATED SINGLE HOT PIPES										<u> </u>			
UP TO 2 INCH	Х	Х					Х	Х	Х	A, C			
2-1/2 INCH TO 4 INCH			Х	Х	Х	Х	Х		Х	В, С			
6 INCH TO 8 INCH			Х	Х	Х	Х	Х		Х	В, С			
10 INCH			Х	Х	Х	Х	Х		Х	В, С			
12 INCH			Х		Х	Х	Х		Х	В, С			
14 INCH AND LARGER			Х				Х		Х	В, С			

- 1. "X" INDICATES APPROVED HANGER OR SUPPORT ELEMENTS. IF MORE THAN ONE HANGER OR SUPPORT ELEMENT IS INDICATED, SELECTION FROM APPROVED ELEMENTS IS CONTRACTOR'S OPTION.
- 2. REFER TO HANGER AND SUPPORT SECTION FOR APPROVED MANUFACTURERS. . HANGERS AND SUPPORTS USED FOR FIRE PROTECTION SERVICES SHALL BE UL LISTED OR FMG APPROVED.

5. REFER TO INDIVIDUAL PIPING SPECIFICATION SECTIONS FOR HANGER SPACING.

WITH INSULATION MATCHING ADJOINING INSULATION.

- 4. HANGER ELEMENTS IN CONTACT WITH BARE COPPER PIPE SHALL BE COPPER PLATED, PLASTIC COATED, FELT LINED, OR USE MANUFACTURED COPPER TUBE ISOLATORS.
- 6. MULTIPLE PARALLEL COLD PIPES MAY BE TRAPEZE SUPPORTED FROM BELOW USING U-BOLTS OR STRUT CLAMPS AND THERMAL HANGER SHIELDS. REFER TO KEYED NOTE A.
- 7. MULTIPLE PARALLEL COLD PIPES MAY BE TRAPEZE SUPPORTED FROM ABOVE USING STANDARD HANGER ELEMENTS INDICATED FOR SINGLE COLD PIPES.
- 8. MULTIPLE PARALLEL HOT PIPES MAY BE TRAPEZE SUPPORTED FROM BELOW USING ROLLER ELEMENTS AND THERMAL HANGER SHIELD OR INSULATION PROTECTION SADDLE. REFER TO KEYED NOTES B AND C.
- 9. MULTIPLE PARALLEL HOT PIPES MAY BE TRAPEZE SUPPORTED FROM ABOVE USING STANDARD ROLLER HANGERS INDICATED AND THERMAL HANGER SHIELD OR INSULATION PROTECTION SADDLE. REFER TO KEY NOTES B AND C. 10. REFER TO INDIVIDUAL PIPING SPECIFICATION SECTIONS FOR ADDITIONAL SYSTEM SPECIFIC HANGER APPLICATIONS.
- <u>KEYED NOTES</u> A. USE THERMAL HANGER SHIELD ON TRAPEZE SUPPORTED INSULATED PIPE TO PREVENT CRUSHING OF INSULATION. B. USE THERMAL HANGER SHIELD DESIGNED FOR USE ON ROLLER SUPPORTS FOR INSULATED HOT PIPE . C. USE TYPE 39 PROTECTION SADDLES IF INSULATION WITHOUT VAPOR BARRIER IS INDICATED. FILL INTERIOR VOIDS

1	ADDENDUM #3	09/29/
NO.	REVISION	DATE

STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255



WTAARCH.COM

CONTRACT NO.

Y22003

| WTA A RCHITECTS |

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

WEK

MECHANICAL SCHEDULES

ROJECT NUMBER SHEET NUMBER PROJECT DATE AUGUST 23, 2023 CHECKED BY

Peter Basso Associates Inc CONSULTING ENGINEERS 5145 Livernois, Suite 100 Troy, Michigan 48098-3276 Tel: 248-879-5666 Fax: 248-879-0007 www.PeterBassoAssociates.com PBA Project No.: 2021-0402

							AIR H	ANDLING	3 UNIT	SUPPL	Y AIR F	AN SCI	HEDULE						
UNIT IDENTIFICATION	SYSTEM SERVED	TYPE	AIRFLOW CFM	E.S.P. IN. W.G.	T.S.P. IN. W.G.	MINIMUM WHEEL DIAMETER	RPM	FAN CLASS		МС	TOR		MODULATION/ CONTROL TYPE		ELEC	TRICAL		MODEL NUMBER	KEYED NOTES
						INCHES			BHP	HP	RPM	DRIVE TYPE		VOLTS	PHASE	SCCR KA (NOTE 5)	OPTIONS/ ACCESSORIES		
RF-1	AHU-21H	CENTRIFUGAL	10,000	1.0	1.19	22.25	2403	2	5.12	7.5	1750	DIRECT	VFD	460	3			CAH021GDGC	

GENERAL NOTES:

1. REFER TO SCHEDULES GENERAL NOTES.

2. MODEL NUMBERS ARE DAIKIN UNLESS OTHERWISE NOTED. 3. DESIGN MINIMUM OUTSIDE AIRFLOW CFM (VENTILATION) LISTED IS BASED ON THE ESTIMATED MAXIMUM OCCUPANT LOAD. REFER TO TEMPERATURE CONTROL DRAWINGS FOR OUTSIDE AIR CONTROL SEQUENCE.
4. REFER TO AIR HANDLING UNIT FILTER SCHEDULE FOR AIR PRESSURE DROP TO BE USED FOR TOTAL STATIC PRESSURE CALCULATIONS.

5. CONTROLLER (E.G. VARIABLE FREQUENCY CONTROLLER, MOTOR STARTER) FOR SPECIFIED EQUIPMENT SHALL BE MANUFACTURED AND MARKED PER NEC WITH A MINIMUM SHORT CIRCUIT CURRENT RATING AS INDICATED.

1. PROVIDE BUNGY CORD MAINTENANCE LED LIGHT 235" LONG, WITH MAGNETIC BASE AND FLEXIBLE CORD 2. PROVIDE TWO BLANK OFF SHEETS FOR SUPPLY FAN

	MODULAR AIR HANDLING UNIT DIMENSIONS													
UNIT IDENTIFICATION	MAXIMUM UNIT LENGTH	MAXIMUM UNIT WIDTH	MAXIMUM UNIT HEIGHT	MAXIMUM UNIT WEIGHT POUNDS	MANUFACTURER LEAD TIME	MANUFACTURER	KEYED NOTES							
AHU-21H	310"	90"	58"	5504		DAIKIN	1							
AHU-22H	166"	80"	52"	2877		DAIKIN	1							

GENERAL NOTES: 1. FOR REFERENCE ONLY

KEYED NOTES:

1. AHU TO BE SHIPPED IN SECTIONS AND THEN BROKEN DOWN TO FIT THROUGH DOORWAYS. CONTRACTOR TO REASSEMBLE AHU IN ROOM UNDER DIRECTION FROM MANUFACTURER

	MODULAR AIR HANDLING UNIT COMPONENT SCHEDULE													
UNIT IDENTIFICATION	POSITION NUMBER 1	POSITION NUMBER 2	POSITION NUMBER 3	POSITION NUMBER 4	POSITION NUMBER 5	POSITION NUMBER 6	POSITION NUMBER 7	POSITION NUMBER 8	POSITION NUMBER 9	KEYED NOTES				
AHU-21H	PLENUM	ACCESS	RF-1	ECONOMIZER	AF-1	HC-1	CC-1	ACCESS	SF-1	1				
AHU-22H	PLENUM	AF-2	HC-2	ACCESS	SF-2					1				

GENERAL NOTES:

1. MODULES SELECTED BASED ON DAIKIN INDOOR MODULAR CLIMATE CHANGER AIR HANDLING UNIT. 2. POSITION NUMBERS ARE INDICATED IN THE DIRECTION OF AIRFLOW FROM RETURN AIR INLET TO SUPPLY AIR DISCHARGE.

KEYED NOTES:

1. AHU TO BE SHIPPED IN SECTIONS AND THEN BROKEN DOWN TO FIT THROUGH EXISTING DOORWAYS. CONTRACTOR TO REASSEMBLE AHU IN ROOM UNDER DIRECTION FROM MANUFACTURER
2. AHU IS IS PRE=PURCHASED AND ASSIGNED TO THE CONTRACTOR FOR DELIVERY AND INSTALLATION

				AIF	HAN	IDLIN	G UNI	T FIL	TER S	CHE	DULE					
UNIT I.D.	SYSTEM SERVED	TYPE	AIRFLOW CFM	AIR PRES	SS. DROP	EFFICIENC IES			FILTER MED	IA			HOUSING		MODEL NO.	KEYED NOTES
	INITIAL DIRTY MERV QUAN. WIDTH HEIGHT DEPTH N. IN. W.G. IN. W.G. IN. W.G.										MIN. MEDIA FACE AREA SQ. FT.	ACCESS TYPE	WDTH IN.	HEIGHT IN.		
AF-1	AHU-21H	PLEATED	10,000	0.22	1.0	8	3/3	24/24	24/20	2	20	SIDE	18	48	CAH021GDGC	
AF-1	AHU-21H	VARICEL SH CARTRIDGE	10,000	0.53	1.5	13	3/3	24/24	24/20	12	20	SIDE	18	48	CAH021GDGC	
AF-2	AHU-22H	PLEATED	8700	0.08	1.0	8	3/6/3	24/20/12	24/24/24	2/2/2	12/20/6	SIDE	26	42	CAH018GDGM	

MODEL NUMBERS ARE FARR UNLESS OTHERWISE NOTED.
 PROVIDE 25% TO 30% EFFICIENT 2 INCH THROW AWAY PREFILTERS

3. MERV DESIGNATES THE "MINIMUM EFFICIENCY REPORTING VALUE" AS EVALUATED UNDER ASHRAE STANDARD 52.2 1999. 4. AIR HANDLING UNIT TOTAL STATIC PRESSURE FOR VARIABLE AIR VOLUME SYSTEMS IS BASED ON THE FILTER DIRTY AIR

PRESSURE DROP AND AVERAGE/MIDLIFE FILTER AIR PRESSURE DROP FOR CONSTANT VOLUME SYSTEMS UNLESS NOTED OTHERWISE.

KEYED NOTES:

<u>KE TED</u>	NOTES:							
1.	PROVIDE	THREE	SETS	0F	EACH	TYPE	0F	FILTER

AIR HANDLING UNIT SUPPLY AIR FAN SCHEDULE T SYSTEM TYPE AIRFLOW OUTSIDE AIR E.S.P. T.S.P. MINIMUM WHEEL RPM FAN MODEL MODEL														
MOTOR MODULATION/ CONTROL TYPE ELECTRICAL	FAN CLASS MOTOR BHP HP RPM DRIVE TYPE						MINIMUM WHEEL DIAMETER	T.S.P. IN. W.G.	E.S.P. IN. W.G.	OUTSIDE AIR FLOW	AIRFLOW CFM	TYPE	SYSTEM SERVED	UNIT DENTIFICATION
HP RPM DRIVE TYPE VOLTS PHASE SCCR OF KA ACC (NOTE 5)	RIVE TYPE	RPM	HP	ВНР			INCHES			CFM				
5.0 1750 DIRECT VFD 460 3	DIRECT	1750	15.0	11.29	2	1796	24.5	4.89	2.0	3000	10,000	CENTRIFUGAL	AHU-21H	SF-1
10 3500 DIRECT VFD 460 3	DIRECT	3500	10	7.9	2	3650	18.25	3.51	1.5	8700	8700	CENTRIFUGAL	AHU-22H	SF-2
HP RPM DRIVE TYPE VOLTS PHASE SCCR KA (NOTE 5) 5.0 1750 DIRECT VFD 460 3	DIRECT	1750	15.0	11.29	2		INCHES 24.5	4.89	2.0	3000	10,000		AHU-21H AHU-22H	SF-1

1. REFER TO SCHEDULES GENERAL NOTES. 2. MODEL NUMBERS ARE DAIKIN UNLESS OTHERWISE NOTED.

3. DESIGN MINIMUM OUTSIDE AIRFLOW CFM (VENTILATION) LISTED IS BASED ON THE ESTIMATED MAXIMUM OCCUPANT LOAD. REFER TO TEMPERATURE CONTROL DRAWINGS FOR OUTSIDE AIR CONTROL SEQUENCE.

4. REFER TO AIR HANDLING UNIT FILTER SCHEDULE FOR AIR PRESSURE DROP TO BE USED FOR TOTAL STATIC PRESSURE CALCULATIONS. 5. CONTROLLER (E.G. VARIABLE FREQUENCY CONTROLLER, MOTOR STARTER) FOR SPECIFIED EQUIPMENT SHALL BE MANUFACTURED AND MARKED PER NEC WITH A MINIMUM SHORT CIRCUIT CURRENT RATING AS INDICATED.

1. PROVIDE BUNGY CORD MAINTENANCE LED LIGHT 235" LONG, WITH MAGNETIC BASE AND FLEXIBLE CORD 2. PROVIDE TWO BLANK OFF SHEETS FOR SUPPLY FAN

						CHIL	LED V	VATE	R CO	OLING	COIL	SCHE	DULE						
UNIT IDENTIFICATION	ATION SERVED NUMBER FIN DENSITY CAPACITY MBH AIRFLOW E.D.B. F E.W.B. L.D.B. L.W.B. MAXIMUM FACE AREA FLOW FLUID TYPE E.W.T. L.W.T. MAXI																CONTROL VALVE	MODEL	KEYED NOTES
IDEN IIFICATION	SERVED	ROWS	FINS/INCH	CAPACIT MBH	AIRFLOW CFM	E.D.B. °F	E.W.B.	L.D.B.	L.W.B.		SQ. FT.	FLOW GPM	FLUID TYPE	E.W.T.	L.W.T.	MAXIMUM	W.P.D. FT. HEAD	NUMBER	
			,		CFM		۲	٢	r	A.P.D. IN. W.G.		GPM		٢	r	W.P.D. FT. HEAD			
CC-1	AHU-21H	6	9	388.6	10000	79.7	65.9	53.9	53.0	0.69	20.1	63.7	W	44.0	56.2	16.0	15	5WL0906B	#

GENERAL NOTES:

1. MODEL NUMBERS ARE DAIKIN UNLESS OTHERWISE NOTED.

MECHANICAL

These documents are approved for compliance with the TATE OF MICHIGAN MECHANICAL CODE subject to field inspection and the conditions of approval.

2. COIL SELECTIONS BASED ON .00025 FOULING FACTOR. 3. FLUID TYPE: W = WATER, PGXX = PROPYLENE GLYCOL SOLUTION <math>XX PERCENTAGE OF GLYCOL, EGXX = ETHYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL.

						HOT	WAT	TER HEA	ATING (COIL S	SCHE	DULE					
UNIT	- -															MODEL	KEYED NOTES
IDENTIFICATION	SERVED	ROWS	FINS/INCH	WRH	AIRFLOW CFM	E.D.B. *F	L.D.B. F	MAXIMUM A.P.D. IN. W.G.	SQ. FT.	FLOW GPM	FLUID TYPE	E.W.T. *F	L.W.T. *F	MAXIMUM W.P.D. FT. HEAD	W.P.D. FT. HD.	NUMBER	
HC-1	AHU-21H	2	10	305.5	10000	43.0	70.9	0.30	15.1	19.7	PG35	130	99	2.00	15	5WH1002B	
HC-2	AHU-22H	2	10	804.5	8700	-10.0	82.0	0.33	16.0	42.2	PG35	130	94	8.6	15	5WH1002C	

GENERAL NOTES:

1. MODEL NUMBERS ARE DAIKIN UNLESS OTHERWISE NOTED.

2. COIL SELECTION BASED ON .00025 FOULING FACTOR. 3. FLUID TYPE: W = WATER, PGXX = PROPYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL, EGXX = ETHYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL.

			A	IR TE	RMIN	AL TY	/PE				
DUCT CON	INECTIONS	DISC	CHARGE SOUN	ND POWER/R	ADIATED SOU	ND POWER -	dB	DIMEN	SIONS		
INLET SIZE INCHES	OUTLET SIZE INCHES	125 Hz	250 Hz	500 Hz	1000 Hz	2000 HZ	4000 HZ	LENGTH INCHES	HEIGHT INCHES	MODEL NUMBER	KEYED NOTES
6ø	12x8	73/66	69/63	62/52	56/42	53/40	49/36			ESV	1
8ø	12x10	72/68	70/59	66/53	63/47	57/46	53/46			ESV	2
10ø	14x12-1/2	78/71	70/61	65/56	61/50	58/47	53/45			ESV	3
12ø	16x15	76/72	73/63	69/59	65/53	61/48	57/46			ESV	4
16ø	24x18	78/70	73/63	70/58	68/53	64/52	59/50			ESV	5
24x16	38x18	83/74	81/69	76/63	74/54	73/48	68/41			ESV	6

<u>GENERAL NOTES:</u>
1. MODEL NUMBERS ARE TITUS UNLESS OTHERWISE NOTED.

2. MAXIMUM SOUND POWER LEVEL BASED ON 2" PRESSURE DROP ACROSS UNIT WITH NO ALLOWANCE FOR EXTERNAL ATTENUATION.

KEYED NOTES:

1. BASED ON 350 CFM
2. BASED ON 650 CFM
3. BASED ON 900 CFM 4. BASED ON 1500 CFM 5. BASED ON 2500 CFM

6. BASED ON 5300 CFM

						AIR T	ERMIN	IAL U	NIT W	/ITH F	TOF	WA	TER (COIL S	CHED	ULE				
						AIR FLOW								HE	EATING COIL (I	NOTE 3)				
UNIT IDENTIFICATION	inlet size	AREA SERVED	UNIT SERVED	COOLING MAX	COOLING MIN.	HEATING MIN.	HEATING MAX	MAXIMUM A.P.D.	CAPACITY MBH	NUMBER ROWS	А	IR				WA	TER			KEYED NOTES
IDENTIFICATION		SERVED	FROM	CFM	CFM	CFM	CFM	W/COIL IN. W.G.	MIDIT	KOWS	E.D.B *F	L.D.B. F	FLOW GPM	FLUID TYPE	E.W.T. *F	L.W.T. °F	MAXIMUM W.P.D. FT. HEAD	CONTROL VALVE W.P.D. FT. HEAD	CONTROL VALVE TYPE	
VBR-H108	6	H132,H119, H133	AHU-21H	260	80	80	260	0.11	5.0	2	55.0	90.0	0.5	PG35	130	100	0.29	15	3-WAY	
VBR-H109	12	DINING H131	AHU-21H	1080	325	325	1080	0.16	20.6	2	55.0	90.0	1.2	PG35	130	100	1.41	15	3-WAY	
VBR-H110	12	DINING H131	AHU-21H	1080	325	325	1080	0.16	20.6	2	55.0	90.0	1.2	PG35	130	100	1.41	15	3-WAY	
VBR-H111	12	DINING H131/ SERVERY H130	AHU-21H	1280	325	325	1280	0.22	24.4	2	55.0	90.0	1.5	PG35	130	100	2.77	15	3-WAY	
VBR-H112	12	DINING H131/ SERVERY H130	AHU-21H	1280	325	325	1280	0.22	24.4	2	55.0	90.0	1.5	PG35	130	100	2.77	15	3-WAY	
VBR-H113	12	KITCHEN H123	AHU-21H	1260	325	325	1260	0.21	24.0	2	55.0	90.0	1.4	PG35	130	100	2.63	15	3-WAY	
VBR-H114	12	KITCHEN H123	AHU-21H	1375	325	325	1375	0.22	24.3	2	55.0	90.0	1.5	PG35	130	100	2.74	15	3-WAY	
VBR-H115	6	BREAK ROOM H127	AHU-21H	205	80	80	205	0.08	4.0	2	55.0	90.0	0.5	PG35	130	100	0.11	15	3-WAY	
VBR-H116	12	KITCHEN H123	AHU-21H	1330	325	325	1330	0.30	25.3	2	55.0	90.0	1.5	PG35	130	100	1.78	15	3-WAY	
VBR-H117	6	OFFICE H125	AHU-21H	200	80	80	200	0.07	3.9	2	55.0	90.0	0.5	PG35	130	100	0.10	15	3-WAY	
VBR-H118	8	CORRIDOR H122	AHU-21H	600	145	145	600	0.34	11.5	2	55.0	90.0	0.7	PG35	130	100	4.95	15	3-WAY	
VBR-H119	6	STORAGE H124	AHU-21H	150	80	80	150	0.03	3.1	1	55.0	90.0	0.5	PG35	130	100	0.05	15	3-WAY	

GENERAL NOTES:

1. MODEL NUMBERS ARE TITUS UNLESS OTHERWISE NOTED.

2. MAXIMUM PRESSURE DROP SCHEDULED SHALL BE THE MAXIMUM ALLOWABLE STATIC PRESSURE FOR BOX AND COIL. AT THE MAXIMUM CFM.

3. HEATING COIL SELECTION BASED ON HEATING MAXIMUM AIR FLOW. 4. FLUID TYPE: W = WATER, PGXX = PROPYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL, EGXX = ETHYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL.

KITC	HEN EXHAUS	T DUCT	REQUIF	REMENT SO	CHEDULE		
EXHAUST SYSTEM	MINIMUM DESIGN PRESSURE	MINIMUM DESIGN TEMPERATURE (DEG. F)	WORKING PRESSURE	TEST PRESSURE	LIGHT TEST	TEST TIME	ALLOWABLE LEAKAGE
GREASE DUCT	20 PSIG	>200	-5" PSIG	20 PSIG	TEST ALL JOINTS PER NFPA 96	2 HOURS	NONE

1. CONTRACTOR TO TEST ALL JOIST PER NPFA 96 2. CAP END OF GREASE DUCTS AND TEST WITCH COMPRESSED AIR, REDO JOIST THAT DO NOT PASS, HOLD TEST FOR MINIMUM 2 HOURS

								PU	JMP SC	HEDULE										
UNIT IDENTIFICATION	SYSTEM SERVED	LOCATION	TYPE	COUPLING TYPE	WATERFLOW GPM	FLUID TYPE	COLDEST SYSTEM OPERATING	PUMP HEAD FT.	OVERLOAD GPM	MINIMUM EFFICIENCY %		MOTOR		MODULATION/ CONTROL TYPE		ELE	CTRICAL		MODEL NUMBER	KEYED NOTES
							TEMP. *F FOR PUMP SELECTION				BHP	HP	RPM	33132 1112	VOLTS	PHASE	SCCR KA (NOTE 4)	OPTIONS/ ACCESSORIES		
			-			 	+	*****	NON			~~~	****							1
P-54	HWH	PENTHOUSE	IN-LINE	CLOSE	140	PG35	70 °F	69	NON- OVERLOADING	77.4	3.97	5	3600	AUTO	480	3	5		E-90-2AAC	}
P-55	HWH	PENTHOUSE	IN-LINE	CLOSE	140	PG35	70 °F	69	NON- OVERLOADING	77.4	3.97	5	3600	AUTO	480	3	5		E-90-2AAC	
SENERAL NOTES:		•	-	-		-					~~~	$\overline{}$					-		تسست	

GENERAL NOTES:

1. REFER TO SCHEDULES GENERAL NOTES.

1. KEI EK TO SCHLEDGLES GENERAL NOTES.
2. MODEL NUMBER ARE BELL & GOSSETT UNLESS OTHERWISE NOTED.
3. FLUID TYPE: W = WATER, PGXX = PROPYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL, EGXX = ETHYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL.
4. CONTROLLER (E.G. VARIABLE FREQUENCY CONTROLLER, MOTOR STARTER) FOR SPECIFIED EQUIPMENT SHALL BE MANUFACTURED AND MARKED PER NEC WITH A MINIMUM SHORT CIRCUIT CURRENT RATING AS INDICATED.

KEYED NOTES:

1. PUMPS SIZED FOR CURRENT CONNECTED LOAD, PIPING SIZE FOR WEST BUILDING FUTURE CONNECTED LOAD



2	BULLETIN #1	01/19/2024
1	STATE REVIEW SET	12/20/23
NO.	REVISION	DATE

STATE OF MICHIGAN
DEPARTMENT OF TROUNGLO DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE CONTRACT NO. Y22003 171CODHHS7255



WTA A RCHITECTS

COPYRIGHT © 2023

100 S Jefferson Ave, Suite 601

Saginaw, Michigan 48607 989 752 8107

PROJECT TITLE 491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

MECHANICAL SCHEDULES

Associates Inc G ENGINEERS	PROJECT NUMBER 2021094	SHEET NUMBER
ois, Suite 100 an 48098-3276 -879-5666	PROJECT DATE AUGUST 23, 2023	M7.0
1-879-0007	CHECKED BY	

WEK

												Р	OWER	VENTIL	ATOR :	SCHEDU	JLE																	
UNIT IDENTIFICATION	SYSTEM SERVED	TYPE	AIRFLOW CFM	T.S.P. IN. W.G.	TIP SPEED FPM	FAN RPM		M	OTOR		CURB HEIGHT INCHES	MODULATION/ CONTROL TYPE		ELEC	TRICAL								MAXIMU	M SOUND	POWER LEV	VELS							MODEL NUMBER	KEYED NOTES
							BHP	HP	RPM	DRIVE TYPE	1		VOLTS PHASE SCCR OPTIONS/ KA ACCESSORIES 63 HZ 125 HZ 250 500								w BY OCTA	VE BAND					UNIT IN	NLET Lw BY	OCTAVE I	BAND				
															KA	ACCESSORIES	63 HZ (DB)	125 HZ (DB)	250 HZ (DB)	500 HZ (DB)	1000 HZ (DB)	2000 HZ (DB)	4000 HZ 8 (DB)	3000 HZ (DB)	63 HZ (DB)	125 HZ (DB)	250 HZ (DB)	500 HZ (DB)	1000 HZ (DB)	2000 HZ (DB)	4000 HZ (DB)	8000 HZ (DB)		
EF-6H	TOILET H126	CENTRIFUGAL	100	0.25	3161	1486	0.01	1/10	1725	DIRECT	18	AUTO	120	1	5	В									57	61	58	48	47	48	39	32	G-060-VG	
EF-7H	CHEMICAL STORAGE H129	CENTRIFUGAL	200	0.5	3669	1725	0.03	1/15	1725	DIRECT	18	AUTO	120	1	5	В									68	71	69	54	49	47	43	38	G-070-VG	
EF-8H	DISHWASHER HOOD	CENTRIFUGAL	200	0.5	3669	1725	0.03	1/15	1725	DIRECT	18	AUTO	120	1	5	В									68	71	69	54	49	47	43	38	G-070-VG	
EF-9H	KITCHEN HOOD	CENTRIFUGAL	3600	1.0	6693	1538	1.39	2	1725	DIRECT	18	AUTO	208	1	5	В									78	85	86	84	78	74	71	68	CUE-160-VG	
EF-10H	KITCHEN HOOD	CENTRIFUGAL	5100	1.5	7299	1304	2.53	3	1360	DIRECT	18	AUTO	208	3	5	В									93	81	88	74	70	69	67	62	CUE-200-VG	

GENERAL NOTES:

1. REFER TO SCHEDULES GENERAL NOTES. 2. MODEL NUMBERS ARE GREENHECK UNLESS OTHERWISE NOTED.

				ST	EAM HUI	MIDIFIER	SCHEDU	JLE			
UNIT IDENTIFICATION	SYSTEM SERVED				AHU D	ISTRIBUTION TUBE B	ANK			MODULATION/ CONTROL TYPE	REMARKS
		QUANTITY REQUIRED	TYPE	MODEL LBS/HR	AHU AIR TEMPERATURE °F	AHU WIDTH INCHES	AHU HEIGHT INCHES	MAXIMUM ABSORPTION DISTANCE INCHES	MODEL		
H–1	AHU-21H	1	INSULATED MULTIPLE TUBES	62.8	88.9	78	48	26"	DRISTEEM	AUTO	

1. REFER TO SCHEDULES GENERAL NOTES. 2. MODEL NUMBERS ARE DRISTEEM UNLESS OTHERWISE NOTED.
3. PROVIDE STEAM DISTRIBUTION ASSEMBLY TO AHU MANUFACTURE FOR MOUNTING IN AHU HUMIDIFIER SECTION.

						GAS	FIRED	CONDE	ENSING	ВО	ILE	RSC	CHED	ULE						
UNIT IDENTIFICATION	TURNDOWN		FUEL	AGA INPUT	AGA OUTPUT	MINIMUM EFFICIENCY		DIMENSIONS			١	VATER		UNIT CONTROL TYPE		ELEC	CTRICAL		MODEL NUMBER	KEYED NOTES
		TYPE	MAXIMUM ALLOWABLE OUTPUT AT MINIMUM FIRING RATE (MBH)	МВН	МВН	(%)	DEPTH (IN.)	WIDTH (IN.)	HEIGHT (IN.)	E.W.T.	L.W.T. °F	FLOW GPM	MAXIMUM W.P.D. FT. HD.		VOLTS	PHASE	FLA	OPTIONS/ ACCESSORIES		
B-11	20:1	NAT GAS	100	2000	1800	90	43.6	28	78	90	130	140	7	AUTO	120	1	16	В	BMK2000	
B-12	20:1	NAT GAS	100	2000	1800	90	43.6	28	78	90	130	140	7	AUTO	120	1	16	В	BMK2000	

GENERAL NOTES:

1. REFER TO SCHEDULES GENERAL NOTES.
2. MODEL NUMBERS ARE AERCO UNLESS OTHERWISE NOTED. 3. PROVIDE BOILER WITH CONDENSATE NEUTRALIZATION TANK ASSEMBLY. 4. MINIMUM PRESSURE RATING OF 125 PSIG.

		GRILLI	E, REGI	STER, AN	ID DIFFUS	SER SCHE	EDULE		
UNIT IDENTIFICATION	TYPE	FACE SIZE	NECK SIZE	FRAME TYPE	ACCESSORY	CONSTRUCTION	FINISH	MODEL NUMBER	KEYED NOTES
S – 1	DIFFUSER	24x24	SEE PLANS	LAY-IN	NONE	STEEL	WHITE	SQD	
R–1	GRILLE	24x24	SEE PLANS	LAY-IN	NONE	ALUMINUM	WHITE	80	
R-2	GRILLE	24x12	SEE PLANS	LAY-IN	NONE	ALUMINUM	WHITE	80	
E-1	GRILLE	12x12	SEE PLAN	LAY-IN	NONE	ALUMINUM	WHITE	80	
E-2	GRILLE	24x24	SEE PLAN	LAY-IN	NONE	ALUMINUM	WHITE	80	
L-1	LOUVER	72x78	SEE PLAN	FLANGED	NONE	ALUMINUM	MILL	ESD-635	1
L-2	LOUVER	66x78	SEE PLAN	FLANGED	NONE	ALUMINUM	MILL	ESD-635	1

GENERAL NOTES:

1. MODEL NUMBERS ARE PRICE UNLESS OTHERWISE NOTED.

KEYED NOTES:

1. MODEL NUMBERS ARE GREENHECK.

				EX	PANSIC	ON TAN	K SCHE	EDULE					
UNIT IDENTIFICATION	SYSTEM SERVED	ESTIMATED TOTAL SYSTEM VOLUME	TYPE	OPERATIN	G PRESSURE	OPERATING T	EMPERATURE	TANK VOLUME	ACCEPTANCE VOLUME	DIMEN	SIONS	MODEL NUMBER	REMARKS
	OLIVED.	GALLON		MINIMUM PSIG	MAXIMUM PSIG	MINIMUM *F	MAXIMUM °F	GALLON	GALLON	DIAMETER INCHES	HEIGHT INCHES	Womber	
ET-1	HWHS	200	BLADDER	16	35	40	140	10	7.43	12	24	B35	

UNIT IDENTIFICATION

PG35

<u>NOTE:</u> 1. MODEL NUM 2. COLD FILL I

	HWHS	200	BLADDER	16	35	40	140	10	7.43	12	24	B35	
	irs are bel Essure = 1	L & GOSSETT UNLESS 2PSI	S OTHERWISE NOT	ED.									
<u> </u>	~~	····	·····				~~~~	_				_	
			}			GLY	COL M	AKEU	P UNIT	SCHE	DULE	:	

FLUID TYPE TANK VOLUME FILL PRESSURE

1. MODEL NUMBERS ARE WESSELS UNLESS OTHERWISE NOTED.
2. FLUID TYPE: W = WATER, PGXX = PROPYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL, EGXX = ETHYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL.

INLET/OUTLET PIPE SIZE (INCHES)	MAX SYSTEM FLOW (GPM)	MAX PRESSURE DROP CLEAN (FT HD)	OPERATING WEIGHT (LBS)	TYPE	MODEL NUMBER	}
2	35	0.70	66	STANDARD VELOCITY / AIR & DIRT	VDT 200 FA] {
2 1/2	57	0.75	75	STANDARD VELOCITY / AIR & DIRT	VDT 250 FA] {
3	100	5.0	178	HIGH VELOCITY / AIR & DIRT	VHT 300 FA] {
4	220	6.0	186	HIGH VELOCITY / AIR & DIRT	VHT 400 FA])
6	650	8.0	336	HIGH VELOCITY / AIR & DIRT	VHT 600 FA] }
8	1400	9.0	590	HIGH VELOCITY / AIR & DIRT	VHT 800 FA] {
10	2400	10.0	986	HIGH VELOCITY / AIR & DIRT	VHT 1000 FA	[
12	3500	12.0	1518	HIGH VELOCITY / AIR & DIRT	VHT 1200 FA] { _

VOLTS

									НО	T WA	TER C	ABINET U	NIT H	EATE	R SCI	HEDUI	LE								
UNIT IDENTIFICATION	CAPACITY MBH		AIR		F	AN			WATER			CONTROL VALVE W.P.D. FT. HEAD		DIMENSIONS		RECESS DEPTH	FIL	TER	MODULATION/ CONTROL TYPE		ELEC	TRICAL		MODEL NUMBER	KEYED NOTES
		AIRFLOW CFM	E.D.B. °F	L.D.B. *F	HP	RPM	FLOW GPM	FLUID TYPE	E.W.T. *F	L.W.T. *F	MAXIMUM W.P.D. FT. HEAD		LENGTH INCHES	HEIGHT INCHES	DEPTH INCHES	INCHES	TYPE	AREA SQ. FT.	SONINGE THE	VOLTS	PHASE	SCCR KA	OPTIONS/ ACCESSORIES		
CUH-3H	19.0	860	60	80.4	1/10	1050	2.8	PG35	130	100	1.5	15	61	44	9.5	9	WASHABLE	3.5	AUTO	120	1	5	В	RC-1200-08	
CUH-4H	19.0	860	60	80.4	1/10	1050	2.8	PG35	130	100	1.5	15	61	44	9.5	9	WASHABLE	3.5	AUTO	120	1	5	В	RC-1200-08	
CUH-5H	30.4	1040	60	86.9	1/10	1050	4.4	PG35	130	100	1.5	15	66	49	9.5	9	WASHABLE	3.5	AUTO	120	1	5	В	RC-1200-10	1
CUH-6H	28.2	845	60	90.8	1/10	1050	4.1	PG35	130	100	1.5	15	61	44	9.5	0	WASHABLE	3.5	AUTO	120	1	5	В	WI-1110-08	1
GENERAL NOTES:	_	-	•			•	•																		

 REFER TO SCHEDULES GENERAL NOTES.
 MODEL NUMBERS ARE STERLING UNLESS OTHERWISE NOTED. 3. FLUID TYPE: W = WATER, PGXX = PROPYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL, EGXX = ETHYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL.

KEYED NOTES:

1. HIGH CAPACITY COIL

MODEL

GMP SERIES GMP-18

NUMBER

PHASE

KEYED NOTES

				НО	T WA	TER I	PROP	ELLE	R FAN I	JNIT HEA	TER SCH	EDUL	E				
CAPACITY MRH	AIRFLOW CFM	LEAVING AIR	F/	AN			WATER			CONTROL VALVE	MODULATION/		ELE	CTRICAL		MODEL NUMBER	KEYED NOTES
WOIT	OI W	*F	HP	RPM	FLOW GPM	FLUID TYPE	E.W.T. *F	L.W.T. *F	MAXIMUM W.P.D. FT. HEAD	Will be The HEAD	CONTROL TIFE	VOLTS	PHASE	SCCR KA	OPTIONS/ ACCESSORIES	NOMBLIN	
12.7	750	104	1/20	1000	1.8	PG35	130	100	0.12	15	AUTO	120	1		В	HS-48	
53.0	1800	103	1/12	1000	3.9	PG35	130	100	0.36	15	AUTO	120	1		В	HS-108	
53.0	1800	103	1/12	1000	3.9	PG35	130	100	0.36	15	AUT0	120	1		В	HS-108	
12.7	750	104	1/20	1000	1.8	PG35	130	100	0.12	15	AUTO	120	1		В	HS-48	
	12.7 53.0 53.0	MBH CFM 12.7 750 53.0 1800 53.0 1800	MBH CFM TEMPERATURE F 12.7 750 104 53.0 1800 103 53.0 1800 103	MBH CFM TEMPERATURE HP 12.7 750 104 1/20 53.0 1800 103 1/12 53.0 1800 103 1/12	CAPACITY MBH AIRFLOW CFM LEAVING AIR TEMPERATURE F F F HP RPM 12.7 750 104 1/20 1000 53.0 1800 103 1/12 1000 53.0 1800 103 1/12 1000	CAPACITY MBH AIRFLOW CFM LEAVING AIR TEMPERATURE F FILOW GPM 12.7 750 104 1/20 1000 1.8 53.0 1800 103 1/12 1000 3.9 53.0 1800 103 1/12 1000 3.9	CAPACITY MBH AIRFLOW CFM LEAVING AIR TEMPERATURE F FAN HP RPM FLOW GPM FLUID TYPE 12.7 750 104 1/20 1000 1.8 PG35 53.0 1800 103 1/12 1000 3.9 PG35 53.0 1800 103 1/12 1000 3.9 PG35	CAPACITY MBH AIRFLOW CFM LEAVING AIR TEMPERATURE F FAN WATER 12.7 750 104 1/20 1000 1.8 PG35 130 53.0 1800 103 1/12 1000 3.9 PG35 130 53.0 1800 103 1/12 1000 3.9 PG35 130	CAPACITY MBH AIRFLOW CFM LEAVING AIR TEMPERATURE F FAN FLOW GPM FLUID TYPE E.W.T. F L.W.T. F 12.7 750 104 1/20 1000 1.8 PG35 130 100 53.0 1800 103 1/12 1000 3.9 PG35 130 100 53.0 1800 103 1/12 1000 3.9 PG35 130 100	CAPACITY MBH AIRFLOW CFM LEAVING AIR TEMPERATURE TF FAN FLOW GPM FLUID TYPE E.W.T. TF L.W.T. TF MAXIMUM W.P.D. FT. HEAD 12.7 750 104 1/20 1000 1.8 PG35 130 100 0.12 53.0 1800 103 1/12 1000 3.9 PG35 130 100 0.36 53.0 1800 103 1/12 1000 3.9 PG35 130 100 0.36	CAPACITY AIRFLOW CFM CFM TEMPERATURE T	CAPACITY AIRFLOW CFM TEMPERATURE F F F F F F F F F	CAPACITY MBH CFM LEAVING AIR TEMPERATURE T	MBH CFM TEMPERATURE T MAXIMUM M.P.D. FT. HEAD CONTROL TYPE TYPE TEMPERATURE T MAXIMUM M.P.D. FT. HEAD CONTROL TYPE TYPE T MAXIMUM M.P.D. FT. HEAD CONTROL TYPE TYPE TYPE TYPE TYPE T MAXIMUM M.P.D. FT. HEAD CONTROL TYPE TYP	CAPACITY MBH AIRFLOW CFM LEAVING AIR TEMPERATURE F F AIRFLOW CPM F AIRFLOW CPM WATER WATER CONTROL VALVE W.P.D. FT. HEAD MODULATION/ CONTROL TYPE ELECTRICAL 12.7 750 104 1/20 1000 1.8 PG35 130 100 0.12 15 AUTO 120 1 53.0 1800 103 1/12 1000 3.9 PG35 130 100 0.36 15 AUTO 120 1 53.0 1800 103 1/12 1000 3.9 PG35 130 100 0.36 15 AUTO 120 1	CAPACITY MBH CFM TEMPERATURE T F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F F	CAPACITY MBH CFM LEAVING AIR TEMPERATURE T F F F F F F F F F

GENERAL NOTES:

1. REFER TO SCHEDULES GENERAL NOTES.
2. MODEL NUMBERS ARE STERLING UNLESS OTHERWISE NOTED.
3. FLUID TYPE: W = WATER, PGXX = PROPYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL, EGXX = ETHYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL.

			Н	OT W	ATEF	FINN	ED TU	JBE R	ADIA	ΓΙΟΝ :	SCHE	DULE			
UNIT IDENTIFICATION	CAPACITY BTUH/	ENTERING AIR TEMP	FLUID TYPE	WATER	TEMP.		ENCLOSURE			EL	EMENT		CONTROL VALVE W.P.D. FT. HEAD	MODEL NUMBER	KEYED NOTES
DEN III IONII ON	LINEAR FT.	*F		E.W.T. *F	AVERAGE *F	TYPE	LENGTH INCHES	HEIGHT INCHES	TUBE DIAMETER INCHES	WIDTH INCHES	HEIGHT INCHES	NUMBER OF TIERS	Will John Till Till Till Till Till Till Till Til	Nomber	
FTR-1	300	65	W	130	110	SLOPE TOP (JVB-S-LT)	SEE PLAN	14	0.75	4.25	3.63	1	15	C3/4-433-14B	

GENERAL NOTES:

1. MODEL NUMBERS ARE STERLING UNLESS OTHERWISE NOTED. 2. FLUID TYPE: W = WATER, PGXX = PROPYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL, EGXX = ETHYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL.

		НОТ	WATE	ER RA	DIAN	Γ CEII	LING PA	NEL SCH	I EDULE		
UNIT IDENTIFICATION	CAPACITY BTUH/ LINEAR FT.	FLUID TYPE	WATER E.W.T. °F	L.W.T.	DIMEN LENGTH INCHES	SIONS WIDTH INCHES	Finish	CONSTRUCTION	CONTROL VALVE W.P.D. FT. HEAD	MODEL NUMBER	KEYED NOTES
RCP-1	142	PG35	130	100	SEE PLANS	12	WHITE	STEEL	15	RC-4	

GENERAL NOTES:

1. MODEL NUMBERS ARE RUNTAL UNLESS OTHERWISE NOTED.
2. EXTRUDED ARCHITECTURAL SPACE MASTERY SERIES HEF-2 FLUTED.
3. FLUID TYPE: W = WATER, PGXX = PROPYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL, EGXX = ETHYLENE GLYCOL SOLUTION XX PERCENTAGE OF GLYCOL.

VARIAE	BLE FRE	EQUENCY	CONTRO	LLER SCH	IEDULE
UNIT IDENTIFICATION	SYSTEM SERVED	LOCATION	RATED HORSEPOWER	OPERATING HORSEPOWER	REMARKS
VFC-AHU-21H-SF	SF-1	SEE DRAWINGS	15	11.3	PRIMARY
VFC-AHU-21H-RF	RF-1	SEE DRAWINGS	7.5	5.1	PRIMARY
VFC-AHU-22H-SF	SF-2	SEE DRAWINGS	10	7.9	PRIMARY
VFC-EF-9H	EF-9H	SEE DRAWINGS	2	1.4	PRIMARY
VFC-EF-10H	EF-10H	SEE DRAWINGS	3	2.5	BACKUP

NOTE:

1. REFER TO SPECIFICATIONS FOR APPROVED MANUFACTURERS.
2. REFER TO ELECTRICAL WIRING DIAGRAM FOR CONNECTION REQUIREMENTS.




1	ADDENDUM #3	09/29/23
NO.	REVISION	DATE

CONTRACT NO. Y22003

STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255



WTA A RCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500:


CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

MECHANICAL SCHEDULES


PROJECT NUMBER SHEET NUMBER PROJECT DATE AUGUST 23, 2023 CHECKED BY WEK


M7.04



TC DEVICE STANDARD MOUNTING HEIGHTS DETAIL

AVERAGING ELEMENT INSTALLATION DETAIL NO SCALE





Typical Work Station

(NOTE 8)

ETHERNET

1200 🖳

TEMPERATURE

CONTROL

SUPERVISORY

(NOTES 2, 3 & 5)

TEMPERATURE CONTROL GENERAL NOTES

1. THESE GENERAL NOTES SHALL BE APPLICABLE FOR ALL TC

3. TC CONTRACTOR SHALL BE RESPONSIBLE TO COMPLY WITH

4. THE PORTIONS OF CONTROL DIAGRAMS AND WIRING DIAGRAMS

DRAWN IN HEAVY LINE WEIGHT INDICATE NETWORK. THE

PORTIONS DRAWNS IN LIGHT LINE WEIGHT INDICATE EXISTING.

2. "PROVIDE" IS DEFINED AS "FURNISH AND INSTALL".

ALL APPLICABLE CODES AND STANDARDS.

(TYP.) —

OWNER'S CAMPUS ETHERNET (TCP/IP)

FIREWALL

TEMPERATURE

CONTROL

AUX PANEL

AS REQ'D

NO SCALE (JOHNSON CONTROL SYSTEM)

INFORMATION TECHNOLOGY PERSONNEL.

FOR EACH SYSTEM.

NOTES:

BACNET MS/TP

120V - - -

TEMPERATURE

CONTROL

(DDC) PANEL

QTY AS REQ'D

(AHU-21H)

(NOTES 1, 2, & 3)

DDC SYSTEM ARCHITECTURE

REFER TO TEMPERATURE CONTROL SCHEMATICS FOR THE REQUIRED POINTS ASSOCIATED

AND AVAILABLE MOUNTING SPACE. UNLESS SPECIFICALLY NOTED IN DESIGN DRAWINGS. TC

WHERE IDENTIFIED ON ELECTRICAL PANEL SCHEDULES. COORDINATE WITH ELEC

LOCATED IN MECHANICAL OR ELECTRICAL ROOMS - COORDINATE LOCATIONS. MAXIMUM

BUILDING DDC NETWORK SHALL BE CONNECTED TO THE ETHERNET, TC CONTRACTOR

SHALL PROVIDE DDC PANEL OR OTHER INTERFACE COMPONENT COMPATIBLE FOR THIS CONNECTION. COORDINATE ETHERNET CONNECTION AND I/P ADDRESS WITH OWNER'S

2. TC CONTRACTOR SHALL DETERMINE DDC PANEL QUANTITY BASED ON POINT DENSITIES

3. TC CONTRACTOR SHALL PROVIDE REQUIRED POWER SUPPLIES FROM SPARE CIRCUITS

4. 24V TRANSFORMERS REQUIRED FOR TERMINAL UNIT DDC CONTROLLERS SHALL BE

TRANSFORMER SIZE SHALL BE 100VA. PROVIDE ENCLOSURE(S) FOR TRANSFORMERS.

6. AUXILIARY PANEL FOR GAUGES, TRANSMITTERS, RELAYS, POWER TRANSFORMERS, ETC.

7. TC CONTRACTOR SHALL CONNECT ALL NEW TERMINAL UNIT CONTROLLERS TO NEW


CONTRACTOR SHALL LOCATE DDC PANELS AND COORDINATE WITH OTHER TRADES.

CONTRACTOR. REFER TO ELECTRICAL DWGS FOR PANEL LOCATIONS.

CAMPUS BMS NETWORK VIA IT ASSOCIATED AHU CONTROL PANEL..

8. PROVIDE COMPLETE GRAPHICS FOR THE NEW HVAC SYSTEMS.

NEW DATA DROP CONNECTION



INTERNET/INTRANET

FIREWALL

REMOTE WEB BROWSER

1200 🖳

TEMPERATURE

CONTROL

AUX PANEL

AS REQ'D

(NOTE 6)

UNIT DDC

CONTROLLER

TEMPERATURE

(DDC) PANEI

QTY AS REQ'D

(AHU-22H)

(NOTES 1, 2, & 3)

COMMUNICATION NETWORK

UNIT CONTROLLERS.

CABLE TO OTHER TERMINAL

BACNET MS/TP

TERMINAL

UNIT DDC

CONTROLLER

(NOTES 1, 2 & 4)

OWNER'S ETHERNET (TCP/IP)

- 12. ALL DDC AND CONTROL INTERLOCK WIRING BETWEEN COMPONENTS SHALL BE INSTALLED WITHOUT INTERMEDIATE STOPS. WIRE SPLICING AT INTERMEDIATE TERMINAL STRIPS IS NOT ACCEPTABLE.
- 13. ALL ELECTRICAL WIRING AND RACEWAY SYSTEMS SHALL COMPLY WITH ELECTRICAL SPECIFICATION REQUIREMENTS. TWO SEPERATE ELECTRICAL RACEWAY SYSTEMS SHALL BE PROVIDED: ONE FOR A.C. WIRING AND THE OTHER FOR D.C.
- 14. TC CONTRACTOR SHALL BE RESPONSIBLE FOR ALL POWER SUPPLIES REQUIRED FOR TC SYSTEM UNLESS OTHERWISE NOTED. REFER TO ELECTRICAL PANEL SCHEDULES FOR SPARE CIRCUITS OR CIRCUITS DEDICATED TO TEMPERATURE CONTROLS. COORDINATE CIRCUIT USE WITH ELECTRICAL CONTRACTOR.
- 15 TC CONTRACTOR SHALL VERIFY EXACT LOCATION OF ALL FIELD MOUNTED COMPONENTS.
- 16. THERMOSTATS AND SPACE TEMPERATURE SENSORS SHALL BE MOUNTED 4'-0" ABOVE FINISHED FLOOR UNLESS NOTED
- 17. TC CONTRACTOR SHALL PROVIDE AUXILIARY PANELS FOR REQUIRED PANEL MOUNTED EQUIPMENT SUCH AS RELAYS, TRANSDUCERS, CONTROL TRANSFORMERS, ETC. AUXILIARY PANELS SHALL BE LOCATED NEXT TO ASSOCIATED DDC
- REMOTELY MOUNTED FIELD DEVICES SUCH AS RELAYS, CONTROL TRANSFORMERS, ETC., SHALL BE HOUSE IN AN ENCLOSURE PROVIDED BY THE TC CONTRACTOR.

19. CONTROL TRANSFORMERS WHEN REQUIRED SHALL BE SIZED FOR 150% OF ACTUAL LOAD.

BELT OR DRIVE FAILURE.

20. FREEZE-STATS SHALL BE MOUNTED ON UPSTREAM FACE OF COOLING COILS.

21. CURRENT SWITCHES USED FOR OPERATIONAL STATUS SHALL

HAVE CURRENT THRESHOLD SETPOINT ADJUSTED TO INDICATE


- 22. ALL CONTROL VALVES, CONTROL DAMPERS AND ASSOCIATED CONTROL ACTUATORS IDENTIFIED ON TC DRAWINGS SHALL BE FURNISHED BY TC CONTRACTOR UNLESS OTHERWISE NOTED. DAMPER SIZE AND LOCATIONS ARE INDICATED ON MECHANICAL
- FLOOR PLAN DRAWINGS. 23. ALL CONTROL VALVES AND DAMPERS FURNISHED BY THE TC CONTRACTOR SHALL BE INSTALLED BY THE MECHANICAL CONTRACTOR. ALL PIPE PENETRATIONS AND BASIC FITTINGS
- 24. DAMPER ACTUATORS SHALL BE INSTALLED BY TO

BY MECHANICAL CONTRACTOR.

25. ALL INSTRUMENTATION TUBING REQUIRED FOR DPS, DPT AND SPT COMPONENT INSTALLATIONS SHALL BE PROVIDED BY TC CONTRACTOR.

REQUIRED FOR SENSOR INSTALLATIONS SHALL BE PROVIDED

- 26. TC CONTRACTOR SHALL FIELD MOUNT ALL REQUIRED PACKAGED CONTROL COMPONENTS FURNISHED BY EQUIPMENT SUPPLIERS WHERE INDICATED. ALL REQUIRED 24V PACKAGED CONTROL FIELD WIRING AND 120V FAN INTERLOCK WIRING SHALL BE PROVIDED BY TC CONTRACTOR UNLESS NOTED OTHERWISE. TC CONTRACTOR SHALL COORDINATE SPECIFIC SYSTEM WIRING REQUIREMENTS WITH PACKAGED EQUIPMENT SUPPLIERS.
- 27.. ROOM TEMPERATURE SENSORS ARE IDENTIFIED IN GENERAL LOCATIONS TEMPERATURE CONTROL CONTRACTOR SHALL VERIFY FINAL LOCATION IN FIELD PRIOR TO INSTALLATION.



OWNER REVIEW 08/02/23 DATE REVISION STATE OF MICHIGAN DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION

ADAM LACH, RA, DIRECTOR

DESIGN AND CONSTRUCTION DIVISION

FILE NO. 491/20167.SDW

> CONTRACT NO. FUNDING CODE 171CODHHS7255 Y22003

WTAARCH.COM

| WTA A RCHITECTS |

100 S Jefferson Ave, Suite 601

Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

Peter Basso Associates In

CONSULTING ENGINEERS

5145 Livernois, Suite 100

Troy, Michigan 48098-3276

Tel: 248-879-5666 Fax: 248-879-0007


www.PeterBassoAssociates.com PBA Project No.: 2021-0402

TEMPERATURE CONTROL STANDARDS AND GENERAL **NOTES**

PROJECT NUMBER SHEET NUMBER PROJECT DATE M8.01 AUGUST 23, 2023 CHECKED BY WEK

REFER TO SHEET M801 FOR T.C. (TEMPERATURE CONTROL) GENERAL NOTES.


CURRENT SWITCH INSTALLATION DETAIL



, INTERLOCK TO RF VFC CM (AO) SPEED CONTROL SIGNAL HI-LIMIT CIRCUIT NOT USED (STATUS BY CURRENT SWITCH) STATUS ENABLE


AHU-21H SF VFC WIRING

1. WIRING DETAIL IDENTIFIES INTENT AND DOES NOT INDICATE ACTUAL WIRING REQUIREMENTS. CONSULT WITH VFC SUPPLIER FOR THE ACTUAL WIRING REQUIREMENTS.



AHU-21H RF VFC WIRING

NOTE: 1. WIRING DETAIL IDENTIFIES INTENT AND DOES NOT INDICATE ACTUAL WIRING REQUIREMENTS. CONSULT WITH VFC SUPPLIER FOR THE ACTUAL WIRING REQUIREMENTS.



TYPICAL EXHAUST FAN CONTROL

TYPICAL STAFF TOILET EF-6H, CHEMICAL STORAGE EF-7H AND DISH WASH AREA EF-8H.

1. REFER TO FLOOR PLANS FOR QUANTITIES AND LOCATIONS..


SEQUENCE OF OPERATION

- 1. EXHAUST FAN SHALL BE STARTED AND STOPPED BY DDC BASED ON TIME SCHEDULE. WIRING INTERLOCK SHALL OPEN DAMPERS.
- 2. DDC SHALL MONITOR EF RUN STATUS THRU CURRENT SWITCH. ABNORMAL STATUS CONDITION SHALL ACTIVATE ALARM.

AIR HANDLING UNIT AHU-21H CONTROL SCHEMATIC

NO SCALE SERVES DINNING ROOM AND KITCHEN

- DAMPERS SHALL BE FURNISHED AND FACTORY INSTALLED BY AHU MANUFACTURER. TC CONTRACTOR SHALL PROVIDE DAMPER ACTUATORS.
- 2. ELECTRICAL CONTRACTOR SHALL PROVIDE FIRE ALARM SYSTEM COMPONENTS AND WIRING FROM FIRE ALARM PANEL TO CONTROL MODULE. TC CONTRACTOR SHALL PROVIDE WIRING FROM CONTROL MODULE TO VFC SAFETY CIRCUIT.
- 3. COORDINATE EXACT CONTROL, WIRING, AND INTERFACE REQUIREMENTS WITH EQUIPMENT SUPPLIER. REQUIREMENTS MAY VARY DEPENDING ON MANUFACTURER.



AIR TERMINAL UNIT WITH PERIMETER HTG CONTROL

NOTES:

PROVIDE DAMPER ACTUATOR.

- 1. REFER TO PIPING & SHEET METAL PLANS FOR LOCATIONS AND QUANTITY OF UNITS AND LOCATIONS OF ROOM TEMP SENSORS.
- 2. WHERE INDICATED ON FLOOR PLANS, SPACE TEMPERATURE SHALL BE REFERENCED TO MULTIPLE AIR TERMINAL UNIT CONTROLLERS VIA DDC NETWORK.
- 3. PERIMETER HEATING CONTROL VALVE SHALL BE CONTROLLED FROM THE ASSOCIATED TERMINAL UNIT CONTROLLER AS SHOWN ON HVAC PIPING PLANS.
- 4. TC CONTRACTOR SHALL PROVIDE 24V POWER SUPPLY TO TERMINAL UNIT CONTROLLER.
- 5. TERMINAL UNIT MANUFACTURER SHALL PROVIDE DAMPER AND TC CONTRACTOR SHALL
- 6. TERMINAL UNIT MANUFACTURER SHALL PROVIDE VELOCITY SENSOR FOR SYSTEM CONTROL. TC CONTRACTOR SHALL COORDINATE WITH TAB CONTRACTOR TO DETERMINE DAMPER CONTROL SETTINGS TO ACHIEVE SCHEDULED MINIMUM AND MAXIMUM CFMs.
- 7. TC CONTRACTOR SHALL FURNISH CONTROL VALVES FOR HEATING ELEMENTS PER THE MECHANICAL DETAILS. SELECT CONTROL VALVES TO ACHIEVE THE SCHEDULED FLOW

SEQUENCE OF OPERATION

AIR TERMINAL UNIT WITH PERIMETER HEATING:

NOTE: ALL SETPOINTS DESCRIBED IN SEQUENCE SHALL BE ADJUSTABLE BY SYSTEM OPERATORS (CREATE REQUIRED VIRTUAL POINTS). APPROPRIATE DEADBANDS SHALL BE USED TO PREVENT SHORT CYCLING SITUATIONS.

- 1. ALL TU'S ASSOCIATED WITH A SINGLE SPACE TEMP SENSOR SHALL CONTROL IN
- 2. SUPPLY AIR TERMINAL UNIT'S (TU) VAV MINIMUM AND MAXIMUM AIRFLOW SETTINGS SHALL BE AS INDICATED ON THE MECHANICAL SCHEDULES. WHERE MINIMUM AND MAXIMUM AIRFLOW SETTINGS ARE THE SAME, THE TU CONTROLLER SHALL PERFORM CONSTANT AIR VOLUME CONTROL.
- 3. IN ALL MODES OF HEATING, TU DISCHARGE AIR TEMP SENSOR SHALL PROVIDE HIGH LIMIT SETPOINT CONTROL AT 90°F DAT.
- 4. WHEN ROOM TEMPERATURE RISES ABOVE THE SETPOINT, THE SUPPLY AIR TERMINAL UNIT CONTROLLER SHALL KEEP THE TEMPERING COIL VALVE AND PERIMETER HEATING CONTROL VALVE CLOSED AND SHALL MODULATE THE SUPPLY AIRFLOW BETWEEN ITS MINIMUM AND MAXIMUM SETTING TO MAINTAIN ROOM TEMPERATURE.
- 5. WHEN OA TEMP IS 60 DEG F OR BELOW AND ROOM TEMPERATURE FALLS BELOW SETPOINT, THE SUPPLY TERMINAL UNIT CONTROLLER SHALL KEEP THE SUPPLY AIRFLOW AT ITS MINIMUM SETTING AND SHALL FIRST MODULATE THE PERIMETER HEATING CONTROL VALVE FOLLOWED BY TEMPERING COIL CONTROL VALVE (WHEN PERIMETER HEATING CONTROL VALVE IS FULL OPEN) TO MAINTAIN THE ROOM TEMPERATURE SETPOINT.
- 6. WHEN OA TEMP IS ABOVE 60 DEG F AND ROOM TEMPERATURE FALLS BELOW SETPOINT, THE SUPPLY TERMINAL UNIT CONTROLLER SHALL KEEP THE SUPPLY AIRFLOW AT ITS MINIMUM SETTING AND SHALL MODULATE THE TEMPERING COIL CONTROL VALVE TO MAINTAIN THE ROOM TEMPERATURE SETPOINT. PERIMETER HEATING CONTROL VALVE SHALL REMAIN CLOSED.
- 7. THE SUPPLY AIR TERMINAL UNIT'S MINIMUM AND MAXIMUM VOLUME AIRFLOW
- SETTINGS SHALL BE AS INDICATED ON THE SHEET METAL FLOOR PLANS 8. WHEN SPACE CARBON DIOXIDE LEVEL RISES ABOVE 1100 PPM SETPOINT, THE SUPPLY AIR TU CONTROLLER SHALL OVERRIDE TEMPERATURE CONTROL AND MODULATE DAMPER OPEN TO INCREASE SUPPLY AIRFLOW UNTIL CO2 SETPOINT IS SATISFIED. THE TEMPERING COIL VALVE SHALL BE MODULATED TO MAINTAIN SPACE TEMP SETPOINT. [NOTE: THERE IS NOT A REQUIREMENT TO INCREASE OUTSIDE AIRFLOW AT RELATED RTU IF CO2 LEVEL IS ABOVE SETPOINT WHEN TU DAMPER IS AT MAX POSITION].
- 9. WHEN SPACE CARBON DIOXIDE LEVEL FALLS BELOW 800 PPM SETPOINT AFTER BEING IN VENTILATION OVERRIDE MODE, THE TU DAMPER SHALL BE MODULATED CLOSED TOWARDS MINIMUM POSITION. THE TEMPERING COIL VALVE SHALL BE MODULATED TO MAINTAIN SPACE TEMP SETPOINT.
- 10. SPACE TEMPERATURE SETPOINTS SHALL BE AS FOLLOWS:
 - HEATING UNOCCUPIED SETPOINT = 62°F
 - HEATING TEMPORARY UNOCCUPIED SETPOINT = 68°F HEATING OCCUPIED SETPOINT = 70°F
 - COOLING OCCUPIED SETPOINT = 75°F

COOLING UNOCCUPIED SETPOINT = 80°F

- COOLING TEMPORARY UNOCCUPIED SETPOINT = 77°F
- REQUIRED TO MAINTAIN BUILDING SETBACK AND SETUP TEMP SETPOINTS.
- 12. WHEN RESPECTIVE AHU (RTU OR ERU) IS DEACTIVATED: THE AIR TERMINAL UNIT DAMPER SHALL REMAIN IN MINIMUM POSITION AND THE TEMPERING COIL VALVE SHALL REMAIN CLOSED. THE PERIMETER HEATING VALVE SHALL BE MODULATED TO MAINTAIN HEATING UNOCCUPIED SETPOINT.

14. CONTROL SIGNALS FOR AIR TERMINAL UNIT DAMPER ACTUATOR AND HEATING

CONTROL OUTPUT(S) SHALL BE DISPLAYED WITH SYSTEM GRAPHICS.

11. DURING BUILDING UNOCCUPANCY, RELATED AHU (RTU OR ERU) SHALL CYCLE AS

- 13. THE DDC TERMINAL UNIT CONTROLLER SHALL RE-CALIBRATE THE AIRFLOW SENSOR ONCE A WEEK MINIMUM. THE RE-CALIBRATION PROCESS SHALL BE STAGGERED AMONGST THE TERMINAL UNITS SO THE DUCT STATIC PRESSURE DOES NOT EXCEED LIMITS.

REFER TO SHEET M801 FOR T.C. (TEMPERATURE CONTROL) GENERAL NOTES.

SEQUENCE OF OPERATION


AIR HANDLING UNIT AHU-21H CONTROL:

NOTE: ALL SETPOINTS DESCRIBED IN SEQUENCE SHALL BE ADJUSTABLE BY SYSTEM OPERATORS (CREATE REQUIRED VIRTUAL POINTS). APPROPRIATE DEADBANDS SHALL BE USED TO PREVENT SHORT CYCLING SITUATIONS. ALL FAN MOTOR CONTROL SWITCHES SHALL BE IN "AUTO" POSITION.

- 1. SUPPLY SHALL HAVE START/STOP CAPABILITY FROM THE DDC SYSTEM. AHU SHALL OPERATE BASED ON TIME SCHEDULED OCCUPIED MODE COMPENSATED BY OPTIMUM START PROGRAM AND UNOCCUPIED CYCLE MODE. OPTIMUM START PROGRAM SHALL DETERMINE REQUIRED LEAD TIME TO ACHIEVE DESIRED SPACE TEMP AT BUILDING OCCUPANCY (BASED ON TRENDED DATA).
- 2. RETURN FAN SHALL BE ACTIVATED WITH SUPPLY FAN DURING OCCUPIED MODE.
- 3. EACH SF AND RF STATUS SHALL BE MONITORED BY DDC THRU RESPECTIVE FAN AUX. CONTACT SWITCH. ABNORMAL STATUS CONDITION SHALL ACTIVATE ALARM.
- 4. VFC COMMON FAILURE ALARM FOR EACH FAN OR FAN WALL SYSTEM SHALL BE MONITORED BY DDC THRU FAULT STATUS AT RESPECTIVE FAN VFC.
- 5. WHEN AHU IS ACTIVATED DURING OCCUPIED MODE; OUTSIDE & RETURN AIR (MIXED AIR) DAMPERS SHALL BE ALLOWED TO MODULATE AS DESCRIBED. WHEN AHU IS DEACTIVATED OR OPERATING IN UNOCCUPIED CYCLE MODE OR MORNING WARM-UP MODE, DAMPERS SHALL REMAIN IN NORMAL POSITIONS (FULL CLOSED TO OA).
- 6. DURING THE OCCUPIED PERIOD, THE OUTSIDE AIR FLOW MEASURING DEVICE THROUGH DDC SHALL MODULATE THE OUTSIDE AIR DAMPER (D-1) AND RECIRCULATION DAMPER (D-2) TO MAINTAIN A MINIMUM OUTSIDE AIR FLOW VOLUME RANGE BETWEEN OA MINIMUM AND OA MINIMUM MAXIMUM BASED ON DEMAND VENTILATION RESET CONTROL. THE DEMAND VENTILATION CONTROL THROUGH DDC SHALL MONITOR THE AHU'S RESPECTIVE RETURN AIR CO2 SENSOR, IF ALL THE ASSOCIATED AHU'S RETURN CO2 SENSOR IS READING 800 PPM OR BELOW, THE AHU'S OA MINIMUM SHALL BE MAINTAINED. IF THE ASSOCIATED AHU'S RETURN CO2 SENSOR IS READING ABOVE 800 PPM, THE AHU'S OUTSIDE AIR DAMPER SHALL BE MODULATED TOWARD THE OA MINIMUM MAXIMUM POSITION TO PREVENT CO2 LEVELS FROM RISING ABOVE 1,100 PPM. IF THE RETURN CO2 LEVEL RISES ABOVE 1,100 PPMP. THE ASSOCIATED AHU'S OUTSIDE AIR DAMPERS SHALL BE CONTROLLED TO THE MINIMUM MAXIMUM POSITION. ALL SETPOINTS SHALL BE ADJUSTABLE THROUGH THE DDC SYSTEM.
- 7. WHEN DISCHARGE AIR TEMP IS BELOW HEATING SETPOINT, DDC SHALL KEEP MIXED AIR DAMPERS AT MINIMUM OA POSITION AND MODULATE HEATING COIL VALVE TO ACHIEVE DISCHARGE AIR SETPOINT.
- 8. DURING MORNING WARM-UP OR UNOCCUPIED MODE HEATING CYCLE, DAT SETPOINT SHALL BE 95°F UNTIL BUILDING OCCUPANCY TIME OR WHEN SPACE TEMPERATURE SETPOINT IS REACHED.
- 9. WHEN SPACE TEMP IS ABOVE COOLING SETPOINT AND OUTDOOR AIR TEMPERATURE IS GREATER THAN 70°F, DDC SHALL KEEP MIXED AIR DAMPERS AT MINIMUM OA POSITION AND THE COOLING COIL CONTROL VALVE SHALL BE MODULATED TO MAINTAIN DISCHARGE AIR TEMP SETPOINT.
- 10. WHEN DISCAHRGE TEMP IS ABOVE COOLING SETPOINT AND OUTDOOR AIR TEMPERATURE IS LESS THAN 70°F, DDC SHALL MODULATE MIXED AIR DAMPERS ABOVE MINIMUM OA POSITION TO MAINTAIN SPACE TEMP SETPOINT.
- 11. DDC SHALL MODULATE HEATING COIL VALVE CONTROL TO MAINTAIN DISCHARGE AIR TEMP SETPOINT BASED ON THE FOLLOWING OUTDOOR AIR TEMP RESET SCHEDULE:



- 12. SF VFC SHALL BE MODULATED BY DDC TO MAINTAIN REMOTE SYSTEM SUPPLY AIR STATIC PRESSURE SETPOINT OF .75" W.G. (TO BE ADJUSTED BY THE AIR BALANCE CONTRACTOR). (REFER TO PLANS FOR LOCATION OF REMOTE STATIC PRESSURE
- 13. DISCHARGE STATIC PRESSURE HIGH LIMIT AT ERU WITH SETPOINT OF 5.0" W.G. SHALL PROVIDE OVERRIDE CONTROL OF SUPPLY FAN SPEED AND HIGH LIMIT SWITCH WITH SETPOINT OF 5.5" W.G. SHALL PROVIDE HARDWIRED SAFETY. DDC SHALL ACTIVATE ALARM IF OPERATING IN OVERRIDE CONDITION.
- 14. RF VFC SHALL BE MODULATED TO MAINTAIN A CFM DIFFERENTIAL SETPOINT BETWEEN SUPPLY AIRFLOW AND EXHAUST AIRFLOW. REFER TO CFM OFFSET SCHEDULES THIS SHEET FOR SUPPLY AND EXHAUST AIRFLOW DIFFERENTIAL.
- 15. FREEZESTAT(S) SHALL DEACTIVATE SF & INTERLOCKED EF WHEN TEMPERATURE IS 35°F OR BELOW. DDC SHALL MONITOR FREEZESTAT STATUS AND ACTIVATE ALARM IF CONDITION OCCURS.
- 16. DUCT SMOKE DETECTOR(S) SHALL DEACTIVATE SF & EF WHEN PRODUCTS OF
- COMBUSTION ARE DETECTED. 17. IF AHU IS DEACTIVATED, OUTDOOR AIR DAMPER SHALL CLOSE, CHILLED WATER COOLING COIL VALVE SHALL REMAIN CLOSED AND HEATING COIL VALVE SHALL BE MODULATED TO MAINTAIN A LOW LIMIT PLENUM TEMPERATURE SETPOINT OF 50°F (BASED ON READING AT NEAREST TEMP SENSOR).



DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

> CONTRACT NO. FUNDING CODE Y22003 171CODHHS7255



WTA A RCHITECTS 100 S Jefferson Ave, Suite 601

Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN


SHEET TITLE TEMPERATURE CONTROLS

Peter Basso Associates In CONSULTING ENGINEERS 5145 Livernois, Suite 100 Troy, Michigan 48098-3276 Tel: 248-879-5666 Fax: 248-879-0007


ROJECT NUMBER PROJECT DATE AUGUST 23, 2023 CHECKED BY www.PeterBassoAssociates.com PBA Project No.: 2021-0402 WEK

SHEET NUMBER

KITCHEN HOOD EF M/S WIRING




AHU-22H SF M/S WIRING



KEF'S AND AHU-22H CONTROL

FIRE SUPPRESSION SYSTEM IS NEW. COORDINATE VOLTAGE REQUIREMENTS, WIRING, ETC. WITH FIRE SUPPRESSION SYSTEM MANUFACTURER.




HWH UH & CUH CONTROL - NEW WORK

1. REFER TO FLOOR PLANS FOR QUANTITY AND LOCATION OF UNITS.


2. AQUASTAT SHALL BE WIRED IN SERIES WITH FAN CONTROL WIRING CIRCUIT.

SEQUENCE OF OPERATION:

DDC SHALL ENABLE/DISABLE FAN CIRCUIT AND OPEN/CLOSE HEATING VALVE AS REQUIRED TO MAINTAIN SPACE TEMP SETPOINT OF 68°F DURING BLDG OCCUPANCY AND 55 °F DURING BLDG UNOCCUPANCY. FAN SHALL ACTIVATE UPON PROOF OF HWHR FLOW BY AQ.



HWH UH & CUH WIRING



KITCHEN EXHAUST HOODS (EF-9H & EF-10H) AND MAKE-UP AIR UNIT (AHU-22H) CONTROL

NOTES: COORDINATE WIRING WITH EQUIPMENT SUPPLIERS.

AIR TERMINAL UNIT WITH PERIMETER HEATING - DISH WASH AREA:

SEQUENCE OF OPERATION

AHU-22H/EF-9H/EF-10H SHALL BE CAPABLE OF BEING CONTROLLED INDIVIDUALLY.

EF-9H AND EF-10H SHALL BE STARTED AND STOPPED MANUALLY BY ITS ON/OFF

WITH THE SUPPLY FAN VFC HAND/OFF/AUTO SWITCH AND EXHAUST MOTOR STARTER

INTERLOCKED WITH THE KITCHEN HOOD EXHAUST FANS. WHENEVER THE KITCHEN HOOD

HAND/OFF/AUTO SWITCH(S) IN THE "AUTO" POSITION, THE SUPPLY FAN SHALL BE

EXHAUST FAN IS ENERGIZED, THE MAKE UP AIR UNIT SHALL BE ENERGIZED. WHENEVER THE KITCHEN HOOD EXHAUST FAN IS DE-ENERGIZED, THE MAKE UP AIR

WHEN THE CONTROL CIRCUIT OF THE SUPPLY FAN IS ENERGIZED TO START, ITS

THE DDC SYSTEM BY MEANS OF THE FAN MOTOR CURRENT SWITCH.

SPACE TEMPERATURE SET POINT OF 68 DEGREES F (ADJUSTABLE).

8. THE FILTER DIFFERENTIAL PRESSURE SWITCH SHALL ISSUE A DIRTY FILTER

9. IF THE LOW LIMIT SET POINT (40 DEGREES F ADJUSTABLE) OF THE DISCHARGE AIR SENSOR IS REACHED FOR MORE THAT 1 MINUTE (ADJUSTABLE) THROUGH DDC, THE

10. WHEN THE SUPPLY FAN IS DE-ENERGIZED, THE OUTSIDE AIR DAMPER (D-1) SHALL

WHEN FIRE SUPPRESSION SYSTEM IS ACTIVATED, THE MAU SUPPLY FAN WILL BE

REGARDLESS OF LOCAL CONTROL SWITCH POSITION. THIS CONDITION WILL ACTIVATE A

REGARDLESS OF LOCAL CONTROL SWITCH POSITION, IF HEAT IS DETECTED UNDER THE

DE-ACTIVATED AND THE KITCHEN HOOD EXHAUST FAN SHALL BE ACTIVATED

12. KITCHEN HOOD EXHAUST FAN MAY ALSO BE ACTIVATED BY HI-LIMIT THERMOSTAT

SUPPLY AND EXHAUST FAN SHALL BE DE_ENERGIZED AND AN ALARM SHALL BE SENT

OUTSIDE AIR DAMPER SHALL FULLY OPEN FIRST. AFTER THE DAMPER IS FULLY OPEN, THE OUTSIDE AIR DAMPER LIMIT SWITCH SHALL COMPLETE THE CONTROL CIRCUITS TO

PROOF OF FLOW STATUS FOR THE SUPPLY FAN AND EXHAUST SHALL BE PROVEN TO

THE SUPPLY FAN VARIABLE FREQUENCY CONTROLLER SHALL BE MODULATED BASED

THE DISCHARGE AIR TEMPERATURE SENSOR THROUGH DDC SHALL MODULATE THE UNITS HOT WATER HEATING (GLYCOL) COIL CONTROL VALVE TO MAINTAIN DISCHARGE

AIR TEMPERATURE SET POINT. THE DISCHARGE AIR SET POINT SHALL BE RESET BY THE SPACE TEMPERATURE BETWEEN 55 DEGREES F AND 95 DEGREES F TO MAINTAIN

ASSOCIATED KITCHEN HOOD EXHAUST FAN OPERATION. WHEN AN ASSOCIATED KITCHEN HOOD EXHAUST FAN IS ENERGIZED AS SENSED BY DDC THRU THE FAN MOTOR CURRENT SWITCH THE SUPPLY FAN VFC SHALL BE MODULATED TO THE EF CFM RATE.

KITCHEN EXHAUST HOOD AND MAKE-UP AIR UNIT CONTROL):

SWITCH LOCATED NEAR THE KITCHEN EXHAUST HOOD.

UNIT SHALL BE DE-ENERGIZED.

ALARM IF IT'S SET POINT IS REACHED.

THROUGH THE DDC SYSTEM.

DDC SYSTEM ALARM.

START THE SUPPLY FAN.

NOTE: ALL SETPOINTS DESCRIBED IN SEQUENCE SHALL BE ADJUSTABLE BY SYSTEM OPERATORS (CREATE REQUIRED VIRTUAL POINTS). APPROPRIATE DEADBANDS SHALL BE USED TO PREVENT SHORT CYCLING SITUATIONS.

1. ALL TU'S ASSOCIATED WITH A SINGLE SPACE TEMP SENSOR SHALL CONTROL IN

2. SUPPLY AIR TERMINAL UNIT'S (TU) VAV MINIMUM AND MAXIMUM AIRFLOW SETTINGS SHALL BE AS INDICATED ON THE MECHANICAL SCHEDULES. WHERE MINIMUM AND MAXIMUM AIRFLOW SETTINGS ARE THE SAME, THE TU CONTROLLER

3. IN ALL MODES OF HEATING, TU DISCHARGE AIR TEMP SENSOR SHALL PROVIDE

HIGH LIMIT SETPOINT CONTROL AT 90°F DAT. 4. WHEN ROOM TEMPERATURE RISES ABOVE THE SETPOINT, THE SUPPLY AIR TERMINAL UNIT CONTROLLER SHALL KEEP THE TEMPERING COIL VALVE AND PERIMETER HEATING CONTROL VALVE CLOSED AND SHALL MODULATE THE SUPPLY AIRFLOW BETWEEN ITS MINIMUM AND MAXIMUM SETTING TO MAINTAIN

5. WHEN OA TEMP IS 60 DEG F OR BELOW AND ROOM TEMPERATURE FALLS BELOW SETPOINT, THE SUPPLY TERMINAL UNIT CONTROLLER SHALL KEEP THE SUPPLY AIRFLOW AT ITS MINIMUM SETTING AND SHALL FIRST MODULATE THE PERIMETER HEATING CONTROL VALVE FOLLOWED BY TEMPERING COIL CONTROL

6. WHEN OA TEMP IS ABOVE 60 DEG F AND ROOM TEMPERATURE FALLS BELOW SETPOINT, THE SUPPLY TERMINAL UNIT CONTROLLER SHALL KEEP THE SUPPLY AIRFLOW AT ITS MINIMUM SETTING AND SHALL MODULATE THE TEMPERING COIL CONTROL VALVE TO MAINTAIN THE ROOM TEMPERATURE SETPOINT. PERIMETER

UNITS AIR FLOW SHALL INCREASE TO MAKE UP EXHAUST AIR 100 CFM LESS

8. THE SUPPLY AIR TERMINAL UNIT'S MINIMUM AND MAXIMUM VOLUME AIRFLOW

9. WHEN SPACE CARBON DIOXIDE LEVEL RISES ABOVE 1100 PPM SETPOINT, THE SUPPLY AIR TU CONTROLLER SHALL OVERRIDE TEMPERATURE CONTROL AND MODULATE DAMPER OPEN TO INCREASE SUPPLY AIRFLOW UNTIL CO2 SETPOINT IS SATISFIED. THE TEMPERING COIL VALVE SHALL BE MODULATED TO MAINTAIN SPACE TEMP SETPOINT. [NOTE: THERE IS NOT A REQUIREMENT TO INCREASE OUTSIDE AIRFLOW AT RELATED RTU IF CO2 LEVEL IS ABOVE SETPOINT WHEN TU DAMPER IS AT MAX POSITION].

BEING IN VENTILATION OVERRIDE MODE, THE TU DAMPER SHALL BE MODULATED CLOSED TOWARDS MINIMUM POSITION. THE TEMPERING COIL VALVE SHALL BE MODULATED TO MAINTAIN SPACE TEMP SETPOINT.

> HEATING UNOCCUPIED SETPOINT = 62°F HEATING TEMPORARY UNOCCUPIED SETPOINT = 68°F HEATING OCCUPIED SETPOINT = 70°F


COOLING TEMPORARY UNOCCUPIED SETPOINT = 77°F COOLING UNOCCUPIED SETPOINT = 80°F

12. DURING BUILDING UNOCCUPANCY, RELATED AHU (RTU OR ERU) SHALL CYCLE AS REQUIRED TO MAINTAIN BUILDING SETBACK AND SETUP TEMP SETPOINTS.

14. THE DDC TERMINAL UNIT CONTROLLER SHALL RE-CALIBRATE THE AIRFLOW SENSOR ONCE A WEEK MINIMUM. THE RE-CALIBRATION PROCESS SHALL BE STAGGERED AMONGST THE TERMINAL UNITS SO THE DUCT STATIC PRESSURE DOES NOT EXCEED LIMITS.


CONTROL OUTPUT(S) SHALL BE DISPLAYED WITH SYSTEM GRAPHICS.

REFER TO SHEET M801 FOR T.C. (TEMPERATURE CONTROL) GENERAL NOTES.



DISHWASH AREA TERMINAL UNIT CONTROL WITH PERIMETER HEAT CONTROL DIAGRAM

1. REFER TO SHEET METAL PLANS FOR LOCATIONS AND QUANTITY OF UNITS. REFER TO HVAC PIPING PLANS FOR LOCATIONS OF ROOM TEMP SENSORS.





SHALL PERFORM CONSTANT AIR VOLUME CONTROL.

ROOM TEMPERATURE.

VALVE (WHEN PERIMETER HEATING CONTROL VALVE IS FULL OPEN) TO MAINTAIN THE ROOM TEMPERATURE SETPOINT.

HEATING CONTROL VALVE SHALL REMAIN CLOSED. 7. WHENEVER THE DISH WASH EXHAUST FAN IS ENERGIZED THE VAV TERMINAL

THE EXHAST AIR FLOW (ADJUSTABLE).

SETTINGS SHALL BE AS INDICATED ON THE SHEET METAL FLOOR PLANS

10. WHEN SPACE CARBON DIOXIDE LEVEL FALLS BELOW 800 PPM SETPOINT AFTER

11. SPACE TEMPERATURE SETPOINTS SHALL BE AS FOLLOWS:

COOLING OCCUPIED SETPOINT = 75°F

13. WHEN RESPECTIVE AHU (RTU OR ERU) IS DEACTIVATED; THE AIR TERMINAL UNIT DAMPER SHALL REMAIN IN MINIMUM POSITION AND THE TEMPERING COIL VALVE SHALL REMAIN CLOSED. THE PERIMETER HEATING VALVE SHALL BE MODULATED TO MAINTAIN HEATING UNOCCUPIED SETPOINT.

15. CONTROL SIGNALS FOR AIR TERMINAL UNIT DAMPER ACTUATOR AND HEATING

CONSULTING ENGINEERS

Peter Basso Associates In

PBA Project No.: 2021-0402

SHEET NUMBER ROJECT NUMBER 5145 Livernois, Suite 100 PROJECT DATE Troy, Michigan 48098-3276 AUGUST 23, 2023 Tel: 248-879-5666 Fax: 248-879-0007

WEK

CHECKED BY www.PeterBassoAssociates.com

STATE REVIEW SET

REVISION

DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET

CONTRACT NO.

WTAARCH.COM

COPYRIGHT © 2023

Y22003

WTA A RCHITECTS

FACILITIES AND BUSINESS SERVICES ADMINISTRATION

DESIGN AND CONSTRUCTION DIVISION

STATE OF MICHIGAN

FILE NO.

491/20167.SDW

171CODHHS7255

100 S Jefferson Ave, Suite 601

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC

PSYCHIATRY - CREATE

TEMPERATURE CONTROLS

Saginaw, Michigan 48607

989 752 8107

PROJECT TITLE

KITCHEN

SALINE, MICHIGAN

FUNDING CODE

ADAM LACH, RA, DIRECTOR

12/20/23

DATE

3. TC CONTRACTOR SHALL PROVIDE BOILER EMERGENCY AND DOMESTIC HW NATURAL GAS SHUTDOWN COMPONENTS AND WIRING. REFER TO REMOTE

BOILER SHUTDOWN WIRING DIAGRAM.

SEQUENCE OF OPERATION PENTHOUSE HOT WATER HEATING SYSTEM: NOTE: ALL SETPOINTS, RESET SCHEDULE SETPOINTS, DEADBANDS, AND TIME INTERVALS DESCRIBED IN SEQUENCE SHALL BE ADJUSTABLE BY SYSTEM OPERATORS (CREATE REQUIRED VIRTUAL POINTS). ALL MOTOR CONTROL SWITCHES SHALL BE IN "AUTO" HOT WATER HEATING SYSTEM SHALL BE ACTIVATED BY BOILER SEQUENCING PANEL WHEN OUTDOOR AIR TEMPERATURE IS BELOW 55°F. 2. THE BOILER SEQUENCING PANEL SHALL ACTIVATE OR DEACTIVATE BOILERS AND

FROM AHU HEATING COILS

- LOW SYSTEM PRESSURE ALARM

SWITCH SET @ 5 PSIG BELOW

SYSTEM LVL DI LOW TANK RESERVE ALARM (NOTE 3

(TYPICAL) (NOTE 2)

PUMP START PRESSURE SWITCH

— HWHS → S TO AHU HEATING COILS

HWHS TEMP

RESET SCHEDULE

HOT WATER SUPPLY

TEMPERATURE

100°F

OUTSIDE

AIR TEMP.

≤ 0°F

≥ 55°F

HWH WATER SYSTEM GLYCOL FILL PUMP START PRESSURE SWITCH

GLYCOL FILL PUMP -

GLYCOL FILL STATION SERVES HWH SYSTEM

PROVIDED WITH GLYCOL FILL STATION.

WITH GLYCOL FILL STATION.

GLYCOL FILL STATION MONITORING

1. PUMP CONTROL PRESSURE SWITCH AND ASSOCIATED CONTROL WIRING ARE

2. PRESSURE SWITCH FOR ALARM MONITORING SHALL BE FURNISHED BY TC CONTRACTOR AND INSTALLED BY MECHANICAL CONTRACTOR.

3. DRY CONTACTS FOR REMOTE MONITORING OF LOW TANK RESERVE ALARM PROVIDED

SET @ 21 PSIG (NOTE 1)


- CONTROL BOILER MODULATION AS REQUIRED TO MAINTAIN HWH SUPPLY TEMP (T-1) SETPOINT BASED ON OUTSIDE AIR RESET SCHEDULE. 3. THE BOILER SEQUENCING PANEL SHALL INCLUDE OPERATOR SELECTABLE BOILER
- LEAD/LAG OPERATION OR FIRST ON/FIRST OFF OPERATION. 4. WHENEVER A BOILER CIRCUIT IS ACTIVATED, ITS ASSOCIATED PRIMARY CIRC PUMP
- SHALL BE ACTIVATED BY FACTORY WIRED PUMP RELAY.
- WHENEVER A BOILER IS DEACTIVATED, ITS ASSOCIATED PRIMARY CIRC PUMP SHALL CONTINUE TO RUN BASED ON BOILER CONTROLLER TIME DELAY RELAY TO DISSIPATE HEAT FROM THE DEACTIVATED BOILER.
- 6. IF REMOTE CONTROL IS LOST, LOCAL BURNER MODULATING CONTROL AT EACH BOILER SHALL BE SET TO MAINTAIN 130°F LEAVING WATER TEMPERATURE.
- 7. EACH BOILER SAFETY CONTROLS SHALL INCLUDE AN AUTO-RESET HI-LIMIT (BOILER OPERATOR) WITH SETPOINT OF 195°F AND A MANUAL-RESET HI-LIMIT WITH SETPOINT OF 215°F.
- 8. DDC SYSTEM SHALL MONITOR SYSTEM TEMPERATURE T-2 THRU T-3 FOR SYSTEM
- 9. WHEN ONE OF THE REMOTE BOILER SYSTEM SHUTDOWN SWITCHES IS PUSHED, BURNER CONTROLS FOR ALL BOILERS SHALL BE DE-ENERGIZED THRU HARDWIRE INTERLOCK. DDC SHALL MONITOR SWITCH CIRCUIT AND ACTIVATE LOCAL ALARM INDICATION LIGHT WHEN REMOTE BOILER SYSTEM SHUTDOWN CONDITION OCCURS.

208V/120V XFMR

TYPICAL BOILER CP M/S WIRING

INTERLOCKED TO RESPECTIVE BOILER

BOILER CONTROL PANEL S/S




REMOTE BOILER EMERGENCY SHUTDOWN WIRING

SEQUENCE OF OPERATION

SEQUENCE OF OPERATION:

- 1. UNDER NORMAL OPERATING CONDITIONS THE CIRCUIT SHALL BE ENERGIZED AND THE CUT-OUT RELAYS' NORMALLY OPEN (NO) CONTACTS SHALL BE CLOSED TO ENERGIZE BOILER CONTROL CIRCUITS AND OPEN THE DOMESTIC HW SYSTEMS NATURAL GAS SOLENOID VALVES. WHEN A SWITCH IS PUSHED (LATCHED) THE CUT-OUT RELAY CONTACTS SHALL INTERRUPT BOILERS' CONTROL CIRCUITS AND CLOSE THE DOMESTIC HW SYSTEM SOLENOID VALVE. THE SWITCH MUST BE MANUALLY RELEASED TO ALLOW
- 2. DDC SHALL ACTIVATE EMERGENCY SHUTDOWN ALARM IN DDC SYSTEM WHEN A REMOTE SWITCH HAS BEEN PUSHED.




OA SENSOR INSTALLATION DETAIL

NO SCALE

- TC CONTRACTOR HAS THE OPTION OF USING EXISTING OA TEMP AND HUMIDITY SENSORS AS AVAILABLE FOR BUILDING.
- 2. CALCULATE OA ENTHALPY OR DEW POINT TEMPERATURE AS REQUIRED PER SEQUENCE OF OPERATION REQUIREMENTS.
- 3. BROADCAST OUTSIDE AIR TEMPERATURE, HUMIDITY, AND CALCULATED OA ENTHALPY OR DEWPOINT TEMPERATURE, AS REQUIRED, THROUGH BAS COMMUNICATION NETWORK TO CONTROLLERS REQUIRING INFORMATION FOR DDC PROGRAMMING LOGIC.

- NOTES:









WTAARCH.COM

COPYRIGHT © 2023

SALINE, MICHIGAN TEMPERATURE CONTROLS

| WTA A RCHITECTS |

OWNER REVIEW

REVISION

ADAM LACH, RA, DIRECTOR

DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION

CONTRACT NO.

Y22003

STATE OF MICHIGAN
DEPARTMENT OF TECHNICI OF

FILE NO.

491/20167.SDW

171CODHHS7255

989 752 8107

PROJECT TITLE

KITCHEN

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607

FUNDING CODE

DATE

SHEET NUMBER ROJECT NUMBER PROJECT DATE AUGUST 23, 2023 CHECKED BY WEK

48" A.F.F. TO TOP OF

ENCLOSURE, U.O.N.

ELECTRICAL DRAWING INDEX

SHEET NO.	SHEET TITLE
E0.01	ELECTRICAL STANDARDS AND DRAWING INDEX
E0.02	ELECTRICAL STANDARD SCHEDULES
E0.03	ELECTRICAL DEMOLITION SITE PLAN
E0.04	ELECTRICAL NEW WORK SITE PLAN
ED1.01	FIRST FLOOR ELECTRICAL DEMOLITION PLAN
E2.01	FIRST FLOOR LIGHTING PLAN - UNIT H
E3.00	BASEMENT FLOOR POWER PLAN - UNIT H
E3.01	FIRST FLOOR POWER PLAN - UNIT H
E4.01	FIRST FLOOR AUXILIARY SYSTEMS PLAN - UNIT H
E4.04	ELECTRICAL ROOF PLAN
E5.01	ONE LINE DIAGRAM - NEW WORK
E5.02	PANEL SCHEDULES
E6.01	ELECTRICAL ENLARGED PLAN
E6.02	ELECTRICAL ENLARGED PLAN
E7.00	ELECTRICAL DETAILS AND DIAGRAMS

ELECTRICAL DETAILS AND DIAGRAMS

ELECTRICAL ABBREVIATION LIST

FOOD SERVICE EQUIPMENT CONTRACTOR

GROUND FAULT CIRCUIT INTERRUPTER

GROUND FAULT PROTECTION

HAND-OFF-AUTO HORSEPOWER HIGH VOLTAGE

ISOLATED GROUND

FUSE


FSEC

HEIGHTS WITH

ARCHITECT

ABBREVIATION	DESCRIPTION	ABBREVIATION	DESCRIPTION	ABBREVIATION	DESCRIPTION
A	AMPERES	JB	JUNCTION BOX	Р	POLE
AER	ARC ENERGY REDUCTION			PB	PUSHBUTTON STATION
AF	AMPERES FRAME (BREAKER RATING)	KA	THOUSAND AMP	PH	PHASE
AFCI	ARC FAULT CIRCUIT INTERRUPTER	KV	KILOVOLT	PT	POTENTIAL TRANSFORMER
A.F.F.	ABOVE FINISH FLOOR	KVA	KILOVOLT - AMPERES	PDP	POWER DISTRIBUTION PANEL
AIC	AMPS INTERRUPTING CAPACITY	KW	KILOWATT		
AL	AUDIENCE LEFT	KWH	KILOWATT - HOURS	RECEPT.	RECEPTACLE
ALCR	AUTOMATIC LOAD CONTROL RELAY	IXVVII	NEOWATT TIOONS	RDP	RECEPTACLE DISTRIBUTION PANE
AR	AUDIENCE RIGHT	LA	LIGHTING ARRESTOR	RP	RECEPTACLE PANEL
AT	AMPERES TRIP (BREAKER SETTING)	LP	LIGHTING PANEL	RSC	RIGID STEEL CONDUIT
ATS		LDP	LIGHTING PANEL LIGHTING DISTRIBUTION PANEL	ROU	RIGID STEEL CONDUIT
	AUTOMATIC TRANSFER SWITCH	LDP	LIGHTING DISTRIBUTION PANEL	0000	OLIOPE OIDOLUE OLIPPENE DATINO
AUX	AUXILIARY		*****	SCCR	SHORT CIRCUIT CURRENT RATING
		MAX	MAXIMUM	SCHED	SCHEDULE
BCELTS	BRANCH CIRCUIT EMERGENCY LIGHTING	MCA	MINIMUM CIRCUIT AMPACITY	SPD	SURGE PROTECTION DEVICE
	TRANSFER SWITCH	MCB	MAIN CIRCUIT BREAKER	SW	SWITCH
BKR	BREAKER	MCC	MOTOR CONTROL CENTER	SWBD	SWITCHBOARD
BPS	BOLTED PRESSURE SWITCH	MDP	MAIN DISTRIBUTION PANEL	SWGR	SWITCHGEAR
		MECH	MECHANICAL		
С	CONDUIT	MIN	MINIMUM	TB	TERMINAL BOX
СВ	CIRCUIT BREAKER	MISC.	MISCELLANEOUS	TELECOM	TELECOMMUNICATIONS
CKT	CIRCUIT	MLO	MAIN LUGS ONLY	TR	TAMPER RESISTANT
CT	CURRENT TRANSFORMER	MOP	MAXIMUM OVERCURRENT PROTECTION		TELEPHONE TERMINAL BACKBOAR
O1	CONTRACT TO WELL	MTD	MOUNTED	TYP	TYPICAL
DEMO	DEMOLITION	MTG	MOUNTING	1 11	TITIOAL
DIM	DIMENSION	MTR	MOTOR	U.O.N.	UNLESS OTHERWISE NOTED
DISC		WITK	MOTOR		
	DISCONNECT	N.I.	NEUTDAL	US	UPSTAGE
DP	DISTRIBUTION PANEL	N	NEUTRAL		
DS	DOWNSTAGE	NC	NORMALLY CLOSED	V	VOLTS
DWG	DRAWING	NEC	NATIONAL ELECTRICAL CODE		
		NF	NON-FUSIBLE	W	WIRE OR WATTS
EBU	EMERGENCY BATTERY UNIT	NIC	NOT IN CONTRACT	WG	WIRE GUARD
EC	ELECTRICAL CONTRACTOR	NL	NIGHT LIGHT	WP	WEATHERPROOF
ELEC	ELECTRICAL	NO	NORMALLY OPEN	WR	WEATHER RESISTANT
EM/ EMERG	EMERGENCY	NTS	NOT TO SCALE		
EMT	ELECTRICAL METALLIC TUBING			XFMR	TRANSFORMER
EO	ELECTRICALLY OPERATED	OC	ON CENTER	XP	EXPLOSION PROOF
EPO	EMERGENCY POWER OFF	OFCI	OWNER FURNISHED,		
EWC	ELECTRIC WATER COOLER	0. 0.	CONTRACTOR INSTALLED	(E)	EXISTING
EXIST	EXISTING	OFOI	OWNER FURNISHED,	(E) (R)	RELOCATED
LAIOT	LAIOTINO	OI OI	OWNER FORNISHED, OWNER INSTALLED	(13)	NELOUATED
FA	FIRE ALARM		OWNER INSTALLED		
FA FLA					
	FULL LOAD AMPS	\circ T			
FLR	FLOOR	SIF	ANDARD METHOI	JS (JF ľ	NOTATION
FOH	FRONT OF HOUSE	_			

STANDARD METHODS OF NOTATION



HATCH MARKS INDICATE EQUIPMENT OR MATERIALS


DUCT BANK - CONCRETE ENCASED / DIRECT BURIED

SPARE


TO BE DISCONNECTED AND REMOVED.

CIRCUIT HOMERUN

IN USE







REVISION

DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET

CONTRACT NO.

Y22003

FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION

STATE OF MICHIGAN

FILE NO.

491/20167.SDW

171CODHHS7255

FUNDING CODE

ADAM LACH, RA, DIRECTOR

DATE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

ELECTRICAL STANDARDS AND DRAWING INDEX

PROJECT NUMBER SHEET NUMBER PROJECT DATE E0.01 SEPTEMBER 6, 2023 CHECKED BY TLC

STANDARD MOUNTING HEIGHTS PARTITION T

18" A.F.F. TO CENTER OF BOX, U.O.N.

♦T⊗₁**-**▶ 6" A.F.F. HORIZONTALLY

TO TOP OF BOX, U.O.N.

DRY TY	PE DISTRIB	UTION TRAI	NSFORM	IER CIR	CUIT SIZIN	IG SCHEE	DULE
	PRIMARY (480V)		SECON	IDARY (208Y/120	O VOLT)		
			CONDU	CTOR SIZE (AW	G OR KCMIL)	GROUNDING ELECTRODE CONDUCTOR	
				SUPPLY SIDE			
TRANSFORMER	OVERCURRENT	OVERCURRENT	PHASE & NEUTRAL	BONDING JUMPER	CONDUIT (4W + SSBJ)		KEYED
KVA	PROTECTION	PROTECTION	COPPER	COPPER	COPPER	COPPER	NOTES
9	20A	30A	10	8	3/4"	8	
15	25A	60A	6	8	1"	8	1
30	45A	100A	3	8	1 1/4"	8	1
45	70A	175A	2/0	4	2"	4	
75	125A	300A/225A	350 / 4/0	2	3"	2	2
112 1/2	175A	400A	600	1/0	3 1/2"	1/0	
150	225A	600A	2-350	2-2	2-3"	2/0	
225	350A	800A	2-600	2-1/0	2-3 1/2"	3/0	
300	500A	1200A	3-600	3-1/0	3-3 1/2"	3/0	
500	800A	1600A	4-600	4-1/0	4-3 1/2"	3/0	

- GENERAL NOTES:

 1. TRANSFORMERS AND FEEDERS ARE BASED ON 480 VOLT, 3 PHASE, 3 WIRE PRIMARY AND 208Y/120 VOLT, 3 PHASE, 4 WIRE,
- ALUMINUM CONDUCTORS ARE PERMITTED ONLY IF INCLUDED IN FEEDER AND BRANCH CIRCUIT SIZING SCHEDULE. PRIMARY OVERCURRENT PROTECTION IS SIZED AT 125% OF TRANSFORMER FULL LOAD CURRENT. PROVIDE PRIMARY
- OVERCURRENT DEVICE SELECTION TO ALLOW TRANSFORMER IN-RUSH CURRENT AND PROTECT BASED ON THE ANSI DAMAGE CURVE. IF MANUFACTURER REQUIRES PRIMARY OVERCURRENT GREATER THAN 125% (NOT TO EXCEED 250%) THEN PRIMARY FEEDER SHALL BE INCREASED ACCORDINGLY.
- 4. SECONDARY CONDUCTOR BASED ON TEN FOOT MAXIMUM LENGTH (NEC 240.21(C)(2)). IF CONDUCTORS ARE LONGER THAN TEN FOOT, REQUIREMENTS IN NEC 240.21(C)(6) MUST BE MET. IN NO CASE SHALL CONDUCTORS BE LONGER THAN TWENTY-FIVE FEET.

KEYED NOTES:

1. CONDUCTORS ARE BASED ON 90°C, 600V. INSULATED WIRE APPLIED AT 75°C FOR TERMINATION RATED 60/75°C OR 75°C. 2. THE SMALLER SIZE IS TO BE USED TO FEED 225A PANELBOARDS.

BRANCH CIRC	CUIT VOL	TAGE DROP	WIRING SCH	EDULE FOR S	SINGLE PHASE	CIRCUITS
	WIRE SIZE		MAXIMUN	M BRANCH CIRCUIT LENGT	ΓΗ (IN FEET)	
BRANCH CIRCUIT RATING (A)	(AWG)	120V	208V	240V	277V	480V
20A	12	83	143	165	191	331
20A	10	128	222	256	295	511
20A	8	201	348	402	464	804
20A	6	313	542	625	721	1250
30A	10	85	148	170	197	341
30A	8	134	232	268	309	536
30A	6	208	361	417	481	833
30A	4	313	542	625	721	1250

- GENERAL NOTES:

 1. THE ABOVE TABLE VALUES ARE BASED ON COPPER CONDUCTORS, IN STEEL CONDUIT, WITH A LOAD POWER FACTOR OF 0.85 PER NEC CHAPTER 9, TABLE 9.
- PROVIDE BRANCH CIRCUIT CONDUCTORS AS INDICATED IN THE TABLE ABOVE FOR ALL LIGHTING AND RECEPTACLE BRANCH CIRCUITS. WHERE BRANCH CIRCUITS SERVE DEDICATED EQUIPMENT, THE CONTRACTOR MAY PERFORM VOLTAGE DROP CALCULATIONS BASED ON ACTUAL EQUIPMENT CONNECTED LOAD AND PROVIDE CONDUCTORS
- APPROPRIATELY SIZED TO LIMIT VOLTAGE DROP TO A MAXIMUM OF 3%. CONDUCTOR SIZES ARE BASED ON MAXIMUM OF 9 CURRENT CARRYING CONDUCTORS IN A SINGLE CONDUIT.
- LIMITS FOR CONDUCTOR LENGTHS SHOWN ARE BASED ON A MAXIMUM BRANCH CIRCUIT LOADING OF 64% OF THE BRANCH BREAKER RATING AND A MAXIMUM OF 3 PERCENT VOLTAGE DROP TO COMPLY WITH ASHRAE 90.1 AND THE NEC. FOR CIRCUITS LOADED GREATER THAN 64% OF BRANCH BREAKER RATING, THE CONTRACTOR SHALL PROVIDE CONDUCTORS APPROPRIATELY SIZED TO LIMIT VOLTAGE DROP TO 3%.

MOTO	OR CIRCUIT	SIZING SCHE	EDULE (480V, 3	PHASE)
			STARTER	MOTOR DISCONNECT
MOTOR HP	SWITCH/FUSE	CIRCUIT BREAKER	SIZE/TYPE	(NOTE 3)
1/2	30/3A	15A	1	30A
3/4	30/3A	15A	1	30A
1	30/6A	15A	1	30A
1 1/2	30/6A	15A	1	30A
2	30/6A	15A	1	30A
3	30/10A	15A	1	30A
5	30/15A	15A	1	30A
7 1/2	30/20A	20A	1	30A
10	30/20A	25A	1	30A
15	30/30A	40A	2	30A
20	60/40A	60A	2	60A
25	60/50A	70A	2	60A
30	60/60A	80A	3	60A
40	100/80A	90A	3	100A
50	100/100A	100A	3	100A
60	200/125A	125A	4	200A
75	200/150A	150A	4	200A
100	200/200A	200A	4	200A
125	200/200A	225A	5	200A
150	400/250A	250A	5	400A
200	400/350A	350A	5	400A

- GENERAL NOTES:

 1. BASED ON MOTOR FULL LOAD AMPERES AS PROVIDED BY THE N.E.C. BASED ON MOTOR RUNNING OVERLOAD PROTECTIONS PROVIDED BY
- THERMAL OVERLOAD RELAYS. 3. WHERE THE STARTER IS LOCATED REMOTE FROM THE MOTOR, PROVIDE DISCONNECT LOCATED AT THE MOTOR, SIZE AS INDICATED.

	SPECIAL RECEPTACLES
TYPE	DESCRIPTION
Type 4	250V, 20A, THREE PHASE, LOCKING RECEPTACLE, 3 POLE, 4 WIRE (NEMA L15-20R)
Type 8	125/250V SINGLE PHASE RECEPTACLE, 3 POLE, 4 WIRE (NEMA 14-20R)

	WI	RE	Γ		CEW		CH	CAE	
	V V I			1 1/7				MC)	
	COPPER, TYPE THHN/THWN-2	СОРРЕR, ТҮРЕ ХННW-2	ELECTRICAL METALLIC TUBING (EMT)	RIGID STEEL CONDUIT (RSC)	HIGH DENSITY POLYETHYLENE (HDPE) SCHEDULE 40	FLEXIBLE METAL CONDUIT (FMC)	LIQUID TIGHT FLEXIBLE METAL CONDUIT (LFMC)	METAL CLAD TYPE CABLE WITH INSULATED GROUND WIRE (TYPE	TWO HOLIR RATED MC POWER CARLE (KEVED NOTE 3)
FEEDERS - INTERIOR	8	8	ᆸ	N N		<u> </u>		M	É
CONCEALED, ACCESSIBLE CEILINGS	Х	Ι	Х		I	1	I	l	1
CONCEALED, INACCESSIBLE CEILINGS CONCEALED, INACCESSIBLE CEILINGS	X		X						
CONCEALED IN GYPSUM BOARD PARTITION WALLS	X		X						
EXPOSED, BELOW 10' AFF AND SUBJECT TO DAMAGE	X			Х					
EXPOSED, BELOW 10' AFF AND NOT SUBJECT TO DAMAGE	X		Х						
EXPOSED, ABOVE 10' AFF UNFINISHED SPACES	Х		Х						
EXPOSED, FINISHED SPACES	Х								
BELOW SLAB ON GRADE	Х			Х					
DAMP AND WET LOCATIONS	Х			Χ					
BRANCH CIRCUITS - EXTERIOR									
EXPOSED, SURFACE MOUNTED TO STRUCTURE		Х		Х					
EXPOSED, WITH FREESTANDING SUPPORT		Х		Χ					
CONCEALED IN RETAINING WALL OR SIMILAR ELEMENT		Х		Χ					
BELOW PARKING LOTS AND ROADWAYS		Х		Χ	Х				
BELOW GREEN SPACE		Х							
WITHIN 5' OF FOUNDATION WALL		Х		Х					
ROOFTOPS (WHEN APPROVED BY ENGINEER)		Х		Х					
BRANCH CIRCUITS - INTERIOR									
CONCEALED, ACCESSIBLE CEILINGS	X		X					Х	\perp
CONCEALED, INACCESSIBLE CEILINGS	X		Х		-	ļ.,			
CONCEALED IN GYPSUM BOARD PARTITION WALLS	X		X			Х		Х	
CONCEALED IN CMU WALLS	X		Х	\ <u>\</u>	-		-		┝
EXPOSED, BELOW 10' AFF AND NOT SUBJECT TO DAMAGE	X		Х	Х					
EXPOSED, BELOW 10' AFF AND NOT SUBJECT TO DAMAGE EXPOSED, ABOVE 10' AFF UNFINISHED SPACES	X		X						
EXPOSED, FINISHED SPACES	X								
BELOW SLAB ON GRADE	X								
EMBEDDED IN ELEVATED CONCRETE SLAB	X								
DAMP AND WET LOCATIONS	X			Х			Х		
SPECIAL APPLICATIONS									
CONNECTION BETWEEN VFC AND MOTORS (KEYED NOTE 1)		l					T		Π
CLASS 1 CONTROL CIRCUITS	X		Х	Х					\vdash
CLASS 2 CONTROL CIRCUITS	X		X	X					\vdash
CLASS 2 CONTROL CIRCUITS		\vdash	X	X					T
CLASS 3 CONTROL CIRCUITS	X	l	_ ^					_	
	X	Х	X	X	Х				X

TRANSITION FROM PVC/HDPE AND PROVIDE RIGID STEEL OR RTRC SWEEPS WHERE CONDUITS PENETRATE

- WALLS, CONCRETE SLABS, CONCRETE BASES, AND ASPHALT. REFER TO SPECIFICATIONS FOR RESTRICTIONS ON MC/AC CABLE INSTALLATION.
- EMT SHALL NOT BE USED ON THE EXTERIOR OF A BUILDING OR IN AREAS SUBJECT TO DAMAGE BELOW 10' AFF. 4. INSTALL SURFACE RACEWAYS ONLY WHERE SHOWN ON DRAWINGS.
- KEYED NOTES:
 1. NON-ARMORED CABLE SHALL BE INSTALLED IN RACEWAY. ARMORED CABLE SHALL BE INSTALLED IN TRAY OR FREE-AIR AS APPLICABLE.
- EMERGENCY FEEDERS IN OCCUPANCIES THAT ARE UNDER 700.10(D) SHALL HAVE A TWO HOUR RATING. RATING SHALL BE OBTAINED BY ROUTING CONDUIT AND BUILDING WIRE IN SPRINKLERED SPACE, IN A TWO HOUR SHAFT, OUTSIDE OF THE BUILDING, IN A LISTED TWO HOUR RATED RACEWAY, OR UNDER A MINIMUM OF 2" OF
- CONCRETE; OR BY USING A LISTED TWO-HOUR RATED CABLE ASSEMBLY. 3. SHALL BE INSTALLED PER MANUFACTURER'S INSTRUCTIONS BASED ON UL TESTING AND RATING.

FEEDER A	ND BR	ANCH (CIRCUIT SIZ	ING SCHE	DULE - GE	NERAL PU	RPOSE
			COP	PER CONDUCTORS			
		E SIZE R KCMIL)		CONDUI	T SIZE		
OVERCURRENT DEVICE RATING (AMPERES)	PHASE & NEUTRAL	GROUND	SINGLE PHASE 2 WIRE+G (1PH, 1N, 1G)	SINGLE PHASE 3 WIRE+G (2PH, 1N, 1G)	THREE PHASE 3 WIRE+G (3PH, 1G)	THREE PHASE & NEUTRAL 4 WIRE+G (3PH, 1N, 1G)	KEYED NOTES
15-20	12	12	3/4"	3/4"	3/4"	3/4"	
25-30	10	10	3/4"	3/4"	3/4"	3/4"	
35-40	8	10	3/4"	3/4"	3/4"	3/4"	
45-50	8 (6)	10	3/4"	3/4"	3/4"	3/4"	1
60	6 (4)	10	3/4" (1")	3/4" (1")	3/4" (1")	1" (1 1/4")	1
70	4	8	1"	1 1/4"	1 1/4"	1 1/4"	
80	4 (3)	8	1"	1 1/4"	1 1/4"	1 1/4"	1
90-100	3 (2)	8	1 1/4"	1 1/4"	1 1/4"	1 1/4"	1
110	2 (1)	6	-	1 1/4"	1 1/4"	1 1/4" (1 1/2")	1
125	1 (1/0)	6	-	1 1/4" (1 1/2")	1 1/4" (1 1/2")	1 1/2"	1
150	1/0	6	-	1 1/2"	1 1/2"	1 1/2"	
175	2/0	6	-	2"	2"	2"	
200	3/0	6	-	2"	2"	2 1/2"	
225	4/0	4	-	2"	2"	2 1/2"	
250	250	4	-	2 1/2"	2 1/2"	2 1/2"	
300	350	4	-	2 1/2"	2 1/2"	3"	
350	500	3	-	3"	3"	3"	
400	500	3	-	3"	3"	3"	
450	2-4/0	2-2	-	2-2"	2-2"	2-2 1/2"	
500	2-250	2-2	-	2-2 1/2"	2-2 1/2"	2-2 1/2"	
600	2-350	2-1	-	2-2 1/2"	2-2 1/2"	2-3"	
700	2-500	2-1/0	-	2-3"	2-3"	2-3"	
800	2-500	2-1/0	-	2-3"	2-3"	2-3 1/2"	
1000	3-400	3-2/0	-	3-3"	3-3"	3-3"	
1200	3-600	3-3/0	-	3-3 1/2"	3-3 1/2"	3-3 1/2"	
1600	4-600	4-4/0	-	4-3 1/2"	4-3 1/2"	4-3 1/2"	
2000	5-600	5-250	-	5-3 1/2"	5-3 1/2"	5-3 1/2"	

9. N/A = NOT ACCEPTABLE


- GENERAL NOTES:

 1. CONTRACTOR TO SIZE FEEDERS AND BRANCH CIRCUITS BASED ON THIS SCHEDULE AND OVER CURRENT DEVICE SIZE, UNLESS CONTRACTOR MAY COMBINE 20A CIRCUITS AS NOTED IN SPECIFICATION.
- CONDUCTORS ARE BASED ON THHN/THWN UP TO AND INCLUDING #4/0. LARGER THAN #4/0 ARE BASED ON TYPE XHHW. CONDUIT SIZES ARE VALID FOR EMT OR RGS. CONDUIT SIZES SHALL BE ADJUSTED AS REQUIRED FOR OTHER TYPES OF
- ELECTRICAL CONTRACTOR TO COORDINATE WITH MECHANICAL CONTRACTOR AND PROVIDE REQUIRED WIRE SIZES TO ACCOMMODATE MECHANICAL EQUIPMENT LUG SIZES.
- SIZE OF DISCONNECT SWITCH LOCATED AT EQUIPMENT SHALL BE SIZED BASED UPON OVERCURRENT PROTECTION OF THAT OBTAIN APPROVAL FROM ENGINEER PRIOR TO INSTALLING DIFFERENT SIZE/QUANTITY OF CONDUCTORS TO OBTAIN AN
- EQUIVALENT AMPACITY. 8. SPLICE FROM ALUMINUM TO COPPER PRIOR TO ENTERING EQUIPMENT LISTED FOR USE WITH COPPER CONDUCTORS ONLY OR
- USE COPPER CONDUCTORS FOR THE ENTIRE LENGTH OF FEEDER.

KEYED NOTES:
1. CONDUCTORS ARE BASED ON 90°C, 600V. INSULATED WIRE APPLIED AT 75°C FOR TERMINATION RATED 60/75°C OR 75°C. FOR TERMINATION RATED AT 60°C, USE CONDUCTORS AND CONDUIT SIZES INDICATED IN PARENTHESES.







STATE OF MICHIGAN
DEPARTMENT OF TECHNOLO DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE CONTRACT NO. 171CODHHS7255 Y22003



COPYRIGHT © 2023

WTAARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN


ELECTRICAL STANDARD SCHEDULES

SHEET NUMBER PROJECT NUMBER PROJECT DATE SEPTEMBER 6, 2023 CHECKED BY

TLC

E0.02

NOTE: SOME SYMBOLS AND ABBREVIATIONS SHOWN MAY NOT APPLY TO THIS PROJECT





subject to field inspection and the

conditions of approval.

Peter Basso Associates Inc CONSULTING ENGINEERS

SITE PLAN 5145 Livernois, Suite 100 Troy, Michigan 48098-3276 Tel: 248-879-5666 Fax: 248-879-0007 PROJECT DATE

PROJECT NUMBER SHEET NUMBER E0.03 AUGUST 23, 2023 CHECKED BY TLC

OWNER REVIEW

REVISION

ADAM LACH, RA, DIRECTOR

DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION

CONTRACT NO.


WTAARCH.COM

COPYRIGHT © 2023

Y22003

DESIGN AND CONSTRUCTION DIVISION

DATE



OWNER REVIEW DATE REVISION

ADAM LACH, RA, DIRECTOR

491/20167.SDW

171CODHHS7255

CONTRACT NO. Y22003

WTAARCH.COM

WTA A RCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

ELECTRICAL NEW WORK SITE PLAN

PROJECT NUMBER SHEET NUMBER PROJECT DATE E0.04 AUGUST 23, 2023 CHECKED BY TLC

5145 Livernois, Suite 100 Troy, Michigan 48098-3276 Tel: 248-879-5666 Fax: 248-879-0007 www.PeterBassoAssociates.com PBA Project No.: 2021-0402

ELECTRICAL DEMOLITION GENERAL NOTES:

INCLUDE, BUT NOT BE LIMITED TO, THOSE COMPONENTS SHOWN.


DEMOLITION WORK

VISIT THE SITE PRIOR TO SUBMISSION OF BID TO EXAMINE THE EXISTING CONDITIONS AND THE EXTENT OF DEMOLITION WORK.

- EXAMINE THE DRAWINGS OF OTHER TRADES AND BE FAMILIAR WITH THE DEMOLITION REQUIRED BY OTHER TRADES. PERFORM ALL INCIDENTAL ELECTRICAL DEMOLITION AND/OR RELOCATION REQUIRED TO FACILITATE THE DEMOLITION WORK OF OTHER TRADES, WHETHER OR NOT SPECIFICALLY INDICATED.
- REMOVE EQUIPMENT OR MATERIALS AS INDICATED ON PLAN WITH CROSS HATCHING. DEMOLITION SHALL
- COORDINATE WITH NEW WORK PLANS, ONE LINE DIAGRAMS AND RISER DIAGRAMS FOR EXTENT OF
- PROVIDE PROPER SUPPORT FOR EXISTING TO REMAIN CONDUITS AND BOXES WHERE EXISTING SUPPORT IS TO BE REMOVED. RE-ROUTE BRANCH CIRCUIT CONDUITS AND RELOCATE JUNCTION BOXES AS REQUIRED TO FACILITATE INSTALLATION OF NEW EQUIPMENT AND SYSTEMS IN CEILING SPACES.
- REMOVE ALL CONDUIT AND WIRE BACK TO THE SOURCE OR NEAREST UPSTREAM DEVICE REMAINING IN
- MAINTAIN ELECTRICAL SERVICE TO ALL LIGHTING FIXTURES, DEVICES AND EQUIPMENT THAT ARE TO REMAIN. EXTEND CONDUIT AND WIRE AS REQUIRED WHERE DEMOLITION WORK AFFECTS ELECTRICAL SERVICE TO DOWNSTREAM LOADS THAT ARE TO REMAIN.
- DISPOSE OF ALL MATERIALS OFF SITE AND INCLUDE ALL COSTS FOR DISPOSAL IN BID. ALL MATERIALS SHALL BE DISPOSED OF IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL REGULATIONS, INCLUDING TCLP TESTING, PROPER DISPOSAL AND/OR RECYCLING OF FLUORESCENT LAMPS.
- PROVIDE BLANK COVER PLATES WHERE SWITCHES AND DEVICES ARE REMOVED BUT EXISTING WALLS
- RING OUT AND TAG ALL CIRCUITS AFFECTED BY THIS ALTERATION AT BOTH ENDS. MARK ALL UNUSED CIRCUIT BREAKERS "SPARE".
- PROVIDE UPDATED TYPED-IN DIRECTORIES FOR ALL PANELS AFFECTED BY THIS ALTERATION.
- VERIFY ALL UNDERGROUND AND IN SLAB UTILITY LOCATIONS PRIOR TO SAW-CUTTING OR PENETRATING ANY FLOOR SLAB.
- COORDINATE ANY SHUT DOWN OF EXISTING SERVICES AND EQUIPMENT THAT ARE REMAINING IN USE WITH THE OWNER'S REPRESENTATIVE. WHERE EXISTING BUILDING SERVICE IS REQUIRED TO BE SHUT DOWN, INCLUDE ALL ASSOCIATED OVERTIME COSTS TO PERFORM THIS WORK DURING WEEKENDS AND EVENINGS INCLUDE ALL COSTS FOR PROVIDING TEMPORARY POWER WHERE SHUT DOWNS MUST OCCUR FOR PERIODS LONGER THAN THESE HOURS. COORDINATE ELECTRICAL SHUT DOWNS WITH THE OWNER 72 HOURS PRIOR TO SHUT DOWN.

DEMOLITION KEY NOTES:


- SALVAGE FOR RELOCATION. EXISTING BRANCH CIRCUIT TO REMAIN.
- SALVAGE FOR RELOCATION. REMOVE CONTROL WIRING UP TO CEILING SPACE.
- C SALVAGE FOR RELOCATION. EXISTING LIGHTING BRANCH CIRCUIT TO REMAIN.



STATE OF MICHIGAN
DEPARTMENT OF TECHNOLO DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE CONTRACT NO. 171CODHHS7255 Y22003





WTAARCH.COM

COPYRIGHT © 2023

WTAARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

PROJECT TITLE


491/20167.SDW - PHASE 500:


CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN


SALINE, MICHIGAN


FIRST FLOOR ELECTRICAL **DEMOLITION PLAN**

SHEET NUMBER PROJECT NUMBER Peter Basso Associates Inc CONSULTING ENGINEERS 5145 Livernois, Suite 100 Troy, Michigan 48098-3276 Tel: 248-879-5666 Fax: 248-879-0007 PROJECT DATE
SEPTEMBER 6, 2023 ED1.01 CHECKED BY www.PeterBassoAssociates.com PBA Project No.: 2021-0402 TLC









BASEMENT FLOOR POWER PLAN - UNIT H SCALE: 1" - 20'



TO ARCHITECTURAL DRAWINGS FOR CEILING TYPES.

- 1. THESE DRAWINGS REPRESENT THE GENERAL EXTENT AND ARRANGEMENT OF SYSTEMS. COORDINATE EXACT EQUIPMENT LOCATIONS, ELEVATIONS, AND FINAL CONNECTION REQUIREMENTS. PROVIDE EACH SYSTEM COMPLETE, INCLUDING ALL NECESSARY COMPONENTS, FITTINGS AND OFFSETS.
- 2. INSTALL SYSTEMS SUCH THAT REQUIRED CLEARANCE AND SERVICE ACCESS SPACE IS PROVIDED AROUND ALL MECHANICAL AND ELECTRICAL EQUIPMENT, AND AROUND ANY COMPONENTS WHICH REQUIRE SERVICE ACCESS.
- 3. COORDINATE AND PROVIDE ACCESS DOORS WITHIN INACCESSIBLE CEILING, SHAFT, AND CHASE AREAS FOR ALL COMPONENTS WHICH REQUIRE SERVICE ACCESS. REFER
- 4. PROVIDE SUPPLEMENTARY STEEL AS REQUIRED FOR THE PROPER SUPPORT OF ALL SYSTEMS.
- 5. TRANSFORMER SECONDARY CONDUCTORS SHALL BE SIZED IN ACCORDANCE WITH TRANSFORMER CIRCUIT SIZING SCHEDULE SHOWN ON "ELECTRICAL STANDARD SCHEDULES DRAWING" UNLESS OTHERWISE NOTED.
- 6. MOTOR CIRCUIT PROTECTION SHALL BE SIZED IN ACCORDANCE WITH MOTOR CIRCUIT SIZING SCHEDULES SHOWN ON "ELECTRICAL STANDARD SCHEDULES DRAWING" UNLESS OTHERWISE NOTED.
- 7. COORDINATE THE MOUNTING HEIGHTS OF DEVICES WITH ARCHITECTURAL ELEVATIONS AND THE TRADES INSTALLING THE WORK.
- 8. REFER TO MECHANICAL SCHEDULE SHEETS FOR ELECTRICAL REQUIREMENTS FOR MECHANICAL EQUIPMENT. PROVIDE ALL CONNECTIONS, STARTERS, DISCONNECTS, ETC. AS REQUIRED BY SCHEDULES AND WHERE NOTED ELSEWHERE. VERIFY REQUIREMENTS OF ALL MECHANICAL EQUIPMENT WITH SHOP DRAWINGS SUBMITTALS. NOTIFY ENGINEER OF ANY CONFLICTS BETWEEN EQUIPMENT SUBMITTALS AND ELECTRICAL DRAWINGS. WHERE CIRCUIT SIZES ARE SHOWN ON THE ELECTRICAL DRAWINGS THAT DIFFER FROM WHAT IS INDICATED ON THE MECHANICAL SCHEDULES, PROVIDE THE CIRCUIT OF HIGHER AMPACITY.
- 9. REFER TO TEMPERATURE CONTROLS SHEETS FOR REQUIRED FIRE ALARM CONTROL MODULES, DUCT SMOKE DETECTORS, AND MOTOR CONTROLLERS. PROVIDE ALL ACCESSORIES INDICATED.
- 10. REFER TO LIGHTING CONTROL SCHEDULE FOR ROOM CONTROL AND EMERGENCY LIGHTING CIRCUIT CONTROL REQUIREMENTS. DESIGNATION FOR ROOM IS INDICATED AS A LETTERED OVAL SYMBOL.
- 11. ALL FIRE ALARM DEVICES SHALL BE COMPATIBLE WITH EXISTING SIMPLEX GRINNEL 4120 FIRE ALARM SYSTEMS. PROVIDE NECESSARY COMPONENTS, MODULES, ETC. AS REQUIRED FOR A FULLY FUNCTIONAL SYSTEM. RE—TEST AND CERTIFY EXISTING FIRE ALARM SYSTEM AT COMPLETION OF PROJECT.
- 12. PROVIDE TAMPER RESISTANT COVER PLATE KENALL WPP SERIES OR EQUAL WHERE PATIENTS WILL HAVE ACCESS TO DEVICES.
- 13. REFER TO SECURITY/TELECOMMUNICATION DRAWINGS FOR FINAL DEVICE LOCATIONS AND RACEWAY REQUIREMENTS. COORDINATE WITH SECURITY REQUIREMENTS WITH INSTALLING TRADES.
- 14. COORDINATE ELECTRICAL REQUIREMENTS DEVICE LOCATIONS AND MOUNTING HEIGHTS WITH KITCHEN EQUIPMENT DRAWINGS, SHOP DRAWINGS AND KITCHEN EQUIPMENT INSTALLER.

CONSTRUCTION KEY NOTES:

- 1. PROVIDE (2) 120V 20A DEDICATED BRANCH CIRCUITS FROM SPARE CIRCUIT BREAKERS IN (E)CRLOEB FOR NEW IT RACK IN SECURITY ELECTRONICS E024.
- 2. EXISTING LINE VOLTAGE MASTER CLOCK HEAD-END. EXTEND CIRCUITING TO NEW

1	OWNER REVIEW	08/02/23
NO.	REVISION	DATE



STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOG DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION
DESIGN AND CONSTRUCTION DIVISION
ADAM LACH, RA, DIRECTOR DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

CONTRACT NO.

Y22003

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255



| WTA A RCHITECTS |

100 S Jefferson Ave, Suite 601

Saginaw, Michigan 48607 989 752 8107

WTAARCH.COM

COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

TCL

BASEMENT FLOOR POWER PLAN - UNIT H

Peter Basso Associates Inc CONSULTING ENGINEERS 5145 Livernois, Suite 100 Troy, Michigan 48098-3276 Tel: 248-879-5666 Fax: 248-879-0007 www.PeterBassoAssociates.com PBA Project No.: 2021-0402

ELECTRICAL


These documents are approved


subject to field inspection and the

conditions of approval.

for compliance with the STATE OF MICHIGAN ELECTRICAL CODE

SHEET NUMBER PROJECT NUMBER PROJECT DATE E3.00 AUGUST 23, 2023 CHECKED BY






ELECTRICAL GENERAL NOTES:

- THESE DRAWINGS REPRESENT THE GENERAL EXTENT AND ARRANGEMENT OF SYSTEMS. COORDINATE EXACT EQUIPMENT LOCATIONS, ELEVATIONS, AND FINAL CONNECTION REQUIREMENTS. PROVIDE EACH SYSTEM COMPLETE, INCLUDING ALL NECESSARY
- INSTALL SYSTEMS SUCH THAT REQUIRED CLEARANCE AND SERVICE ACCESS SPACE IS PROVIDED AROUND ALL MECHANICAL AND ELECTRICAL EQUIPMENT, AND AROUND ANY
- COORDINATE AND PROVIDE ACCESS DOORS WITHIN INACCESSIBLE CEILING, SHAFT, AND CHASE AREAS FOR ALL COMPONENTS WHICH REQUIRE SERVICE ACCESS. REFER TO
- PROVIDE SUPPLEMENTARY STEEL AS REQUIRED FOR THE PROPER SUPPORT OF ALL
- TRANSFORMER SECONDARY CONDUCTORS SHALL BE SIZED IN ACCORDANCE WITH TRANSFORMER CIRCUIT SIZING SCHEDULE SHOWN ON "ELECTRICAL STANDARD
- MOTOR CIRCUIT PROTECTION SHALL BE SIZED IN ACCORDANCE WITH MOTOR CIRCUIT SIZING SCHEDULES SHOWN ON "ELECTRICAL STANDARD SCHEDULES DRAWING" UNLESS
- COORDINATE THE MOUNTING HEIGHTS OF DEVICES WITH ARCHITECTURAL ELEVATIONS
- MECHANICAL EQUIPMENT. PROVIDE ALL CONNECTIONS, STARTERS, DISCONNECTS, ETC. AS REQUIRED BY SCHEDULES AND WHERE NOTED ELSEWHERE. VERIFY REQUIREMENTS OF ALL MECHANICAL EQUIPMENT WITH SHOP DRAWINGS SUBMITTALS. NOTIFY ENGINEER OF ANY CONFLICTS BETWEEN EQUIPMENT SUBMITTALS AND ELECTRICAL DRAWINGS. WHERE CIRCUIT SIZES ARE SHOWN ON THE ELECTRICAL DRAWINGS THAT DIFFER FROM WHAT IS
- REFER TO TEMPERATURE CONTROLS SHEETS FOR REQUIRED FIRE ALARM CONTROL MODULES, DUCT SMOKE DETECTORS, AND MOTOR CONTROLLERS. PROVIDE ALL
- REFER TO LIGHTING CONTROL SCHEDULE FOR ROOM CONTROL AND EMERGENCY LIGHTING CIRCUIT CONTROL REQUIREMENTS. DESIGNATION FOR ROOM IS INDICATED AS A
- FIRE ALARM SYSTEM. PROVIDE NECESSARY COMPONENTS, MODULES, ETC. AS REQUIRED FOR A FULLY FUNCTIONAL SYSTEM. RE-TEST AND CERTIFY EXISTING FIRE ALARM SYSTEM
- PROVIDE TAMPER RESISTANT COVER PLATE KENALL WPP SERIES OR EQUAL WHERE
- REFER TO SECURITY/TELECOMMUNICATION DRAWINGS FOR FINAL DEVICE LOCATIONS AND RACEWAY REQUIREMENTS. COORDINATE WITH SECURITY REQUIREMENTS WITH
- COORDINATE ELECTRICAL REQUIREMENTS DEVICE LOCATIONS AND MOUNTING HEIGHTS WITH KITCHEN EQUIPMENT DRAWINGS, SHOP DRAWINGS AND KITCHEN EQUIPMENT

CONSTRUCTION KEY NOTES:


- COORDINATE FINAL LOCATION OF TV WITH ARCHITECTURAL DRAWINGS AND TRADES PRIOR
- PROVIDE SINGLE GANG JUNCTION BOX AT 14'-0" ADJACENT TO EXTERIOR MOUNTED CAMERA. PROVIDE SEAL TIGHT CONDUIT AND ASSOCIATED FITTINGS/SEALS FROM EXTERIOR BOX TO CAMERA HOUSING. COORDINATE FINAL MOUNTING LOCATION WITH CAMERA INSTALLER AND DRAWINGS. PROVIDE 1-1/4" CONDUIT FROM SINGLE GANG



STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE CONTRACT NO. Y22003 171CODHHS7255



KEY PLAN NOT TO SCALE WTAARCH.COM

WTAARCHITECTS

COPYRIGHT © 2023

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

FIRST FLOOR AUXILIARY

SYSTEMS PLAN - UNIT H SHEET NUMBER


PROJECT NUMBER 2021094 PROJECT DATE E4.01 SEPTEMBER 6, 2023

5145 Livernois, Suite 100 Troy, Michigan 48098-3276 Tel: 248-879-5666 Fax: 248-879-0007 www.PeterBassoAssociates.com

Peter Basso Associates Inc

CONSULTING ENGINEERS

CHECKED BY PBA Project No.: 2021-0402 TLC




ELECTRICAL GENERAL NOTES:

- 1 THESE DRAWINGS REPRESENT THE GENERAL EXTENT AND ARRANGEMENT OF SYSTEMS. COORDINATE EXACT EQUIPMENT LOCATIONS, ELEVATIONS, AND FINAL CONNECTION REQUIREMENTS. PROVIDE EACH SYSTEM COMPLETE, INCLUDING ALL NECESSARY COMPONENTS, FITTINGS AND OFFSETS.
- INSTALL SYSTEMS SUCH THAT REQUIRED CLEARANCE AND SERVICE ACCESS SPACE IS PROVIDED AROUND ALL MECHANICAL AND ELECTRICAL EQUIPMENT, AND AROUND ANY COMPONENTS WHICH REQUIRE SERVICE ACCESS.
- COORDINATE AND PROVIDE ACCESS DOORS WITHIN INACCESSIBLE CEILING, SHAFT, AND CHASE AREAS FOR ALL COMPONENTS WHICH REQUIRE SERVICE ACCESS. REFER TO
- ARCHITECTURAL DRAWINGS FOR CEILING TYPES. PROVIDE SUPPLEMENTARY STEEL AS REQUIRED FOR THE PROPER SUPPORT OF ALL
- TRANSFORMER SECONDARY CONDUCTORS SHALL BE SIZED IN ACCORDANCE WITH TRANSFORMER CIRCUIT SIZING SCHEDULE SHOWN ON "ELECTRICAL STANDARD
- SCHEDULES DRAWING" UNLESS OTHERWISE NOTED. MOTOR CIRCUIT PROTECTION SHALL BE SIZED IN ACCORDANCE WITH MOTOR CIRCUIT
- 7 COORDINATE THE MOUNTING HEIGHTS OF DEVICES WITH ARCHITECTURAL ELEVATIONS AND THE TRADES INSTALLING THE WORK.
- 8 REFER TO MECHANICAL SCHEDULE SHEETS FOR ELECTRICAL REQUIREMENTS FOR MECHANICAL EQUIPMENT. PROVIDE ALL CONNECTIONS, STARTERS, DISCONNECTS, ETC. AS REQUIRED BY SCHEDULES AND WHERE NOTED ELSEWHERE. VERIFY REQUIREMENTS OF ALL MECHANICAL EQUIPMENT WITH SHOP DRAWINGS SUBMITTALS. NOTIFY ENGINEER OF ANY CONFLICTS BETWEEN EQUIPMENT SUBMITTALS AND ELECTRICAL DRAWINGS. WHERE CIRCUIT SIZES ARE SHOWN ON THE ELECTRICAL DRAWINGS THAT DIFFER FROM WHAT IS
- 9 REFER TO TEMPERATURE CONTROLS SHEETS FOR REQUIRED FIRE ALARM CONTROL MODULES, DUCT SMOKE DETECTORS, AND MOTOR CONTROLLERS. PROVIDE ALL ACCESSORIES INDICATED.
- 10 REFER TO LIGHTING CONTROL SCHEDULE FOR ROOM CONTROL AND EMERGENCY LIGHTING CIRCUIT CONTROL REQUIREMENTS. DESIGNATION FOR ROOM IS INDICATED AS A LETTERED OVAL SYMBOL.
- 11 ALL FIRE ALARM DEVICES SHALL BE COMPATIBLE WITH EXISTING SIMPLEX GRINNEL 4120 FIRE ALARM SYSTEM. PROVIDE NECESSARY COMPONENTS, MODULES, ETC. AS REQUIRED FOR A FULLY FUNCTIONAL SYSTEM. RE-TEST AND CERTIFY EXISTING FIRE ALARM SYSTEM AT COMPLETION OF PROJECT.
- 12 PROVIDE TAMPER RESISTANT COVER PLATE KENALL WPP SERIES OR EQUAL WHERE PATIENTS WILL HAVE ACCESS TO DEVICES.
- 13 REFER TO SECURITY/TELECOMMUNICATION DRAWINGS FOR FINAL DEVICE LOCATIONS AND RACEWAY REQUIREMENTS. COORDINATE WITH SECURITY REQUIREMENTS WITH
- 14 COORDINATE ELECTRICAL REQUIREMENTS DEVICE LOCATIONS AND MOUNTING HEIGHTS WITH KITCHEN EQUIPMENT DRAWINGS, SHOP DRAWINGS AND KITCHEN EQUIPMENT

CONSTRUCTION KEY NOTES:


- INSTALL SALVAGED EQUIPMENT ON NEW ROOF. EXTEND EXISTING BRANCH CIRCUITS AS
- COORDINATE FINAL LOCATION OF TV WITH ARCHITECTURAL DRAWINGS AND TRADES PRIOR TO ROUGH IN.
- 3 UP TO SECOND FLOOR ELECTRICAL ROOM E203. CORE EXISTING FLOOR.
- 4 CORE EXISTING WALL.
- 5 ROUTE IN CEILING SPACE OF GYM. ROUTE ALONG SIDE NEW MECHANICAL PIPING. COORIDINATE FINAL ROUTING WITH MECHANICAL TRADES.
- 6 COORDINATE GROUND ROD PLACEMENT WITH EXISTING UTILITIES PRIOR TO DRIVING THEM
- 7 20'-0" #4/0 BARE COPPER CONDUCTOR FOR CONCRETE-ENCASED ELECTRODE IN FOUNDATION ENCASED BY AT LEASET 2" OF CONCRETE.
- 8 PROVIDE LIGHTNING PROTECTION FOR WHOLE BUILDING ADDITION. LIGHTNING PROTECTION SYSTEM SHALL BE UL LISTED MASTER LABEL. REFER TO SPECIFICATIONS FOR SYSTEM REQUIREMENTS.
- 9 TIE INTO THE EXISTING LIGHTNING PROTECTION ON EXISTING BUILDING AS REQUIRED.
- LINE VOLTAGE CLOCK STANDARD ELECTRIC TIME FARADAY 2364 OR OTHER CLOCK COMPATABLE WITH EXISTING SYSTEM. EXTEND WIRING FROM EXISTING CLOCK HEAD END SYSTEM AS REQUIRED.



STATE OF MICHIGAN
DEPARTMENT OF TECHNOLO DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255



CONTRACT NO.

Y22003



WTA A RCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023

SHEET NUMBER

E4.04

WTAARCH.COM

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

ELECTRICAL ROOF PLAN

PROJECT NUMBER PROJECT DATE SEPTEMBER 6, 2023

CHECKED BY

TLC

Pa Peter Basso Associates Inc CONSULTING ENGINEERS 5145 Livernois, Suite 100 Troy, Michigan 48098-3276 Tel: 248-879-5666 Fax: 248-879-0007 www.PeterBassoAssociates.com PBA Project No.: 2021-0402

ELECTRICAL

These documents are approved

for compliance with the STATE OF MICHIGAN ELECTRICAL CODE

subject to field inspection and the

conditions of approval.

TO POWER

ELECTRICAL These documents are approved for compliance with the TATE OF MICHIGAN ELECTRICAL CODE subject to field inspection and the conditions of approval.

DIAGRAM GENERAL NOTES:

NECESSARY COMPONENTS, FITTINGS AND OFFSETS.

1. THESE DRAWINGS REPRESENT THE GENERAL EXTENT AND ARRANGEMENT OF SYSTEMS. COORDINATE EXACT EQUIPMENT LOCATIONS, ELEVATIONS, AND FINAL CONNECTION REQUIREMENTS. PROVIDE EACH SYSTEM COMPLETE, INCLUDING ALL

2. FEEDER AND BRANCH CIRCUIT CONDUCTORS SHALL BE SIZED IN ACCORDANCE WITH

Peter Basso Associates Ind CONSULTING ENGINEERS 5145 Livernois, Suite 100 Troy, Michigan 48098-3276 Tel: 248-879-5666 Fax: 248-879-0007 www.PeterBassoAssociates.com PBA Project No.: 2021-0402

PROJECT TITLE 491/20167.SDW - PHASE 500: CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN SALINE, MICHIGAN ONE LINE DIAGRAM - NEW WORK

TLC

100 S Jefferson Ave, Suite 601

Saginaw, Michigan 48607

PROJECT NUMBER SHEET NUMBER PROJECT DATE E5.01 AUGUST 23, 2023 CHECKED BY

OWNER REVIEW

REVISION

ADAM LACH, RA, DIRECTOR

FILE NO.

491/20167.SDW

171CODHHS7255

FUNDING CODE

DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION

CONTRACT NO.


WTAARCH.COM

COPYRIGHT © 2023

Y22003

| WTA ARCHITECTS |


DATE




								PAN	IELBC	ARD	KP-2						
	LOAD TYPE	DESCRIP ⁻	ΓΙΟΝ		CB TYPE	СВ	,	Ą	Е	3	(0	СВ	CB TYPE	DESCRIPTION	LOAD TYPE	
1		SPARE				20	0	0					20		SPARE		2
3		SPARE				20			0	0			20		SPARE		4
5		SPARE				20					0	0	20		SPARE		6
7		SPARE				20	0	0					20		SPARE		8
9	R	RECEPTS	; H123,H125			20			1080	0			20		SPARE		10
11	R		; H124,H125,H126	6,H127		20					1080	1260	20		RECEPTS;H123,H127	R	12
13	R		; H123,H129			20	900	900					20		RECEPTS;H123	R	14
15	R	RECEPTS	;H123,H124			20			720	1272			20		KITCHEN COUNTERTOP	K	16
17	С	REFRIGE	RATOR;H112		GFCI	20					1200	1500	20		COFFEE;H112	NC	18
19	NC	MICROWA	AVE;H112			20	1500	1200					20		GARBAGE DISPOSAL;H112	NC	20
21		SPARE				20			0	0			20		SPARE		22
23		SPARE				20					0	0	20		SPARE		24
25		SPARE				20	0	1654					20	GFCI	1B:SERVING LINE - HOT/COLD FOOD) K	26
27	K	1BA: SER	VING LINE - H/C F	FOOD	GFCI	20			420	1654				0. 0.	COMBO	.`	28
29	K	1A·SFRVII	NG LINE - HOT FO	OOD	GFCI	20					1654	1654	20	GFCI	1A:SERVING LINE - HOT FOOD	K	30
31		17 1.021 17 11			0.0.		1654	1654						0. 0.		.`	32
33	R	ROOF,ME	CH/ELEC ROOM	RECEPTS		20			1080	0			20		SPARE		34
35		SPARE				20					0	0	20		SPARE		36
37		SPARE				20	0	0					20		SPARE		38
39		SPARE				20			0	0			20		SPARE		40
41		SPARE				20					0	0	20		SPARE		42
								61	62:			347					
							Q	βA	Ø	iΒ	Q	oc.					
•	PANEL	BOARD INI	FORMATION	BRANCH LOAD	H CIRCUIT CO	NNECT	<u>ED</u>				ID CALCU OR LOAD	<u>JLATED</u>			DER AND RCURRENT NOTES		
	VOLTA	GE:	208Y/120V	CONTIN	UOUS LOAD (C):	1	200		100	% 1200			125% 1500)		
	BUS AI	MPACITY:	100A	- ELECTR	IC HEAT (E)		0			100	% 0			125% 0			
	MAIN T	YPE:	MLO	NON-CO	NTINUOUS L	OAD (NO	C): 4	200		100	% 4200			100% 4200)		
		JM A.I.C.:	10,000	_	N LOAD (K):			1613.6			% 8129.5	2		100% 8129			
	MOUN		SURFACE	_	BASE LOAD	(P).	_	020			% 7020			100% 7020			
	WOON	ilivo.	OON ACE	_			_								<u>, </u>		
					DEMAND LO	AD (N).	_				% 0			100% 0			
					IG LOAD (L):					100	% 0			125% 0			
					NAL TRACK L		_							100% 0			
					S, HIGHEST L): _0			125	% 0			100% 0			
	PANEL	BOARD LO	CATION	MOTOR	S, REMAINING	}	0			100	% 0			100 % 0			
				NOTE: D	EMAND AND	SIZING	_		то	TAL (kVA	A): 20.55						
					IATION IS CAL					TOTAL	57.04		TO	OTAL 57.8	7		

R R R R R R R R R R R R R R R R R R R	DESCRIPTION RECEPTS; H119,H131,EX RECEPTS; H131,H120 RECEPTS; H122,EXT SPARE SPARE SOUTH OVERHEAD DOOL UH-8H; H124 UH-10H; H201 CUH-6H; H121 CUH-4H: H131 SPARE SPARE CUH-11H; H119 SPARE SPARE SPARE SPARE SPARE SPARE SPARE	 R; H120	CB 20 20 20 20 20 15 15 15 20 20 20 15	1260 0 528	A 1260 0 528	1080 0	1080	360	0	CB 20 20 20 20 20	CB TYPE	DESCRIPTION RECEPTS; H131,H132,H133,EXT RECEPTS; H107,H130,H131,EXT SPARE SPARE NORTH OVERHEAD DOOR;H120	LOAD TYPE R R
R R R	RECEPTS; H131,H120 RECEPTS; H131,H120 RECEPTS; H122,EXT SPARE SPARE SOUTH OVERHEAD DOO! UH-8H; H124 UH-10H; H201 CUH-6H; H121 CUH-4H: H131 SPARE SPARE CUH-11H; H119 SPARE SPARE SPARE SPARE SPARE	 R; H120	20 20 20 20 20 15 15 15 15 20	0 528	0 528	0				20 20 20		RECEPTS; H107,H130,H131,EXT SPARE SPARE	R
R	RECEPTS; H122,EXT SPARE SPARE SOUTH OVERHEAD DOO! UH-8H; H124 UH-10H; H201 CUH-6H; H121 CUH-4H: H131 SPARE SPARE CUH-11H; H119 SPARE SPARE SPARE SPARE SPARE SPARE	 R; H120	20 20 20 20 15 15 15 15 20	528	528	0				20 20		SPARE SPARE	
	SPARE SPARE SOUTH OVERHEAD DOO! UH-8H; H124 UH-10H; H201 CUH-6H; H121 CUH-4H: H131 SPARE SPARE CUH-11H; H119 SPARE SPARE SPARE SPARE SPARE SPARE	 R; H120	20 20 15 15 15 15 20 20	528	528		600	600	1000				
	SPARE SOUTH OVERHEAD DOO UH-8H; H124 UH-10H; H201 CUH-6H; H121 CUH-4H: H131 SPARE SPARE CUH-11H; H119 SPARE SPARE SPARE SPARE SPARE SPARE	 R; H120	20 20 15 15 15 15 20 20	528	528		600	600	4000				
M M M M M M M M M M M M M M M M M M M	SOUTH OVERHEAD DOO! UH-8H; H124 UH-10H; H201 CUH-6H; H121 CUH-4H: H131 SPARE SPARE CUH-11H; H119 SPARE SPARE SPARE SPARE SPARE SPARE	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	20 15 15 15 15 20 20					600	4000				
B M B M C M C M C C C C C C	UH-8H; H124 UH-10H; H201 CUH-6H; H121 CUH-4H: H131 SPARE SPARE CUH-11H; H119 SPARE SPARE SPARE SPARE	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	15 15 15 15 20 20			528			1000	20		FIRE ALARM NAC; H201	C
5 M 7 M 9 M 5 M 7 9 11 33 7 9 11	UH-10H; H201 CUH-6H; H121 CUH-4H: H131 SPARE SPARE CUH-11H; H119 SPARE SPARE SPARE SPARE		15 15 15 20 20			528				15		UH-9H; H201	M
7 M 9 M 5 M 7 9 11 33 7 9 11	CUH-6H; H121 CUH-4H: H131 SPARE SPARE CUH-11H; H119 SPARE SPARE SPARE SPARE		15 15 20 20	528	500		528			15		CUH-5H; H120	M
M 5 M 6 1 3 7 9 1 1 PANEL	CUH-4H: H131 SPARE SPARE CUH-11H; H119 SPARE SPARE SPARE		15 20 20	528	500		323	528	528	15		CUH-3H; H132	M
5 M 7 9 11 5 7 9 11 PANELI	SPARE CUH-11H; H119 SPARE SPARE SPARE		20 20	020	528				0_0	15		EF-6H: ROOF	M
	SPARE CUH-11H; H119 SPARE SPARE SPARE		20		323	0	528			15		EF-7H: ROOF	M
5 M 7 9 1 3 7 9 1	CUH-11H; H119 SPARE SPARE SPARE					-		0	528	15		EF-8H: ROOF	M
7 9 1 3 7 9 1 7 9 1	SPARE SPARE SPARE			528	0					20		SPARE	
9 11 33	SPARE SPARE		20			0	0			20		SPARE	
1 3 5 7 9 1 PANELI	SPARE		20			-		0	0	20		SPARE	
3 5 7 9 1			20	0	0				-	20		SPARE	
5 7 9 1 PANELI			20			0	0			20		SPARE	
7 9 11 PANELI	SPARE		20			-		0	0	20		SPARE	
PANEL	SPARE		20	0	0					20		SPARE	
PANELI	SPARE		20			0	0			20		SPARE	
	SPARE		20					0	0	20		SPARE	
		I		51	160	43	44	35	⊥ 544				
			ı	Q	ðΑ	Ø	ίΒ	Q)C	1			
VOLTA	BOARD INFORMATION	BRANCH CIRCUIT C LOAD	ONNECT	<u>ED</u>			DEMANI FACTO	CALCU R LOAD	<u>JLATED</u>			DER AND RCURRENT NOTES	
	AGE: 208Y/120V	CONTINUOUS LOAD	(C):	1	000		1009	6 1000			125% 1250		
BUS AN	MPACITY: 100A	— ELECTRIC HEAT (E)		0)		1009	6 O			125% 0		
MAIN T	TYPE: MLO	NON-CONTINUOUS	I OAD (NO	C): C)		1009	6 O			100% 0		
	UM A.I.C.: 10,000	KITCHEN LOAD (K):						0			100% 0		
MOUNT) (D):	_	5040		1000	6 5040			100% 5		
MOON	TING. SURFACE	RECEPT BASE LOAI		_								<u>'</u>	
		RECEPT DEMAND L	` ,	0				6 0			100% 0		
		LIGHTING LOAD (L):		_0)		1009	6 <u>0</u>			125% 0		
		ADDITIONAL TRACK	LIGHTIN	G							100% 0		
		MOTORS, HIGHEST	LOAD (M): _6	00		125 9	⁶ 750			100% 750		
<u>PANELI</u>		MOTORS, REMAININ	IG	6	3408		100 9	6408			100 % 6408		
	BOARD LOCATION		SIZING	_		тс	TAL (kVA	: 13.2					
	BOARD LOCATION	NOTE: DEMAND ANI	ALCULAT	ED			TOTAL.			T			

SPARE 3 SPARE 5 SPARE	 	CB 20 20 20 20 20	1924	A 280		В	(0	СВ	CB TYPE	DESCRIPTION	LOAD TYPE	
SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE		20 20 20		280	0					00	DECORMITION		-1
SPARE SPARE SPARE SPARE 3 SPARE 5 SPARE		20 20	0		_				20		EXTERIOR BUILDING MOUNTED	L	Ť
SPARE SPARE SPARE SPARE SPARE SPARE		20	0		0	368			20		LIGHTING STAIR H121	L	T
SPARE SPARE SPARE SPARE SPARE			0				0	0	20		SPARE		T
SPARE 3 SPARE 5 SPARE		20		0					20		SPARE		T
SPARE SPARE		20			0	0			20		SPARE		T
SPARE		20					0	0	20		SPARE		Ī
		20	0	0					20		SPARE		T
SPARE		20			0	0			20		SPARE		T
		20					0	0	20		SPARE		T
SPARE		20	0	0					20		SPARE		
SPARE		20			0	0			20		SPARE		T
3 SPARE		20					0	0	20		SPARE		1
SPARE		20	0	0					20		SPARE		1
7 SPARE		20			0	0			20		SPARE		
9 SPARE		20					0	0	20		SPARE		Ī
1 SPARE		20	0	0					20		SPARE		Ī
3 SPARE		20			0	0			20		SPARE		Ī
5 SPARE		20					0	0	20		SPARE		Ī
7 SPARE		20	0	0					20		SPARE		T
9 SPARE		20			0	0			20		SPARE		1
1 SPARE		20					0	0	20		SPARE		T
			22	204	3	68	()					
			Q	ĎΑ	Q	ØВ	Ø	iC					
PANELBOARD INFORMATION	BRANCH CIRCUIT CO LOAD	NNECT	ED			DEMAN FACTO	ID CALCU OR LOAD	ILATED			DER AND RCURRENT NOTES		
VOLTAGE: 480Y/277V	CONTINUOUS LOAD ((C):	0)		100	% 0			125% 0			
BUS AMPACITY: 60A	ELECTRIC HEAT (E)	,	0)		100	% O		-	125% 0			
MAIN TYPE: MLO	NON-CONTINUOUS LO	ΩΔD (NI	_				% 0		-	100% 0			
		OAD (IV	_			100			=	100% 0			
	KITCHEN LOAD (K):	(5)	0			400	0		-				
MOUNTING: SURFACE	RECEPT BASE LOAD		0				% 0		=	100% 0			
	RECEPT DEMAND LO	AD (R):	_				% 0		-	100% 0			
	LIGHTING LOAD (L):		2	2571.6		100	% 2571.6		_	125% 3214	.5		
	ADDITIONAL TRACK L	IGHTIN	IG							100% 0			
	MOTORS, HIGHEST L	OAD (M	1): 0	1		125	% 0			100% 0			
PANELBOARD LOCATION	MOTORS, REMAINING	3	0	ı		100	% 0			100 % 0			
	NOTE: DEMAND AND	SIZING	_			OTAL (kVA	A): 2.57		-				
	INFORMATION IS CAL						3.09		Т(OTAL 3.87			



								ANELE		D LQ	1 1 -1 12	-0 1			T		
#	LOAD	DESCRIP	ESCRIPTION		CB TYPE	CB 20	A		В		C		CB 20	CB TYPE	DESCRIPTION 91: WALK-IN PRODUCE COOLER	LOAD TYPE	
1	K	90: WALK-IN MEAT COOLER		R			1200 1200				Ĭ					K	
3	K		(-IN FREEZER			20	1200	1200	1200	192			15		90B: WALK-IN MEAT COOLER EVAP	K	4
5	K		K-IN PRODUCE O	COOLER		15			1200	102	192	1487	10		SOB. WILLEN IN MEAN SOCIETY EVAN		6
7	K		IN LINE HEATER		GFPE	20	1800	1487			102	1101	20		92A: WALK-IN FREEZER EVAP	K	8
9		<u> </u>	K-IN MEAT COOL		<u> </u>				770	728					91A: WALK-IN PRODUCE COOLER	+	10
11	K		SING UNIT			15				. = -	770	728	15		CONDENSING UNIT	K	12
13		92A: WAI	K-IN FREEZER C	ONDENSING			2226	1920					20		B-11: H201	М	14
15	K	UNIT	in in including	ONDENGINO		30			2226	1920			20		B-12: H201	М	16
17	NC	AHU-21H	LIGHTS			20					1200	1200	20		AHU-22H LIGHTS	NC	18
19	_ R _	RECEPTS	5.:_H201			20	540	0					20		SPARE		20
21	C	AHU-21H	DDC CONTROL F	PANEL		20			1000	0			20		SPARE		22
23	С	AHU-22H	DDC CONTROL F	PANEL		20					1000	0	20		SPARE		24
25	C	HWHS D	OC CONTROL PAI	NEL	4 44 44 44 44	20	1000	0					20		SPARE		26
27		SPARE				20			0	0			20		SPARE		28
29		SPARE				20					0	0	20		SPARE		30
31		SPARE				20	0	0					20		SPARE		32
33		SPARE				20			0	0			20		SPARE		34
35		SPARE				20					0	0	20		SPARE		36
37		SPARE				20	0	0					20		SPARE		38
39		SPARE				20			0	0			20		SPARE		40
41		SPARE				20					0	0	20		SPARE		42
							11:	373	80	35	65	577					
						Q	ðΑ	Ø	ίΒ	Q	iC						
PANELBOARD INFORMATION BRANCH CIRCUIT CONNELOAD						NNECT	<u>ED</u>			DEMAND CALCULATED FACTOR LOAD			<u>FEEDER AND</u> <u>OVERCURRENT</u>				
VOLTAGE: 208Y/120V C			CONTINU	CONTINUOUS LOAD (C):			3000		100% 3000			125% 3750					
BUS AMPACITY: 60A		= ELECTRIC	ELECTRIC HEAT (E)			0		100% 0			125% 0						
MAIN TYPE: 60A MCB NO			- NON-CON	-CONTINUOUS LOAD (NC):			2400		100% 2400			100% 2400)			
			_	EN LOAD (K):			16204.8		65.00% 10533.12			100% 10533.12					
MOUNTING: SURFACE RECEPT RECEPT LIGHTING			RECEPT BASE LOAD (R):			_	540 0		100% 540 50% 0			100% 540		<u> </u>			
			_	RECEPT DEMAND LOAD (R):									100% 0				
				LIGHTING LOAD (L):			_	0		100% 0			125% 0				
			NAL TRACK LIGHTING					- <u> </u>			100% 0						
				ORS, HIGHEST LOAD (M):			1920		125 % 2400			100% 2400					
NOTE: D			DCATION .	MOTORS, REMAINING				1920		100 % 1920				100 % 1920	<u> </u>		
			EMAND AND SIZING ATION IS CALCULATED			TC	TOTAL (kVA): 20.79										
				INFORMA	TION IS CAL	.CULA I	ED			ΤΩΤΔΙ	57.72		T	OTAL 59.8	n		



FUNDING CODE CONTRACT NO. 171CODHHS7255 Y22003



Saginaw, Michigan 48607 989 752 8107

491/20167.SDW

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE

SALINE, MICHIGAN

KITCHEN

PANEL SCHEDULES

PROJECT NUMBER 2021094 PROJECT DATE SEPTEMBER 6, 2023

CHECKED BY

Checker

SHEET NUMBER E5.02

COPYRIGHT © 2023

Peter Basso Associates Inc CONSULTING ENGINEERS 5145 Livernois, Suite 100 Troy, Michigan 48098-3276 Tel: 248-879-5666 Fax: 248-879-0007 www.PeterBassoAssociates.com PBA Project No.: 2021-0402


FIRST FLOOR ELECTRICAL ENLARGED KITCHEN PLAN

ELECTRICAL GENERAL NOTES:

- THESE DRAWINGS REPRESENT THE GENERAL EXTENT AND ARRANGEMENT OF SYSTEMS. COORDINATE EXACT EQUIPMENT LOCATIONS, ELEVATIONS, AND FINAL CONNECTION REQUIREMENTS. PROVIDE EACH SYSTEM COMPLETE, INCLUDING ALL NECESSARY COMPONENTS, FITTINGS AND OFFSETS.
- INSTALL SYSTEMS SUCH THAT REQUIRED CLEARANCE AND SERVICE ACCESS SPACE IS PROVIDED AROUND ALL MECHANICAL AND ELECTRICAL EQUIPMENT, AND AROUND ANY COMPONENTS WHICH REQUIRE SERVICE ACCESS.
- COORDINATE AND PROVIDE ACCESS DOORS WITHIN INACCESSIBLE CEILING, SHAFT, AND CHASE AREAS FOR ALL COMPONENTS WHICH REQUIRE SERVICE ACCESS. REFER TO ARCHITECTURAL DRAWINGS FOR CEILING TYPES.
- 4 PROVIDE SUPPLEMENTARY STEEL AS REQUIRED FOR THE PROPER SUPPORT OF ALL SYSTEMS.
- TRANSFORMER SECONDARY CONDUCTORS SHALL BE SIZED IN ACCORDANCE WITH TRANSFORMER CIRCUIT SIZING SCHEDULE SHOWN ON "ELECTRICAL STANDARD SCHEDULES DRAWING" UNLESS OTHERWISE NOTED.
- MOTOR CIRCUIT PROTECTION SHALL BE SIZED IN ACCORDANCE WITH MOTOR CIRCUIT SIZING SCHEDULES SHOWN ON "ELECTRICAL STANDARD SCHEDULES DRAWING" UNLESS OTHERWISE NOTED.
- COORDINATE THE MOUNTING HEIGHTS OF DEVICES WITH ARCHITECTURAL ELEVATIONS AND THE TRADES INSTALLING THE
- REFER TO MECHANICAL SCHEDULE SHEETS FOR ELECTRICAL REQUIREMENTS FOR MECHANICAL EQUIPMENT. PROVIDE ALL CONNECTIONS, STARTERS, DISCONNECTS, ETC. AS REQUIRED BY SCHEDULES AND WHERE NOTED ELSEWHERE. VERIFY REQUIREMENTS OF ALL MECHANICAL EQUIPMENT WITH SHOP DRAWINGS SUBMITTALS. NOTIFY ENGINEER OF ANY CONFLICTS BETWEEN EQUIPMENT SUBMITTALS AND ELECTRICAL DRAWINGS. WHERE CIRCUIT SIZES ARE SHOWN ON THE ELECTRICAL DRAWINGS THAT DIFFER FROM WHAT IS INDICATED ON THE MECHANICAL SCHEDULES, PROVIDE THE CIRCUIT OF HIGHER AMPACITY.
- REFER TO TEMPERATURE CONTROLS SHEETS FOR REQUIRED FIRE ALARM CONTROL MODULES, DUCT SMOKE DETECTORS, AND MOTOR CONTROLLERS. PROVIDE ALL ACCESSORIES INDICATED.
- REFER TO LIGHTING CONTROL SCHEDULE FOR ROOM CONTROL AND EMERGENCY LIGHTING CIRCUIT CONTROL REQUIREMENTS. DESIGNATION FOR ROOM IS INDICATED AS A LETTERED OVAL SYMBOL.
- 11 ALL FIRE ALARM DEVICES SHALL BE COMPATIBLE WITH EXISTING SIMPLEX GRINNEL 4120 FIRE ALARM SYSTEM. PROVIDE NECESSARY COMPONENTS, MODULES, ETC. AS REQUIRED FOR A FULLY FUNCTIONAL SYSTEM. RE-TEST AND CERTIFY EXISTING FIRE ALARM SYSTEM AT COMPLETION OF PROJECT.
- 12 PROVIDE TAMPER RESISTANT COVER PLATE KENALL WPP SERIES OR EQUAL WHERE PATIENTS WILL HAVE ACCESS TO
- REFER TO SECURITY/TELECOMMUNICATION DRAWINGS FOR FINAL DEVICE LOCATIONS AND RACEWAY REQUIREMENTS. COORDINATE WITH SECURITY REQUIREMENTS WITH INSTALLING TRADES.
- 14 COORDINATE ELECTRICAL REQUIREMENTS DEVICE LOCATIONS AND MOUNTING HEIGHTS WITH KITCHEN EQUIPMENT DRAWINGS, SHOP DRAWINGS AND KITCHEN EQUIPMENT INSTALLER.

CONSTRUCTION KEY NOTES:


- 1 PROVIDE TOGGLE SWITCH LOCK GUARD FOR BOILER DISCONNECT LOCKING MEANS.
- 2 PROVIDE INTERWIRE TO CONTROL PANEL. COORDINATE WITH FOOD SERVICE INSTALLER AND INSTALLATION INSTRUCTIONS.
- 3 COORDINATE FINAL LOCATION OF TV WITH ARCHITECTURAL DRAWINGS AND TRADES PRIOR TO ROUGH IN.
- 4 INSTALL BOTTOM OF LIGHT FIXTURE AT 8'-0" AFF.
- ROUTE BRANCH CIRCUIT IN FLOOR AND STUB UP TO FINAL LOCATION. COORDINATE FINAL LOCATION WITH FOOD SERVICE DRAWINGS AND TRADES.
- MATCH ON-OFF TIMES WITH EXISTING SITE LIGHTING. COORDINATE EXACT TIMES WITH OWNER. CONNECT PHOTO CELL CONTROL TO EXISTING MAIN BUILDING PHOTO CELL WIRING/CONTROL.
- 7 4" HOUSEKEEPING PAD.
- LINE VOLTAGE CLOCK STANDARD ELECTRIC TIME FARADAY 2364 OR OTHER CLOCK COMPATABLE WITH EXISTING SYSTEM. EXTEND WIRING FROM EXISTING CLOCK HEAD END SYSTEM AS REQUIRED.



STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255



CONTRACT NO.

Y22003



WTAARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607

COPYRIGHT © 2023

WTAARCH.COM

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

ELECTRICAL ENLARGED PLAN

SHEET NUMBER PROJECT NUMBER PROJECT DATE E6.01 SEPTEMBER 6, 2023


CHECKED BY

TLC

ELECTRICAL These documents are approved for compliance with the TATE OF MICHIGAN ELECTRICAL CODE subject to field inspection and the conditions of approval.



THE FOLLOWING DIMENSION EQUALS ONE INCH WHEN PRINTED TO SCALE.






ELECTRICAL GENERAL NOTES:

- THESE DRAWINGS REPRESENT THE GENERAL EXTENT AND ARRANGEMENT OF SYSTEMS. COORDINATE EXACT EQUIPMENT LOCATIONS, ELEVATIONS, AND FINAL CONNECTION REQUIREMENTS. PROVIDE EACH SYSTEM COMPLETE, INCLUDING ALL NECESSARY COMPONENTS, FITTINGS AND OFFSETS.
- 2 INSTALL SYSTEMS SUCH THAT REQUIRED CLEARANCE AND SERVICE ACCESS SPACE IS PROVIDED AROUND ALL MECHANICAL AND ELECTRICAL EQUIPMENT, AND AROUND ANY COMPONENTS WHICH REQUIRE SERVICE ACCESS.
- 3 COORDINATE AND PROVIDE ACCESS DOORS WITHIN INACCESSIBLE CEILING, SHAFT, AND CHASE AREAS FOR ALL COMPONENTS WHICH REQUIRE SERVICE ACCESS. REFER TO ARCHITECTURAL DRAWINGS FOR CEILING TYPES.
- 4 PROVIDE SUPPLEMENTARY STEEL AS REQUIRED FOR THE PROPER SUPPORT OF ALL SYSTEMS.
- 5 TRANSFORMER SECONDARY CONDUCTORS SHALL BE SIZED IN ACCORDANCE WITH TRANSFORMER CIRCUIT SIZING SCHEDULE SHOWN ON "ELECTRICAL STANDARD SCHEDULES DRAWING" UNLESS OTHERWISE NOTED.
- 6 MOTOR CIRCUIT PROTECTION SHALL BE SIZED IN ACCORDANCE WITH MOTOR CIRCUIT SIZING SCHEDULES SHOWN ON "ELECTRICAL STANDARD SCHEDULES DRAWING" UNLESS OTHERWISE NOTED.
- 7 COORDINATE THE MOUNTING HEIGHTS OF DEVICES WITH ARCHITECTURAL ELEVATIONS AND THE TRADES INSTALLING THE
- REFER TO MECHANICAL SCHEDULE SHEETS FOR ELECTRICAL REQUIREMENTS FOR MECHANICAL EQUIPMENT. PROVIDE ALL CONNECTIONS, STARTERS, DISCONNECTS, ETC. AS REQUIRED BY SCHEDULES AND WHERE NOTED ELSEWHERE. VERIFY REQUIREMENTS OF ALL MECHANICAL EQUIPMENT WITH SHOP DRAWINGS SUBMITTALS. NOTIFY ENGINEER OF ANY CONFLICTS BETWEEN EQUIPMENT SUBMITTALS AND ELECTRICAL DRAWINGS. WHERE CIRCUIT SIZES ARE SHOWN ON THE ELECTRICAL DRAWINGS THAT DIFFER FROM WHAT IS INDICATED ON THE MECHANICAL SCHEDULES, PROVIDE THE CIRCUIT OF HIGHER AMPACITY.
- 9 REFER TO TEMPERATURE CONTROLS SHEETS FOR REQUIRED FIRE ALARM CONTROL MODULES, DUCT SMOKE DETECTORS, AND MOTOR CONTROLLERS. PROVIDE ALL ACCESSORIES INDICATED.
- 10 REFER TO LIGHTING CONTROL SCHEDULE FOR ROOM CONTROL AND EMERGENCY LIGHTING CIRCUIT CONTROL REQUIREMENTS. DESIGNATION FOR ROOM IS INDICATED AS A LETTERED OVAL SYMBOL.
- ALL FIRE ALARM DEVICES SHALL BE COMPATIBLE WITH EXISTING SIMPLEX GRINNEL 4120 FIRE ALARM SYSTEM. PROVIDE NECESSARY COMPONENTS, MODULES, ETC. AS REQUIRED FOR A FULLY FUNCTIONAL SYSTEM. RE-TEST AND CERTIFY EXISTING FIRE ALARM SYSTEM AT COMPLETION OF PROJECT.
- 12 PROVIDE TAMPER RESISTANT COVER PLATE KENALL WPP SERIES OR EQUAL WHERE PATIENTS WILL HAVE ACCESS TO
- 13 REFER TO SECURITY/TELECOMMUNICATION DRAWINGS FOR FINAL DEVICE LOCATIONS AND RACEWAY REQUIREMENTS. COORDINATE WITH SECURITY REQUIREMENTS WITH INSTALLING TRADES.
- 14 COORDINATE ELECTRICAL REQUIREMENTS DEVICE LOCATIONS AND MOUNTING HEIGHTS WITH KITCHEN EQUIPMENT DRAWINGS, SHOP DRAWINGS AND KITCHEN EQUIPMENT INSTALLER.

CONSTRUCTION KEY NOTES:

1 PROVIDE TOGGLE SWITCH LOCK GUARD FOR BOILER DISCONNECT LOCKING MEANS.

- 2 PROVIDE INTERWIRE TO CONTROL PANEL. COORDINATE WITH FOOD SERVICE INSTALLER AND INSTALLATION INSTRUCTIONS.
- 3 COORDINATE FINAL LOCATION OF TV WITH ARCHITECTURAL DRAWINGS AND TRADES PRIOR TO ROUGH IN.
- 4 INSTALL BOTTOM OF LIGHT FIXTURE AT 8'-0" AFF.
- 5 ROUTE BRANCH CIRCUIT IN FLOOR AND STUB UP TO FINAL LOCATION. COORDINATE FINAL LOCATION WITH FOOD SERVICE DRAWINGS AND TRADES.
- 6 MATCH ON-OFF TIMES WITH EXISTING SITE LIGHTING. COORDINATE EXACT TIMES WITH OWNER. CONNECT PHOTO CELL CONTROL TO EXISTING MAIN BUILDING PHOTO CELL WIRING/CONTROL.
- 7 4" HOUSEKEEPING PAD.
- LINE VOLTAGE CLOCK STANDARD ELECTRIC TIME FARADAY 2364 OR OTHER CLOCK COMPATABLE WITH EXISTING SYSTEM. EXTEND WIRING FROM EXISTING CLOCK HEAD END SYSTEM AS REQUIRED.







100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607

COPYRIGHT © 2023

PROJECT TITLE

989 752 8107

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

ELECTRICAL ENLARGED PLAN

PROJECT NUMBER
2021094

PROJECT DATE
SEPTEMBER 6, 2023

SHEET NUMBER

SHEET NUMBER


5 2021094

CHECKED BY

TLC

Peter Basso Associates Inc CONSULTING ENGINEERS 5145 Livernois, Suite 100 Troy, Michigan 48098-3276 Tel: 248-879-5666 Fax: 248-879-0007 www.PeterBassoAssociates.com PBA Project No.: 2021-0402


LIGHTING CONTACTOR WITH TIME CLOCK CONTROL AND BCELTS WIRING DIAGRAM NO SCALE



TELECOMMUNICATION OUTLET DETAIL NO SCALE

1. IF CEILING IN ROOM IS NOT ACCESSIBLE, ROUTE CONDUIT THROUGH NEAREST ACCESSIBLE CEILING TO CABLE/WIRE BASKET TRAY.


NOTES:




AUTOMATIC LOAD CONTROL RELAY FOR 0-10V DIMMING

NO SCALE


1. BASIS OF DESIGN IS LVS CONTROLS EPC-2-D. REFER TO SPECIFICATIONS FOR APPROVED MANUFACTURERS. ADJUST WIRING AS NECESSARY FOR OTHER APPROVED MANUFACTURERS. 2. PROVIDE ONE AUTOMATIC LOAD CONTROL RELAY PER SWITCHING CIRCUIT.



RECESSED LIGHTING FIXTURE **INSTALLATION DETAIL** NO SCALE



TYPICAL MOUNTING DETAIL FOR CHAIN **HUNG LIGHTING FIXTURES**



BRANCH CIRCUIT EMERGENCY LIGHTING TRANSFER SWITCH FOR 0-10V DIMMING NO SCALE

1. BASIS OF DESIGN IS LVS CONTROLS EPC-D-F-ATS. REFER TO SPECIFICATIONS FOR APPROVED MANUFACTURERS. ADJUST WIRING AS NECESSARY FOR OTHER APPROVED MANUFACTURERS. 2. PROVIDE ONE BRANCH CIRCUIT EMERGENCY LIGHTING TRANSFER SWITCH PER SWITCHING CIRCUIT.

	INTERIOR LIGHTING CONTROL SCHEDULE																		
PLAN REFERENCE	ROOM TYPE		LOCAL CONTROL		CONTROL ON / OFF	SENSOR TYPE	TURN ON LIGHTING	BI-LEVEL CONTROL		DAYLIG		NO DETE PARTIAL (NOTE	L OFF	NO DETECTION FULL OFF	TIME-CLOCK SCHEDULE	RECEPTACLE CONTROL	EMERGENCY LIGHTING CIRCUIT	CONTACT FOR	NOTES
INCI ENLINOE		SWITCH TYPE	SWITCH CONTROL	SCENE CONTROL	ON / ON		10 %	CONTINUE	SIDE LIGHT	TOP LIGHT	MAINTAIN FC LEVEL	REDUCE TO (%)	AT(MIN)	(MIN)	JOHEDOLE	CONTINUE	CONTROL	CONTROL	
A	FOOD PREPARATION AREA	LOW VOLTAGE	ON-OFF-DIM	NA	MANUAL ON / MANUAL OFF	DUAL TECHNOLOGY	FULL 100%	CONTINUOUS DIM	NA	NA	NA	NA	NA	NA	NA	NA	ALCR	NA	
В	STORAGE ROOM (≥50 SQFT AND ≤ 1000 SQFT)	LINE VOLTAGE	ON-OFF	NA	MANUAL ON / SENSOR OFF	DUAL TECHNOLOGY	FULL 100%	NA	NA	NA	NA	NA	NA	20	NA	NA	ALCR	YES	
С	CORRIDOR (IN A HOSPITAL)	LINE VOLTAGE	ON-OFF (KEYED)	NA	SENSOR ON / SENSOR OFF	ULTRASONIC	FULL 100%	NA	NA	NA	NA	NA	NA	20	NA	NA	ALCR	NA	NEW CORRIDOR SHALL BE CONTROLLED SIMILARLY TO EXISTING CORRIDORS
D	DINING AREA (IN CAFETERIA OR FAST FOOD DINING)	LOW VOLTAGE	ON-OFF-DIM	NA	MANUAL ON / SENSOR OFF	DUAL TECHNOLOGY	FULL 100%	CONTINUOUS DIM	YES	NA		NA	NA	20	NA	NA	ALCR	YES	
E	OFFICE (ENCLOSED AND ≤ 250 SQFT)	LOW VOLTAGE	ON-OFF-DIM	NA	MANUAL ON / SENSOR OFF	DUAL TECHNOLOGY	FULL 100%	CONTINUOUS DIM	NA	NA	NA	NA	NA	20	NA	NA	NA	YES	
F	RESTROOM (ALL OTHER RESTROOMS)	LINE VOLTAGE	ON-OFF	NA	SENSOR ON / SENSOR OFF	ULTRASONIC	FULL 100%	NA	NA	NA	NA	NA	NA	20	NA	NA	ALCR	NA	
G	ELECTRICAL/MECHANICAL ROOM	LINE VOLTAGE	ON-OFF	NA	MANUAL ON / MANUAL OFF	NA	FULL 100%	NA	NA	NA	NA	NA	NA	NA	NA	NA	ALCR	NA	
Ħ	STAIRWELL	LINE VOLTAGE	ON-OFF (KEYED)	NA	SENSOR ON / SENSOR OFF	ULTRASONIC	FULL 100%	NA	NA	NA	NA	NA	NA	20	NA	NA	BCELTS	NA	
I	LOUNGE/BREAKROOM (ALL OTHER LOUNGES/BREAKROOMS)	LOW VOLTAGE	ON-OFF-DIM	NA	MANUAL ON / SENSOR OFF	DUAL TECHNOLOGY	FULL 100%	CONTINUOUS DIM	NA	NA	NA	NA	NA	20	NA	NA	NA	NA	
J	CORRIDOR (IN A HOSPITAL)	LINE VOLTAGE	ON-OFF (KEYED)	NA	SENSOR ON / SENSOR OFF	ULTRASONIC	FULL 100%	NA	NA	NA	NA	NA	NA	20	NA	NA	BCELTS	NA	NEW CORRIDOR SHALL BE CONTROLLED SIMILARLY TO EXISTING CORRIDORS

1. REFER TO PLANS FOR LOCATION OF LOCAL CONTROL.

2. REFER TO PLANS FOR SCENE CONTROL.


3. REFER TO PLANS FOR PRIMARY AND SECONDARY DAYLIGHT ZONES. 4. PROVIDE EMERGENCY LIGHTING CIRCUIT CONTROL (BCELTS OR ALCR) PER SWITCHING CIRCUIT AS REQUIRED. 5. CONTRACTOR SHALL PROVIDE FLOOR PLAN INDICATING SENSOR AND EQUIPMENT LOCATIONS OF CHOSEN CONTROL SYSTEM. 6. REFER TO LUMINAIRE SCHEDULE FOR FIXTURE CHARACTERISTICS.

7. LIGHTING SENSOR SHALL HAVE CONTACT FOR HVAC CONTROL WHEN A "YES" SELECTION IS MADE IN THE HVAC CONTROL COLUMN. 8. REFER TO TEMPERATURE CONTROL DRAWINGS AND DIAGRAMS FOR ADDITIONAL SENSOR REQUIREMENTS.

9. PROVIDE WIRING CONTROL DIAGRAM FOR APPLICABLE CONTROL SYSTEM(S). 10. PERCENTAGE LIGHT OUTPUT REDUCTION IS FOR ALL FIXTURES WITHIN THE DESIGNATED ROOM UNLESS OTHERWISE NOTED.

©Copyright 2017 by Peter Basso Associates, Inc

NA = NOT APPLICABLE



ROOM BASED LIGHTING CONTROL SYSTEM DIAGRAM WIRED - LOW VOLTAGE


GENERAL NOTES:

NO SCALE

- 1. REFER TO SPECIFICATIONS FOR ACCEPTED MANUFACTURERS. 2. PROVIDE QUANTITY OF ROOM BASED LIGHTING CONTROLLERS AS REQUIRED TO MEET FUNCTIONALITY INDICATED ON PLAN.
- 3. REFER TO MANUFACTURER'S INSTALLATION GUIDE FOR EXACT WIRING METHOD. WIRING METHOD AND CONFIGURATION TO BE PER MANUFACTURER'S RECOMMENDATIONS.
- 4. LOCATE SENSORS IN CENTER OF A FULL CEILING TILE, WHERE APPLICABLE. 5. MOUNTING LOCATION OF SENSORS PER MANUFACTURER'S RECOMMENDATION.
- 6. REFER TO INTERIOR LIGHTING CONTROL SCHEDULE FOR SYSTEM CONFIGURATIONS SETTINGS. SENSOR ADJUSTMENT: BEFORE MAKING ADJUSTMENTS, MAKE SURE ROOM FURNITURE IS INSTALLED, LIGHTING CIRCUITS ARE TURNED ON, AND THE HVAC SYSTEMS ARE IN THE ON POSITION. VAV SYSTEMS SHOULD BE SET TO THEIR HIGHEST AIRFLOW.

KEYED NOTES


- 1. GANG LIGHTING CONTROL DEVICES IN COMMON GANGED BOX. PROVIDE SAME SIZE GANG COVER PLATE FROM THE SAME MANUFACTURER AS THE LIGHTING CONTROL DEVICE AS REQUIRED.
- 2. LIGHTING CONTROL DEVICE(SWITCH). REFER TO LIGHTING CONTROL DEVICE BUTTON LAYOUT DETAIL FOR ENGRAVING REQUIREMENTS AND PLANS FOR LOCATIONS.
- 3. CEILING MOUNTED SENSOR. MANUFACTURE TO PROVIDE LAYOUT AND QUANTITIES FOR FULL COVERAGE OF SPACE.
- 4. REFER TO LIGHTING FIXTURE SCHEDULE. REFER TO PLANS FOR LAYOUT AND QUANTITIES. 5. CEILING MOUNTED PHOTOCELL (AS REQUIRED). REFER TO PLANS FOR PRIMARY AND SECONDARY ZONE CONTROL.
- 6. PROVIDE ONE AUTOMATIC LOAD CONTROL RELAY PER SWITCHING CIRCUIT WHERE EMERGENCY LIGHTING FROM A GENERATOR OR LIGHTING INVERTER IS INDICATED ON PLANS. REFER TO AUTOMATIC LIGHTING RELAY CONTROL DETAIL.
- 7. ROOM BASED LIGHTING CONTROLLER TO BE LOCATED IN ACCESSIBLE CEILING ADJACENT TO DOOR DIRECTLY ABOVE LIGHTING CONTROL DEVICE. IF ACCESSIBLE CEILING SPACE IS NOT ACCESSIBLE, AN ACCESS HATCH SHALL BE PROVIDED.



OCCUPANCY SENSOR WIRING DIAGRAM

NO SCALE NOTES:

- REFER TO SPECIFICATIONS FOR ACCEPTED MANUFACTURERS. PROVIDE POWER PACKS AND SLAVE PACKS AS REQUIRED FOR SWITCHING AS INDICATED ON
- PLAN. REVISE DETAIL AS REQUIRED BY MANUFACTURER. MOUNTING LOCATION PER MANUFACTURER'S RECOMMENDATION.
- 4. ADJUST SENSITIVITY LEVELS PER THE OWNER REQUIREMENTS. PROVIDE FACTORY SUPPORT FOR AIMING/ADJUSTING OF SENSORS.
- 6. PLACE CEILING MOUNTED OCCUPANCY SÉNSORS IN CENTER OF A FULL CEILING TILE, WHERE APPLICABLE.
- SENSOR ADJUSTMENT: BEFORE MAKING ADJUSTMENTS, MAKE SURE ROOM FURNITURE IS INSTALLED, LIGHTING CIRCUITS ARE TURNED ON, AND THE HVAC SYSTEMS ARE IN THE ON POSITION. VAV SYSTEMS SHOULD BE SET TO THEIR HIGHEST AIRFLOW. SET THE LOGIC CONFIGURATION DIP SWITCHES TO "EITHER". EITHER REQUIRES MOTION DETECTION BY ONLY ONE TECHNOLOGY. SET THE TIME DELAY PER OWNERS DIRECTION.



PANELBOARD FRONT COVER DETAIL

NO SCALE

ELECTRICAL


These documents are approved

for compliance with the STATE OF MICHIGAN ELECTRICAL CODE

subject to field inspection and the

conditions of approval.





STATE OF MICHIGAN
DEPARTMENT OF TECHNICI OF DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

> CONTRACT NO. **FUNDING CODE** 171CODHHS7255 Y22003



| WTA ARCHITECTS |

COPYRIGHT © 2023

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

PROJECT TITLE 491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

ELECTRICAL DETAILS AND DIAGRAMS

SHEET NUMBER ROJECT NUMBER PROJECT DATE AUGUST 23, 2023 CHECKED BY


TLC

E7.00

BUILDING GROUNDING

KEYED NOTES


- 1. METAL IN-GROUND SUPPORT STRUCTURE IN DIRECT CONTACT WITH EARTH VERTICALLY
- FOR A MINIMUM OF 10FT, WHERE AVAILABLE.
- 2. GROUNDING ELECTRODE CONDUCTOR, #4/0 COPPER. 3. GROUNDED CONDUCTOR (NEUTRAL), SEE ONE LINE DIAGRAM.
- 4. PHASE CONDUCTORS, GROUNDED CONDUCTOR (NEUTRAL), AND EQUIPMENT GROUNDING
- CONDUCTOR IN CONDUIT TO MAIN BUILDING. SEE ONE LINE DIAGRAM. 5. REFER TO DRY TYPE DISTRIBUTION TRANSFORMER GROUNDING ARRANGEMENT



DRY TYPE DISTRIBUTION TRANSFORMER **GROUNDING ARRANGEMENT**


KEYED NOTES

- 1. 480V, 3Ø PRIMARY CIRCUIT BREAKER BASED ON DRY TYPE DISTRIBUTION TRANSFORMER CIRCUIT SIZING SCHEDULE ON ELECTRICAL STANDARD SCHEDULI DRAWING UNLESS OTHERWISE NOTED.
- PRIMARY FEEDER BASED ON FEEDER AND BRANCH CIRCUIT SIZING TABLE ON ELECTRICAL STANDARD SCHEDULE DRAWING UNLESS OTHERWISE NOTED. GROUNDING ELECTRODE CONDUCTOR TO NEAREST GROUNDING ELECTRODE (i.e. BUILDING STEEL, METAL WATER PIPE, GROUND RING, OR GROUND BUS).
- SEE DRY TYPE DISTRIBUTION TRANSFORMER CIRCUIT SIZING SCHEDULE ON ELECTRICAL STANDARD SCHEDULE DRAWING FOR SIZE UNLESS OTHERWISE
- 4. 208Y/120V, 3ø, 4W SECONDARY FEEDER BASED ON DRY TYPE DISTRIBUTION TRANSFORMER CIRCUIT SIZING SCHEDULE ON ELECTRICAL STANDARD SCHEDULE DRAWING UNLESS OTHERWISE NOTED.
- 5. SUPPLY SIDE BONDING JUMPER. 6. SYSTEM BONDING JUMPER.
- GROUNDED CONDUCTOR (NEUTRAL). 8. NEUTRAL CONDUCTOR PROVIDED WITH EQUIPMENT.




DUCT TYPE DETECTOR INSTALLATION NO SCALE

1. PROVIDE SAMPLING TUBE LENGTH AS REQUIRED FOR WIDTH OF DUCT.



LIGHTING POLE BASE DETAIL NO SCALE

- 1. PROVIDE PRECAST CONCRETE BASE AS MANUFACTURED BY NORTHERN CONCRETE PIPE, INC. OR APPROVED EQUAL.
- CONCRETE REINFORCEMENTS SHALL BE BARE, ZINC GALVANIZED, OR ELECTRICALLY CONDUCTIVE COATED STEEL. BOND ALL CONCRETE REINFORCEMENTS AND ANCHOR BOLTS TOGETHER SO THAT SYSTEM IS ELECTRICALLY CONTINUOUS.




ANNUNCIATION

FIRE ALARM MATRIX

SYSTEM OUTPUTS

NOTIFICATION


FIRE SAFETY



KITCHEN FIRE PROTECTION WIRING DETAIL

NO SCALE

ELECTRICAL CONTRACTOR SHALL FIELD VERIFY VOLTAGE, AND TYPE (NORM. OPEN/CLOSED) CONTACT IN FIRE PROTECTION PANEL, AND PROVIDE CONTACTOR TO OPERATE ACCORDINGLY. EXHAUST FAN SHALL TURN ON UPON ACTIVATION OF ANSUL SYSTEM.



CABLE TRAY TO CONDUIT TRANSITION THROUGH RATED WALL

NO SCALE NOTES:

- 1. BOND TRAY TO CONDUIT WITH A #6 AWG COPPER GREEN INSULATED
- GROUND WIRE. 2. PROVIDE GROUNDING BUSHINGS ON CONDUIT SLEEVES AND BOND
- SLEEVES WITH #6 AWG COPPER GREEN INSULATED GROUND WIRE. 3. PROVIDE FIRE—STOPPING IN AND AROUND ALL CONDUITS MAINTAIN FIRE RATING OF PARTITION AND TO MAKE PENETRATION AIR TIGHT.

GROUNDING

ELECTRICAL These documents are approved for compliance with the TATE OF MICHIGAN ELECTRICAL CODE subject to field inspection and the conditions of approval.





PROJECT TITLE 491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

OWNER REVIEW

REVISION

DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET

CONTRACT NO.

Y22003

FACILITIES AND BUSINESS SERVICES ADMINISTRATION

DESIGN AND CONSTRUCTION DIVISION

STATE OF MICHIGAN

FILE NO.

491/20167.SDW

171CODHHS7255

FUNDING CODE

ADAM LACH, RA, DIRECTOR


08/02/23


DATE

SALINE, MICHIGAN


ELECTRICAL DETAILS AND DIAGRAMS

PROJECT NUMBER 2021094	SHEET NUMBER
PROJECT DATE AUGUST 23, 2023	E7.01
CHECKED BY	





ELECTRICAL GROUND BUS DETAIL



ACCESS

CONTROL

POWER

SUPPLY

DOOR HARDWARE DOUBLE DOOR CONNECTION DIAGRAM

NO SCALE **GENERAL NOTES:**

TO REMOTE MONITORING

TO FIRE ALARM

PANEL AS

REQUIRED —

STATION BY OTHERS.

AND CONDUIT AS

REQUIRED —

PROVIDE BACK BOXES

- REFER TO ELECTRICAL FLOOR PLANS FOR DOOR LOCATIONS. AS REQUIRED BY MANUFACTURER. COORDINATE EXACT REQUIREMENTS AND SCOPE OF WORK WITH OWNER AND ACCESS CONTROL
- CONTRACTOR 3. SOME DEVICES INDICATED MAY NOT APPLY. REFER TO DOOR HARDWARE AND DOOR SCHEDULE. COORDINATE ALL WORK WITH HARDWARE
- 4. ELECTRICAL CONTRACTOR SHALL PROVIDE INTERCONNECTION WITH FIRE ALARM PANEL TO RELEASE DOORS (I.E. ELECTROMAGNETIC LOCKS) UPON AN ALARM CONDITION, AS REQUIRED.

$\langle \# \rangle$ KEYED NOTES:

DATA CABLING TO

ACCESS CONTROL

CONTROL PANEL

BY OTHERS

- . ACCESS CONTROL CONTROL PANEL, BY OTHERS. 2. ACCESS CONTROL POWER SUPPLY, BY OTHERS. 3. ACCESS CONTROL STATION, BY OTHERS. (EXAMPLE DEVICES: CARD
- READER, KEYPAD, REQUEST TO EXIT PUSH PAD, MOTION DETECTOR, 4. DOOR MONITOR CONTACT SWITCH, BY OTHERS. 5. DOOR HOLDER, BY OTHERS. ELECTROMAGNETIC SWITCH MOUNTED
- ON/IN DOOR AND FRAME. [FOR DELAYED OPERATION] IN LIEU OF ELÉCTRIC STRIKE. 6. ELECTRIC STRIKE, PANIC HARDWARE, POWER TRANSFER, BY OTHERS.
- 8. DOOR OPERATOR, BY OTHERS. (EXAMPLE DEVICES: PUSH PAD, TOUCHLESS, ETC) 9. INTERCOM STATION, BY OTHERS.

DOOR OPERATOR ACTUATOR, BY OTHERS.

NO SCALE

TO REMOTE MONITORING

STATION BY OTHERS.

PROVIDE BACK BOXES

AND CONDUIT AS

REQUIRED —

PANEL AS

REQUIRED -

- REFER TO ELECTRICAL FLOOR PLANS FOR DOOR LOCATIONS. PROVIDE BACK BOXES, CONDUIT, 120 VOLT WIRING AND TERMINATIONS AS REQUIRED BY MANUFACTURER. COORDINATE EXACT REQUIREMENTS AND SCOPE OF WORK WITH OWNER AND ACCESS CONTROL
- 3. SOME DEVICES INDICATED MAY NOT APPLY. REFER TO DOOR HARDWARE AND DOOR SCHEDULE. COORDINATE ALL WORK WITH HARDWARE
- ALARM PANEL TO RELEASE DOORS (I.E. ELECTROMAGNETIC LOCKS)

CONTRACTOR. 4. ELECTRICAL CONTRACTOR SHALL PROVIDE INTERCONNECTION WITH FIRE

UPON AN ALARM CONDITION, AS REQUIRED.

KEYED NOTES:

DATA CABLING TO

ACCESS CONTROL

CONTROL PANEL

BY OTHERS

ACCESS

CONTROL

POWER

DOOR HARDWARE SINGLE DOOR CONNECTION DIAGRAM

ACCESS CONTROL CONTROL PANEL, BY OTHERS. 2. ACCESS CONTROL POWER SUPPLY, BY OTHERS. 3. ACCESS CONTROL STATION. BY OTHERS. (EXAMPLE DEVICES: CARD

120V [EMERGENCY] POWER

CONTROL CONTROL

4. DOOR MONITOR CONTACT SWITCH, BY OTHERS. 5. DOOR HOLDER, BY OTHERS. ELECTROMAGNETIC SWITCH MOUNTED ON/IN DOOR AND FRAME. [FOR DELAYED OPERATION] IN LIEU OF ELÉCTRIC STRIKE. 6. ELECTRIC STRIKE, PANIC HARDWARE, POWER TRANSFER, BY OTHERS.

READER, KEYPAD, REQUEST TO EXIT PUSH PAD, MOTION DETECTOR,

- DOOR OPERATOR ACTUATOR, BY OTHERS, 8. DOOR OPERATOR, BY OTHERS. (EXAMPLE DEVICES: PUSH PAD,
- TOUCHLESS, ETC) 9. INTERCOM STATIÓN, BY OTHERS.

	COMMUNICATION EQUIPMENT SCHEDULE					
MARK	DESCRIPTION	MANUFACTURER	PART NO.			
Α	TECHNOLOGY CABINET. MATCH EXISTING SIZE AND TYPE. WITH LOUVERED DOORS.C2 FRAME 40 RACK UNITS. EQUIP WITH CABLE LACING BARS. EQUIP WITH TOP TO CABINET AND ADJUSTABLE CABINET FEET	HAMMOND	C2 FRAME C2RR197031BK1 W/CDF-1970LBK1 DOORS			
В	POWER STRIP, RACK MOUNT	HAMMOND	15853H6B1			
С	SINGLE RACK UNIT PATCH CORD ORGANIZER (PCO-1) WITH HINGED COVER.	HUBBELL	HS13C			
D	PATCH PANEL-24 PORT, EQUIPPED WITH 8-PIN MODULAR JACKS TO MATCH THE CABLE COLOR AND CABLE TYPE BEING TERMINATED. PROVIDE ONE MODULAR JACK FOR EACH CABLE BEING TERMINATED. SEE SPEC AND DRAWINGS FOR COLORS. EQUIP WITH REAR CABLE ORGANIZER	HUBBELL	PANEL: HPJ24 ORGANIZER: ECMBR3			

AUDIO EQUIPMENT SCHEDULE					
MARK	DESCRIPTION	MANUFACTURER	PART NO.		
WA	AUDIO AMPLIFIER	QSC	SPA OR ISA SERIES		
WB	AUDIO LINE LEVEL DISTRIBUTION AMPLIFIER 1 IN, 2-OUT	RDL LABS	ST-DA3		
WC	VOLUME CONTROL	ATLAS	AT35		

	SPEAKER SCHEDULE	<u> </u>	
MARK	DESCRIPTION	MANUFACTURER	PART NO.
S ₁	PAGING SYSTEM SPEAKER FOR DROP CEILING INSTALLATION. EQUIP WITH WHITE GRILL AND MULTI TAPS. PROVIDE T-BAR AND BACKBOX	ATLAS IED	SD72WV
S ₂	PAGING SYSTEM SPEAKER. RECESSED IN DRYWALL CEILING. PROVIDE AND INSTALL BACKBOX INTO THE CEILING PRIOR TO DRYWALL. WIRE TO SPEAKERS PRIOR TO DRYWALL CEILING BEING INSTALLED.	ATLAS IED	SD72WV

	CAMERA EQUIPMENT SCHEDULE							
MARK	DESCRIPTION	MANUFACTURER	PART NO.	DROP CEILING	BUILDING EXTERIOR	BUILDING EXTERIOR CORNER		
CA	MULTI-HEAD CAMERA, EXTERIOR, 270 DEGREES CORNER MOUNT	BOSCH	NDM-7703		SBP-317HMW, SBP-390WMW2 SBP-300NBW	SBP-300KMW1 SBP-300NBW		
СВ	EXTERIOR 4K CAMERAS. ARM MOUNT ON WALL	BOSCH	NDE-8504-R					
cc	INDOOR AND OUTDOOR 360 FISHEYE SINGLE IMAGER 12 MEGAPIXEL	BOSCH	NDS-5704-F360LE	SHD-1600FPW	SBP-167HMW, SBP-300WMW1 SBP-300NBW	SBP-300KMW1 SBP-300NBW		
CD	INDOOR SHORT DISTANCE CAMERA. 2MP. DROP OR HARD CEILING	BOSCH	NDE-4502-A	SHD-1408FPW				
CE	INDOOR 5 MP DROP OR HARD CEILING OR WALL	BOSCH	NDE-5503-A	SHD-1408FPW				
CF	BOSCH NVR FOR CAMERA STORAGE AND PROCESSING	BOSCH	SEE SPECS					
CG	ETHERNET SWITCH FOR CAMERA SYSTEM	CISCO	9200 SERIES					

COMMUNICATION SYMBOL LEGEND						
SYMBOL	DESCRIPTION					
1	THIS SYMBOL WITH A NUMBER INSIDE REFERS TO KEYNOTES. REFER TO NOTES ON THE SHEET OR WITHIN THE DETAIL FOR ADDITIONAL INFORMATION					
А	EQUIPMENT SCHEDULE. THIS SYMBOL WITH LETTERS INSIDE REFERS EQUIPMENT SCHEDULES, SEE DETAILS AND EQUIPMENT SCHEDULES ON TC101, TC301, TC501 AND TC701.					
1	CABLE SCHEDULE. THIS SYMBOL WITH NUMBERS INSIDE REFERS EQUIPMENT SCHEDULES, SEE DETAILS AND EQUIPMENT SCHEDULES ON TC101, TC301, TC501 AND TC701.					
××××	DATA COMMUNICATIONS OUTLET CONNECTIVITY CODE. X IS A 1 THRU 99. SEE TC1XX SHEETS FOR SPECIFIC REQUIREMENTS. XXXX NOTES THAT THE CABLE IS FOR A SPECIFIC USE					
X 12: 08 12: 08	TWO SIDED DIGITAL CLOCK. SEE CONNECTIVITY CODE FOR CLOCK TYPE.					
× 12:08	SINGLE SIDED DIGITAL CLOCK. SEE CONNECTIVITY CODE FOR CLOCK TYPE.					
	NEW STUN FENCE. INSTALL NEW STUN FENCE WIRING AND DEVICES					
FENCE -	NEW SHAKER WIRE ON FENCE. INSTALL NEW SHAKER WIRE ON THE FENCE					
	TEMPORARY FEED OF STUN FENCE FROM STUN FENCE CABINET TO EXISTING FENCE					
xx	EXISTING SHAKER WIRE AND STUN FENCE. REMOVE FROM FENCE					

	AUDIO VIDEO SYMBOL LEGEND						
SYMBOL	DESCRIPTION						
××××	AUDIO/VIDEO COMMUNICATIONS OUTLET. REFER TO THE ASSOCIATED AV SYSTEM DETAIL FOR REQUIREMENTS. ZZ REFERS TO HEIGHT OF OUTLET. 18" UNLESS OTHER WISE NOTED.						
SEE TC3XX/X	AV SYSTEM DETAIL. REFER TO THIS SHEET AND DETAIL NUMBER FOR THE REQUIREMENTS OF THE AUDIO/VIDEO SYSTEM IN THIS ROOM						
⊚ zz X	SPEAKERS. SEE SPEAKER SCHEDULE ON TC301."X" REFERS TO SPEAKER TYPE. "ZZ" REFERS TO SPEAKER ZONE IF THIS IS A PAGING SPEAKER.						


	SECURITY SYMBOL LEGEND
SYMBOL	DESCRIPTION
(XX)	ACCESS CONTROL SYMBOL. "XX" IS LETTERS. SEE DETAILS ON TC5XX SHEETS FOR EQUIPMENT, CABLING AND RACEWAY DETAILS.
(XX)	ACCESS CONTROL SYMBOL FOR EXISTING DEVICES. "XX" IS LETTERS. SEE DETAILS ON TC5XX SHEETS. LEAVE DEVICES AND CONNECT TO NEW SYSTEM OR LEAVE AS CONNECTED TO EXISTING SYSTEM. SEE NOTES AND DETAILS
XXX	DOOR NUMBER
SEC.PNL	SECURITY PANEL. PROVIDE PANEL AND CONNECT AS SHOWN ON FLOORPLANS AND IN THE SPECIFICATIONS.
	SECURITY CAMERA. PROVIDE AND INSTALL A NEW SECURITY CAMERA. SEE DETAILS ON TC5XX SHEETS.
	SECURITY CAMERA WITH 180 DEGREE VIEWING. PROVIDE AND INSTALL A NEW SECURITY CAMERA. SEE DETAILS ON TC5XX SHEETS.
	SECURITY CAMERA WITH 360 DEGREE VIEWING, SINGLE-IMAGER. PROVIDE AND INSTALL A NEW SECURITY CAMERA. SEE DETAILS ON TC5XX SHEETS.
<u> </u>	SECURITY CAMERA WITH 270 OR 360 DEGREE VIEWING, MULTI-IMAGER. PROVIDE AND INSTALL A NEW SECURITY CAMERA. SEE DETAILS ON TC5XX SHEETS.
	SECURITY CAMERA. PTZ. SEE SPECIFICATIONS FOR CAMERA REQUIREMENTS AND MOUNTING.

	CABLE SCHEDULE						
MARK	DESCRIPTION	MANUFACTURER	PART NO.				
1	CAT-6 UTP CABLES. BLUE IN COLOR. SEE CONNECTIVITY CODES	MOHAWK	M58281				
2	CAT-6 UTP CABLES. GREEN IN COLOR. SEE CONNECTIVITY CODES	MOHAWK	M58286				
3	CAT-6 UTP CABLES. YELLOW IN COLOR. SEE CONNECTIVITY CODES	MOHAWK	M58283				
4	CAT-6 CABLE UNDERGROUND RATED	MOHAWK	M57622				
5	SHAKER FENCE CABLING	ISC	CONTRACTOR				
6	STUN FENCE FEEDER WIRE FROM ENERGIZER TO FENCE	CONTRACTOR	CONTRACTOR				
7	STUN FENCE CABLING ON FENCE	CONTRACTOR	CONTRACTOR				

	ACCESS CONTROL EQUIPMENT SCHEDULE					
MARI	DESCRIPTION	MANUFACTURER	PART NO.			
XA	INTERCOM AT DOOR-INTERIOR	HARDING	ICE-320-217-000			
ХВ	INTERCOM AT DOOR-EXTERIOR	HARDING	ICE-320-227-000			
xc	PLC WITH ETHERNET INTERFACE PROCESSOR	ALLEN BRADLEY	1769-L37ERM			
XD	POINT I/O ETHERNET ETHERNET ADAPTER	ALLEN BRADLEY	1769-AENTR			
XE	POINT I/O OUTPUT MODULE	ALLEN BRADLEY	1769-OB32			
XF	POINT I/O INPUT MODULE	ALLEN BRADLEY	1769-IQ32			
XG	POWER SUPPLY	EMERSON	SVL-1024100			
XH	DIN RAIL MOUNTED TERMINAL STRIPS. PROVIDE AS REQUIRED FOR CABLE TYPE AND CONNECTIVITY. MOUNT IN CABINET. PROVIDE SUPPORTS AND PLASTIC FINGER DUCT FOR ROUTING CABLE	CONTRACTOR	CONTRACTOR			
XJ	INTERCOM BOARD FOR CONNECTION OF AUDIO ON INTERCOMS	HARDING	QCB-120-1			
XK	INTERCOM BOARD FOR CONNECTION OF PUSH BUTTON ON INTERCOMS	HARDING	QCB-120-1			
XL	ETHERNET SWITCH FOR ACCESS CONTROL SYSTEM	CONTRACTOR	CONTRACTOR			
XM	INTERCOM CONTROLLER IP ATTACHED	HARDING	DCC-S100-3030- S100-00IP			

ACCESS CONTROL EQUIPMENT SCHEDULE						
MARK	DESCRIPTION	MANUFACTURER	PART NO.			
CA	ACCESS CONTROL SYSTEM, SOFTWARE AND ASSOCIATED/REQUIRED SERVERS	STANLEY	GATEKEEPER			
СВ	CARD READER SERIAL TO IP DEVICE. SERVES UP TO 16 CARD READERS	MOXA	5650-16			
СС	CARD READER. COMPATIBLE WITH STANLEY SYSTEM.	HID	5352AGN00			
CD						
CE						
CF						
CG						
СН						

ABBREVIATIONS			
ABBREV.	DESCRIPTION	ABBREV.	DESCRIPTION
2G	TWO-GANG BOX - PROVIDED BY EC	NIC	NOT IN CONTRACT
AC	ABOVE COUNTER — INSTALL BACKBOX SAME HEIGHT AS OTHER ELECTRICAL OUTLETS ABOVE THE COUNTER.	PBO	PROVIDED BY OTHERS
AFF	ABOVE FINISHED FLOOR	PCO-1	PATCH CORD ORGANIZER - 1 UNIT HIGH
AFG	ABOVE FINISHED GROUND	PCO-2	PATCH CORD ORGANIZER - 2 UNITS HIGH
AWG	AMERICAN WIRE GAUGE	PET	PROTECTED ENTRANCE TERMINAL
ЕМТ	EMT TYPE CONDUIT	QTY	QUANTITY
EC	ELECTRICAL CONTRACTOR		





FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE

CONTRACT NO. Y22003 171CODHHS7255

Commtech Design ROCKFORD, MICHIGAN 49341 WWW.COMMTECHDESIGN.COM



WTAARCH.COM

COPYRIGHT © 2023

WTA ARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

CHECKED BY BWE

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

SHEET TITLE CABLING LEGENDS, SCHEDULES & DETAILS

SHEET NUMBER PROJECT NUMBER 2021094 TC101 PROJECT DATE SEPTEMBER 6, 2023

AUDIO PAGING SYSTEM **EXPANSION DETAIL** ∖ TC101[']

INSTALL CABLES FROM SPEAKERS TO THE BASEMENT SECURITY ROOM. PROVIDE ONE CABLE FOR EACH ZONE AS DEPICTED.

 $\stackrel{\textstyle >}{3}$ install terminal strips for wire termination. Label each wire and each zone at the terminal strips,


INSTALL A VOLUME CONTROL IN A SINGLE-GANG BACKBOX ON THE WALL. LABEL FOR THE ZONE IT CONNECTS TO.

6 PROVIDE AN AMPLIFIER THAT DRIVES ALL SPEAKERS. WITH ADEQUATE AUDIO LEVEL.

PROVIDE AND INSTALL AN AUDIO SPLITTER FOR THE SYSTEM. SPLIT EXISTING SIGNAL.

5 TEST SYSTEM. LISTEN AND SET AUDIO LEVEL IN EACH ZONE.


KEYED NOTES:





NOTES:


1. THE SITE CURRENTLY HAS AN EXISTING PAGING AUDIO SYSTEM.
THIS SYSTEM SHALL BE EXPANDED TO SUPPORT NEW ZONES
AND SPEAKERS IN THE KITCHEN AREA.


- PROVIDE AN AUDIO SPLITTER AND SPLIT THE EXISTING SIGNAL PRIOR TO CONNECTION TO EXISTING AMPLIFIER
- 3. THE PAGING/BELL SYSTEM SHALL BE MOUNTED IN A CABINET IN THE COMM ROOM IN THE BASEMENT
- 4. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CABLES ASSOCIATED WITH THE CONNECTIVITY OF THE PAGING SYSTEM. ALL NEW CABLES SHALL BE PLENUM RATED
- 5. CONTRACTOR SHALL LABEL EACH PAGING SYSTEM SPEAKER CABLE. THE LABEL SHALL BE "ZONE XXX" WHERE XXX DESIGNATES THE EXTENSION THAT THE CABLE IS CONNECTED TO. CABLES SHALL BE LABELED AT EACH TERMINATION POINT & AT
- EACH INTERCONNECTION POINT. 6. PROVIDE INTERCONNECTION CABLES AS REQUIRED FOR ZONES AND POWER DISTRIBUTION TO THE SPEAKERS. CONTRACTOR SHALL VERIFY CONFIGURATION WITH ENGINEER PRIOR TO
- 7. INSTALL VOLUME CONTROLS FOR AUDIO LEVEL CONTROL OF ALL THREE ZONES BEING ADDED











MOUNT ACCESS CONTROL PANEL ON THE WALL OF THE BASEMENT SECURITY ROOM. ROUTE CABLING TO PLC CABINET AND CARD READERS FOR CONNECTIVITY

INTEGRATE ALL NEW EQUIPMENT AND DOORS AND CONTROLS TO THE EXISTING SYSTEM TO PROVIDE A SINGLE, COHESIVE INTERFACE AND DATABASE FOR THE

DATE REVISION

STATE OF MICHIGAN DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE 171CODHHS7255

Commtech Design

CONTRACT NO.

Y22003

WTAARCH.COM

ROCKFORD, MICHIGAN 49341 WWW.COMMTECHDESIGN.COM

WTA ARCHITECTS

COPYRIGHT © 2023

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607

989 752 8107

PROJECT TITLE

491/20167.SDW - PHASE 500:


CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN


SALINE, MICHIGAN


SECURITY ACCESS CONTROL DETAILS

PROJECT NUMBER SHEET NUMBER 2021094 PROJECT DATE TC106 SEPTEMBER 6, 2023 CHECKED BY BWE

DOOR HARDWARE & SECURITY EQUIPMENT CONNECTIVITY REQUIREMENTS √TC106








GENERAL TECH NOTES

- SECURITY CONTRACTOR SHALL INSTALL ANY CONDUITS & PASS-THRU'S REQUIRED FOR ROUTING CABLES AROUND THE BUILDING IN ADDITION TO THOSE SHOWN.
- CONTRACTOR SHALL COMPLETE A WALK-THRU PRIOR TO CONSTRUCTION & SHALL VERIFY ALL RACEWAYS &
- PATHWAYS. ALL CABLES SHALL BE SUPPORTED ABOVE THE DROP CEILING BY J-HOOKS. HOOKS SHALL BE LOCATED NO
- LESS THAN EVERY 5 FEET. WHERE A CAMERA IS MARKED AS SURFACE MOUNTED ON THE ONE-LINE, THAT CAMERA MAY BE MOUNTED TO THE CEILING OR WALL. PROVIDE A BACKBOX & RACEWAY.

KEYED TECH NOTES

- BACKPULL EXISTING SHAKER WIRE TO JUNCTION POINT OF NEW AN EXISTING FENCE. DURING CONSTRUCTION, CONFIGURE THE SHAKER WIRE SYSTEM TO END AN NEW/EXISTING FENCE JUNCTIONLOCATION.
- REMOVE THE EXISTING STUN FENCE FROM TOP OF EXISTING FENCE.
- ROUTE NEW STUN FENCE WIRES THRU
 UNDERGROUND CONDUITS THAT ARE SHOWN ON
 ELECTRICAL SITE PLAN.
- \langle 4 \rangle MOUNT CAMERA AT 12' AFG
- $\overline{5}$ MOUNT CAMERA AT 15' AFG
- TEMPORARILY INSTALL CABLES FROM STUN FENCE CABINET TO EXISTING FENCE TO MAINTAIN STUN FENCE DURING CONSTRUCTION. INSTALL FLEXIBLE CONDUIT AND ATTACH TO THE BUILDING. INSTALL HIGH ENOUGH TO AVOID VEHICLES AND NEW CONSTRUCTION



DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION

DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

FILE NO. 491/20167.SDW

FUNDING CODE

CONTRACT NO. Y22003 171CODHHS7255

STATE OF MICHIGAN

Commtech Design
6581 BELDING RD NE STE 101
ROCKFORD, MICHIGAN 49341
WWW.COMMTECHDESIGN.COM



WTAARCH.COM

WTA ARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500:


CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

TECHNOLOGY SITE PLAN

PROJECT NUMBER 2021094 SHEET NUMBER PROJECT DATE
SEPTEMBER 6, 2023 TC200

CHECKED BY
BWE



GENERAL TECH NOTES


- SECURITY CONTRACTOR SHALL INSTALL ANY CONDUITS & PASS-THRU'S REQUIRED FOR ROUTING CABLES AROUND THE BUILDING IN ADDITION TO THOSE SHOWN.
- 2. CONTRACTOR SHALL COMPLETE A WALK-THRU PRIOR TO CONSTRUCTION & SHALL VERIFY ALL RACEWAYS & PATHWAYS.
 - ALL CABLES SHALL BE SUPPORTED ABOVE THE DROP CEILING BY J-HOOKS. HOOKS SHALL BE LOCATED NO LESS THAN EVERY 5 FEET.
- 4. WHERE A CAMERA IS MARKED AS SURFACE MOUNTED ON THE ONE-LINE, THAT CAMERA MAY BE MOUNTED TO THE CEILING OR WALL. PROVIDE A BACKBOX &

KEYED TECH NOTES

- BACKPULL EXISTING SHAKER WIRE TO JUNCTION POINT OF NEW AN EXISTING FENCE. DURING CONSTRUCTION, CONFIGURE THE SHAKER WIRE SYSTEM TO END AN NEW/EXISTING FENCE JUNCTIONLOCATION.
- REMOVE THE EXISTING STUN FENCE FROM TOP OF EXISTING FENCE.
- ROUTE NEW STUN FENCE WIRES THRU UNDERGROUND CONDUITS THAT ARE SHOWN ON
- MOUNT CAMERA AT 12' AFG

ELECTRICAL SITE PLAN.


- 5 MOUNT CAMERA AT 15' AFG
- TEMPORARILY INSTALL CABLES FROM STUN FENCE CABINET TO EXISTING FENCE TO MAINTAIN STUN FENCE DURING CONSTRUCTION. INSTALL FLEXIBLE CONDUIT AND ATTACH TO THE BUILDING. INSTALL HIGH ENOUGH TO AVOID VEHICLES AND NEW CONSTRUCTION



STATE OF MICHIGAN
DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET
FACILITIES AND BUSINESS SERVICES ADMINISTRATION
DESIGN AND CONSTRUCTION DIVISION
ADAM LACH, RA, DIRECTOR

491/20167.SDW

FUNDING CODE 171CODHHS7255





WTAARCH.COM

COPYRIGHT © 2023

CONTRACT NO.

WTA A RCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

PROJECT TI

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN SALINE, MICHIGAN

FIRST FLOOR TECHNOLOGY PLAN


PROJECT NUMBER
2021094

PROJECT DATE
SEPTEMBER 6, 2023

SHEET NUMBER
TC201

SEPTEMBER 6, 2023

CHECKED BY
BWE





GENERAL TECH NOTES


- SECURITY CONTRACTOR SHALL INSTALL ANY CONDUITS & PASS-THRU'S REQUIRED FOR ROUTING CABLES AROUND THE BUILDING IN ADDITION TO
- THOSE SHOWN. CONTRACTOR SHALL COMPLETE A WALK-THRU PRIOR TO CONSTRUCTION & SHALL VERIFY ALL RACEWAYS &
- . ALL CABLES SHALL BE SUPPORTED ABOVE THE DROP CEILING BY J-HOOKS. HOOKS SHALL BE LOCATED NO LESS THAN EVERY 5 FEET.

PATHWAYS.

. WHERE A CAMERA IS MARKED AS SURFACE MOUNTED ON THE ONE-LINE, THAT CAMERA MAY BE MOUNTED TO THE CEILING OR WALL. PROVIDE A BACKBOX & RACEWAY.

KEYED TECH NOTES

- BACKPULL EXISTING SHAKER WIRE TO JUNCTION POINT OF NEW AN EXISTING FENCE. DURING CONSTRUCTION, CONFIGURE THE SHAKER WIRE SYSTEM TO END AN NEW/EXISTING FENCE JUNCTIONLOCATION.
- REMOVE THE EXISTING STUN FENCE FROM TOP OF EXISTING FENCE.
- ROUTE NEW STUN FENCE WIRES THRU UNDERGROUND CONDUITS THAT ARE SHOWN ON
- ELECTRICAL SITE PLAN. 4 MOUNT CAMERA AT 12' AFG
- 5 MOUNT CAMERA AT 15' AFG
- TEMPORARILY INSTALL CABLES FROM STUN FENCE CABINET TO EXISTING FENCE TO MAINTAIN STUN FENCE DURING CONSTRUCTION. INSTALL FLEXIBLE CONDUIT AND ATTACH TO THE BUILDING. INSTALL HIGH ENOUGH TO AVOID VEHICLES AND NEW CONSTRUCTION



DEPARTMENT OF TECHNOLOGY, MANAGEMENT AND BUDGET FACILITIES AND BUSINESS SERVICES ADMINISTRATION DESIGN AND CONSTRUCTION DIVISION ADAM LACH, RA, DIRECTOR

STATE OF MICHIGAN

FILE NO. 491/20167.SDW

FUNDING CODE

CONTRACT NO. 171CODHHS7255 Y22003





WTAARCH.COM

WTA ARCHITECTS

100 S Jefferson Ave, Suite 601 Saginaw, Michigan 48607 989 752 8107

COPYRIGHT © 2023

PROJECT TITLE

491/20167.SDW - PHASE 500:

CENTER FOR FORENSIC PSYCHIATRY - CREATE KITCHEN

SALINE, MICHIGAN

SHEET TITLE BASEMENT **TECHNOLOGY PLAN** AREA 100

PROJECT NUMBER 2021094

PROJECT DATE SEPTEMBER 6, 2023 TC201A

SHEET NUMBER

CHECKED BY BWE